

December 06, 2021

EXHIBIT A



SCOPE OF SERVICES

FOR

FINANCIAL PROJECT ID: 210230-2-32-20

SR 312 EXTENSION PROJECT FROM SR 207 TO SR 16

FDOT DISTRICT 2

ST. JOHNS

TABLE OF CONTENTS

1 PURPOSE 4

2 PROJECT DESCRIPTION..... 6

3 PROJECT COMMON AND PROJECT GENERAL TASKS (AS NEEDED) 21

4 ROADWAY ANALYSIS (AS NEEDED) 31

5 ROADWAY PLANS (AS NEEDED) 35

6a DRAINAGE ANALYSIS (AS NEEDED) 37

6b DRAINAGE PLANS (AS NEEDED) 41

7 UTILITIES (AS NEEDED)..... 41

8 ENVIRONMENTAL PERMITS and ENVIRONMENTAL CLEARANCES (AS NEEDED) 45

9 STRUCTURES - SUMMARY AND MISCELLANEOUS TASKS AND DRAWINGS (AS NEEDED) 52

10 STRUCTURES - BRIDGE DEVELOPMENT REPORT (AS NEEDED) 53

11 STRUCTURES - TEMPORARY BRIDGE (N/A)..... 55

12 STRUCTURES - SHORT SPAN CONCRETE BRIDGE (N/A)..... 55

13 STRUCTURES - MEDIUM SPAN CONCRETE BRIDGE (AS NEEDED)..... 55

14 STRUCTURES - STRUCTURAL STEEL BRIDGE (N/A)..... 58

15 STRUCTURES - SEGMENTAL CONCRETE BRIDGE (N/A)..... 58

16 STRUCTURES - MOVABLE SPAN (N/A) 58

17 STRUCTURES - RETAINING WALLS (AS NEEDED) 58

18 STRUCTURES – MISCELLANEOUS (AS NEEDED)..... 60

19 SIGNING AND PAVEMENT MARKING ANALYSIS (AS NEEDED) 62

20 SIGNING AND PAVEMENT MARKING PLANS (AS NEEDED) 64

21 SIGNALIZATION ANALYSIS (AS NEEDED) 64

22 SIGNALIZATION PLANS (AS NEEDED) 66

23 LIGHTING ANALYSIS (AS NEEDED)..... 67

24 LIGHTING PLANS (AS NEEDED)..... 69

25 LANDSCAPE ANALYSIS (N/A)..... 70

26 LANDSCAPE PLANS (N/A)..... 70

27 SURVEY (AS NEEDED)..... 70

28 PHOTOGRAMMETRY (N/A)..... 75

29 MAPPING (AS NEEDED)..... 75

30 TERRESTRIAL MOBILE LiDAR (N/A)..... 79
31 ARCHITECTURE DEVELOPMENT (N/A)..... 79
32 NOISE BARRIERS IMPACT DESIGN ASSESSMENT IN THE DESIGN PHASE (AS
NEEDED) 79
33 INTELLIGENT TRANSPORTATION SYSTEMS ANALYSIS (N/A) 83
34 INTELLIGENT TRANSPORTATION SYSTEMS PLANS (N/A)..... 83
35 GEOTECHNICAL (AS NEEDED)..... 83
36 3D MODELING (AS NEEDED)..... 93
37 PROJECT REQUIREMENTS..... 95
38 INVOICING LIMITS 96

SCOPE OF SERVICES FOR CONSULTING ENGINEERING SERVICES
HIGHWAY AND BRIDGE/STRUCTURAL DESIGN

This Exhibit forms an integral part of the agreement between the State of Florida Department of Transportation (hereinafter referred to as the DEPARTMENT or FDOT) and [*Consultant Name or leave blank until CONSULTANT is selected*] (hereinafter referred to as the CONSULTANT) relative to the transportation facility described as follows:

Financial Project ID: *210230-2-32-20*

Federal Aid Project No.: *To Be Assigned*

Roadway ID: *SR 312, Section 78003000 Begin MP 0.000 / End MP 4.07*

Project Description: *SR 312 Extension from SR 207 to SR 16 (St. Johns County)*

Bridge No(s).: *To Be Assigned for any New Bridges*

Railroad Crossing No.: *To Be Assigned for FEC RR Spur Line (Grade Separated Crossing)*

Context Classification: *N/A (Limited Access Corridor)*

1 PURPOSE

The purpose of this Exhibit is to describe the scope of work and the responsibilities of the CONSULTANT and the DEPARTMENT in connection with the design and preparation of a complete set of construction contract documents and incidental engineering services, as necessary, for improvements to the transportation facility described herein.

- Major work mix includes:
 - *0002 - NEW ROAD CONSTRUCTION*
- Major work groups include:
 - *3.3 – Controlled Access Highway Design*
- Minor work groups include:
 - *2.0 - PD&E Studies*
 - *4.1.1 – Miscellaneous Structures*
 - *4.1.2 – Minor Bridge Design*
 - *7.1 - Signing, Pavement Marking and Channelization*
 - *7.2 - Lighting*
 - *7.3 - Signalization*

- **8.2 - Design, Right of Way & Construction Surveying**
- **8.4 - Right of Way Mapping**
- **9.1 - Soil Exploration**

Known alternative contracting methods include: *N/A*

The general objective is for the CONSULTANT to prepare a set of contract documents including plans, specifications, supporting engineering analysis, calculations and other technical documents in accordance with FDOT policy, procedures and requirements. These Contract documents will be used by the contractor to build the project and test the project components. These Contract documents will be used by the DEPARTMENT or its Construction Engineering Inspection (CEI) representatives for inspection and final acceptance of the project. The CONSULTANT shall follow a systems engineering process to ensure that all required project components are included in the development of the Contract documents and the project can be built as designed and to specifications.

The Scope of Services establishes which items of work in the FDOT Design Manual and other pertinent manuals are specifically prescribed to accomplish the work included in this contract, and also indicate which items of work will be the responsibility of the CONSULTANT and/or the DEPARTMENT.

The CONSULTANT shall be aware that as a project is developed, certain modifications and/or improvements to the original concepts may be required. The CONSULTANT shall incorporate these refinements into the design and consider such refinements to be an anticipated and integral part of the work. This shall not be a basis for any supplemental fee request(s).

The CONSULTANT shall demonstrate good project management practices while working on this project. These include communication with the DEPARTMENT and others as necessary, management of time and resources, and documentation. The CONSULTANT shall set up and maintain throughout the design of the project a contract file in accordance with DEPARTMENT procedures. CONSULTANTS are expected to know the laws and rules governing their professions and are expected to provide services in accordance with current regulations, codes and ordinances and recognized standards applicable to such professional services. The CONSULTANT shall provide qualified technical and professional personnel to perform to Department standards and procedures, the duties and responsibilities assigned under the terms of this agreement. The CONSULTANT shall minimize to the maximum extent possible the DEPARTMENT's need to apply its own resources to assignments authorized by the Department.

The DEPARTMENT will provide contract administration, management services, and technical reviews of all work associated with the development and preparation of contract documents, including Construction documents. The DEPARTMENT's technical reviews are for high-level conformance and are not meant to be comprehensive reviews. The CONSULTANT shall be fully responsible for all work performed and work products developed under this Scope of Services. The DEPARTMENT may provide job-specific information and/or functions as outlined in this contract, if favorable.

2 PROJECT DESCRIPTION

The CONSULTANT shall investigate the status of the project and become familiar with concepts and commitments (typical sections, alignments, etc.) developed from prior studies and/or activities. If a Preliminary Engineering Report is available from a prior or current Project Development and Environment (PD&E) study, the CONSULTANT shall use the approved concepts as a basis for the design unless otherwise directed by the DEPARTMENT.

The DEPARTMENT previously executed a design contract for the SR 312 Ultimate Extension Project in January 200 (210230-2-32-01). Plans were developed to 45% before this contract was closed in March 2019. This SR 312 Ultimate Project was designed as a new 6-lane typical from SR 207 to SR 16. The R/W was mapped for this limited access corridor and most of the Parcels have been acquired.

The DEPARTMENT executed a design contract for the SR 312 Interim Extension Project in September 2019 (210230-4-32-01). This project will consist of a new 2-lane typical section to be constructed from SR 207 to S. Holmes Blvd. Final Plans will be submitted in December 2021 for the scheduled May 2022 Let.

Under this design contract, the CONSULTANT:

- *will perform an alternatives study for the SR 312 Corridor from SR 207 to SR 16 based on the proposed new alignment shown in the 45% Plans.*
- *will provide PD&E Support for the Environmental Re-evaluation.*
- *will prepare final plans after a preferred alternative is selected.*

The DEPARTMENT will authorize additional design tasks as needed for this project.

2.1 Project General and Roadway (Activities 3, 4, and 5)

Public Involvement: *As Needed*

- *Public Hearing for PD&E Re-evaluation*
- *Coordination with St. Johns County*

Joint Project Agreements: *As Needed*

Specifications Package Preparation: *Specs on the Web*

Estimated Quantities Report Preparation: *As Needed*

Value Engineering: *As Needed*

Risk Assessment Workshop: *As Needed*

Plan Type: *Plan / Profile*

Number of SR 312 Typical Sections: *As Needed based on selected Alternative*
2-lane undivided Rural Typical Section (S. Holmes to SR 16)
4-lane divided Urban Typical Section (SR 207 to CR 214)
4-lane divided Rural Typical Section (CR 214 to SR 16)

Number of Pavement Designs: *As Needed base on selected Alternative*
SR 312 (New Construction)
SR 312 (Milling and Resurfacing)
SR 207 & SR 16
Connecting Sideroads
Access Roads

Pavement Type Selection Report(s): *As Needed*

Cross-Slope Correction: *N/A*

Access Management Classification:

- *Access Class 2 Restrictive*

Transit Route Features: *N/A*

Number of Major Intersections: **6**

SR 207, S. Holmes Blvd, Northwood Dr. / FEC RR, CR 214, Deer Run Rd, 4 Mile Rd, SR 16

Roadway Alternatives Study: Traffic Analysis and Intersection Control Evaluations will be performed for the below alternatives. Construction cost estimates will also be prepared. A preferred alternative will be selected based on need and available construction funding.

S. Holmes to SR 16

- *2-lane typical section*
- *At-grade connections*

SR 207 to SR 16

- *4-lane typical section*
- *At-grade connections (except for Northwood Dr. / FEC RR)*

SR 207 to SR 16

- *4-lane typical section*
- *At-grade connections at SR 207, CR 214 & SR 16*
- *Grade separation will be evaluated for other intersections*

Level of Temporary Traffic Control Plan (TTCP): **3**

Temporary Lighting: *As Needed*

Temporary Signals: *As Needed*

Temporary Drainage: *As Needed*

Design Variations: *As Needed*

Design Exceptions: *As Needed*

Back of Sidewalk Profiles: *N/A*

Selective Clearing and Grubbing: *As Needed*

Number of acres of Selective Clearing and Grubbing and/or Plant Preservation Area: *As Needed*

2.2 Drainage (Activities 6a and 6b)

Drainage System Type:

Closed and Open Systems with Storm Water Ponds

Number of stormwater management facility sites: *As Needed, Preliminary Stormwater Pond Sites are shown in 45% Concept Plans and R/W Maps*

Number of cross drains: *As Needed, Preliminary Cross Drains are shown in 45% Concept Plans*

2.3 Utilities Coordination (Activity 7) By FDOT with CONSULTANT Assistance

The CONSULTANT is responsible to certify that all necessary arrangements for utility work on this project have been made and will not conflict with the physical construction schedule. The CONSULTANT should coordinate with DEPARTMENT personnel to coordinate transmittals to Utility Companies and meet production schedules.

The CONSULTANT shall ensure FDOT standards, policies, procedures, practices, and design criteria are followed concerning utility coordination.

The CONSULTANT may employ more than one individual or utility engineering consultant to provide utility coordination and engineering design expertise. The CONSULTANT shall identify a dedicated person responsible for managing all utility coordination activities. This person shall be contractually referred to as the Utility Coordination Manager and shall be identified in the CONSULTANT proposal. The Utility Coordination Manager shall be required to satisfactorily demonstrate to the FDOT District Utilities Administrator that they have the following knowledge, skills, and expertise:

- A minimum of 4 years of experience performing utility coordination in accordance with FDOT, Federal Highway Administration (FHWA), and American Association of State Highway and Transportation Officials (AASHTO) standards, policies, and procedures.
- A thorough knowledge of the FDOT plans production process and District utility coordination process.
- A thorough knowledge of FDOT agreements, standards, policies, and procedures.

The Utility Coordination Manager shall be responsible for managing all utility coordination, including the following:

- Assuring that Utility Coordination and accommodation is in accordance to the FDOT, FHWA, and AASHTO standards, policies, procedures, and design criteria.
- Assisting the engineer of record in identifying all existing utilities and coordinating any new installations. Assisting the Engineer of Record with resolving utility conflicts.
- Scheduling and performing utility coordination meetings, keeping and distribution of minutes/action items of all utility meetings, and ensuring expedient follow-up on all unresolved issues.
- Distributing all plans, conflict matrixes and changes to affected utility owners and making sure this information is properly coordinated and documented.
- Identifying and coordinating the completion of any FDOT or utility owner agreement that is required for reimbursement, or accommodation of the utility facilities associated with the project.
- Review and certify to the District Utilities Administrator that all Utility Work Schedules are correct and in accordance with the DEPARTMENT's standards, policies, and procedures.
- Prepare, review and process all utility related reimbursable paperwork inclusive of betterment and salvage determination.

The CONSULTANT's utility coordination work shall be performed and directed by the Utility Coordination Manager that was identified and approved by FDOT's Project Manager. Any proposed change of the approved Utility Coordination Manager shall be subject to review and approval by FDOT's Project Manager prior to any change being made in this contract.

Expected Utilities: *AT&T, City of St. Augustine, Comcast Cable, FPL Distribution, FPL Transmission, St. Johns County Utility, Teco Gas, Uniti Fiber*

2.4 Environmental Permits and Environmental Clearances (Activity 8)

Expected Permits:

- *SJRWMD Permit*
- *FDEP 404 Permit*

The DEPARTMENT will provide compensatory wetland mitigation in accordance with Section 373.4137, Florida Statutes.

2.5 Structures (Activities 9 - 18)

The below Bridges will to be evaluated for the grade separated alternative. Please note: The construction of the SR 312 Bridge over Northwood Dr. / FEC RR Spur will be required for each alternative.

No.	Bridge Number	Length	Description
1	To Be Assigned	To be Determined	SR 312 Bridge over S. Holmes Blvd
2	To Be Assigned	To be Determined	SR 312 Bridge over Northwood Dr. / FEC RR Spur
3	To Be Assigned	To be Determined	SR 312 Bridge over Deer Run
4	To Be Assigned	To be Determined	Four Mile Rd Bridge over SR 312

Type of Bridge Structure Work

- BDR (Activity 10)
- Temporary Bridge (Activity 11): *N/A*
- Short Span Concrete (Activity 12): *N/A*
- Medium Span Concrete (Activity 13)
- Structural Steel (Activity 14): *N/A*
- Segmental Concrete (Activity 15): *N/A*
- Movable Span (Activity 16): *N/A*

Retaining Walls: *At Borrow Pits and As Needed in other areas*

Miscellaneous Structures:

- *Mast Arms*
- *Overhead Sign Structures*
- *Noise Barrier Walls*
- *Box Culverts*

Noise Barrier Walls: *As Needed*

2.6 Signing and Pavement Markings (Activities 19 & 20)

Sign Structures: *As Needed*

2.7 Signalization (Activities 21 & 22) *As needed for at-grade intersections*

Traffic Data Collection: *As Needed*

Traffic Studies: *As Needed for Alternatives Analysis*

Count Stations: *As Needed*

Traffic Monitoring Sites: *As Needed*

2.8 Lighting (Activities 23 & 24)

Limits and Proposed Type of Lighting: *To be Determined based on Lighting Justification Report prepared by CONSULTANT*

2.9 Landscape (Activities 25 & 26) (N/A)

2.10 Survey (Activity 27)

Design Survey: *As Needed*

Subsurface Utility Exploration: *As Needed*

Right of Way Survey: *As Needed*

Vegetation Survey: *N/A*

2.11 Photogrammetry (Activity 28) (N/A)

2.12 Mapping (Activity 29)

Control Survey Map: *As Needed for any new Parcels*

Right of Way Map: *As Needed for any new Parcels*

Legal Descriptions: *As Needed for any new Parcels*

Maintenance Map: *N/A*

Miscellaneous Items: *N/A*

2.13 Terrestrial Mobile LiDAR (Activity 30) (N/A)

2.14 Architecture (Activity 31) (N/A)

2.15 Noise Barriers (Activity 32) *As Needed*

2.16 Intelligent Transportation Systems (Activities 33 & 34) (N/A)

2.17 Geotechnical (Activity 35) *As Needed*

2.18 3D Modeling (Activity 36) *As Needed*

2.19 Project Schedule

Within ten (10) days after the Notice-To-Proceed, and prior to the CONSULTANT beginning work, the CONSULTANT shall provide a detailed project activity/event schedule for DEPARTMENT and CONSULTANT scheduled activities required to meet the current DEPARTMENT Production Date. The schedule is ***To Be Determined***. The current production date is ***To Be Determined (Construction is currently unfunded)***. The schedule shall be accompanied by an anticipated payout and fiscal progress curve. For the purpose of scheduling, the CONSULTANT shall allow for a ***4 week*** review time for each phase submittal and any other submittals as appropriate.

The schedule shall indicate all required submittals.

All fees and price proposals are to be based on the negotiated schedule of *To Be Determined* months for final construction contract documents. However, the contract deadline is *To Be Determined* months from the Notice to Proceed.

Periodically, throughout the life of the contract, the project schedule and payout and fiscal progress curves shall be reviewed and, with the approval of the DEPARTMENT, adjusted as necessary to incorporate changes in the Scope of Services and progress to date.

The approved schedule and schedule status report, along with progress and payout curves, shall be submitted with the monthly progress report.

The schedule shall be submitted in an FDOT system-compatible format.

2.20 Submittals

The CONSULTANT shall furnish construction contract documents as required by the DEPARTMENT to adequately control, coordinate, and approve the work concepts. The CONSULTANT shall distribute submittals as directed by the DEPARTMENT. The DEPARTMENT will determine the specific number of copies required prior to each submittal.

2.21 Provisions for Work

All work shall be prepared with English units in accordance with the latest editions of standards and requirements utilized by the DEPARTMENT which include, but are not limited to, publications such as:

General:

- *Title 29, Part 1910, Standard 1910.1001, Code of Federal Regulations (29 C.F.R. 1910.1001) - Asbestos Standard for Industry, U.S. Occupational Safety and Health Administration (OSHA)*
- *29 C.F.R. 1926.1101 - Asbestos Standard for Construction, OSHA*
- *40 C.F.R. 61, Subpart M - National Emission Standard for Hazardous Air Pollutants (NESHAP), Environmental Protection Agency (EPA)*
- *40 C.F.R. 763, Subpart E - Asbestos-Containing Materials in Schools, EPA*
- *40 C.F.R. 763, Subpart G - Asbestos Worker Protection, EPA*
- *Americans with Disabilities Act (ADA) Standards for Accessible Design*
- *AASHTO - A Policy on Design Standards Interstate System*
- *AASHTO - Roadside Design Guide*
- *AASHTO - Roadway Lighting Design Guide*
- *AASHTO - A Policy for Geometric Design of Highways and Streets*
- *AASHTO - Highway Safety Manual*
- *Rule Chapter 5J-17, Florida Administrative Code (F.A.C.), Standards of Practice for Professional Surveyors and Mappers*

- *Chapter 469, Florida Statutes (F.S.) - Asbestos Abatement*
- *Rule Chapter 62-257, F.A.C., Asbestos Program*
- *Rule Chapter 62-302, F.A.C., Surface Water Quality Standards*
- *Code of Federal Regulations (C.F.R.)*
- *Florida Administrative Codes (F.A.C.)*
- *Chapters 20, 120, 215, 455, Florida Statutes (F.S.) - Florida Department of Business & Professional Regulations Rules*
- *Florida Department of Environmental Protection Rules*
- *FDOT Basis of Estimates Manual*
- *FDOT Computer Aided Design and Drafting (CADD) Manual*
- *FDOT Standard Plans*
- *FDOT Flexible Pavement Design Manual*
- *FDOT - Florida Roundabout Guide*
- *FDOT Handbook for Preparation of Specifications Package*
- *FDOT Standard Plans Instructions*
- *FDOT Manual of Uniform Minimum Standards for Design, Construction and Maintenance for Streets and Highways ("Florida Greenbook")*
- *FDOT Materials Manual*
- *FDOT Pavement Type Selection Manual*
- *FDOT Design Manual*
- *FDOT Procedures and Policies*
- *FDOT Procurement Procedure 001-375-030, Compensation for Consultant Travel Time on Professional Services Agreements*
- *FDOT Project Development and Environment Manual*
- *FDOT Project Traffic Forecasting Handbook*
- *FDOT Public Involvement Handbook*
- *FDOT Rigid Pavement Design Manual*
- *FDOT Standard Specifications for Road and Bridge Construction*
- *FDOT Utility Accommodation Manual*
- *Manual on Speed Zoning for Highways, Roads, and Streets in Florida*
- *Federal Highway Administration (FHWA) - Manual on Uniform Traffic Control Devices (MUTCD)*
- *FHWA - National Cooperative Highway Research Program (NCHRP) Report 672, Roundabouts: An Informational Guide*
- *FHWA Roadway Construction Noise Model (RCNM) and Guideline Handbook*
- *Florida Fish and Wildlife Conservation Commission - Standard Manatee Construction Conditions 2005*
- *Florida Statutes (F.S.)*
- *Florida's Level of Service Standards and Guidelines Manual for Planning*
- *Model Guide Specifications - Asbestos Abatement and Management in Buildings, National Institute for Building Sciences (NIBS)*

- *Quality Assurance Guidelines*
- *Safety Standards*
- *Any special instructions from the DEPARTMENT*

Roadway:

- *FDOT - Florida Intersection Design Guide*
- *FDOT - Project Traffic Forecasting Handbook*
- *FDOT - Quality/Level of Service Handbook*
- *Florida's Level of Service Standards and Highway Capacity Analysis for the SHS*
- *Transportation Research Board (TRB) - Highway Capacity Manual*

Permits:

- *Chapter 373, F.S. - Water Resources*
- *US Fish and Wildlife Service Endangered Species Programs*
- *Florida Fish and Wildlife Conservation Commission Protected Wildlife Permits*
- *Bridge Permit Application Guide, COMDTPUB P16591.3C*
- *Building Permit*

Drainage:

- *FDOT Drainage Design Guide*
- *FDOT Drainage Manual*
- *Florida Erosion and Sediment Control Manual*
- *FDOT Drainage Connection Permit Handbook*
- *FDOT Bridge Scour Manual*

Survey and Mapping:

- *All applicable Florida Statutes and Administrative Codes*
- *Applicable Rules, Guidelines Codes and authorities of other Municipal, County, State and Federal Agencies.*
- *FDOT Aerial Surveying Standards for Transportation Projects Topic 550-020-002*
- *FDOT Right of Way Mapping Handbook*
- *FDOT Surveying Procedure Topic 550-030-101*
- *Florida Department of Transportation Right of Way Procedures Manual*
- *Florida Department of Transportation Surveying Handbook*
- *Right of Way Mapping Procedure 550-030-015*

Traffic Engineering and Operations and ITS:

- *AASHTO - An Information Guide for Highway Lighting*
- *AASHTO - Guide for Development of Bicycle Facilities*
- *FHWA Standard Highway Signs Manual*

- *FDOT Manual on Uniform Traffic Studies (MUTS)*
- *FDOT Median Handbook*
- *FDOT Traffic Engineering Manual*
- *National Electric Safety Code*
- *National Electrical Code*

Florida's Turnpike Enterprise:

- *Florida's Turnpike Design Handbook (TDH)*
- *Florida's Turnpike Lane Closure Policy*
- *Florida's Turnpike Drainage Manual Supplement*
- *Rigid Pavement Design Guide for Toll Locations with Electronic Toll Collection*
- *Flexible Pavement Design Guide for Toll Locations with Electronic Toll Collection*
- *Florida's Turnpike General Tolling Requirements (GTR)*
- *Additional Florida's Turnpike Enterprise standards, guides, and policies for design and construction can be found on the FTE Design Website:
<https://floridasturnpike.com/business-opportunities/design/>*

Traffic Monitoring:

- *American Institute of Steel Construction (AISC) Manual of Steel Construction, referred to as "AISC Specifications"*
- *American National Standards Institute (ANSI) RP-8-00 Recommended Practice for Roadway Lighting*
- *AASHTO AWS D1.1/ANSI Structural Welding Code - Steel*
- *AASHTO D1.5/AWS D1.5 Bridge Welding Code*
- *FHWA Traffic Detector Handbook*
- *FDOT General Interest Roadway Data Procedure*
- *FHWA Traffic Monitoring Guide*
- *FDOT's Traffic/Polling Equipment Procedures*

Structures:

- *AASHTO Load and Resistance Factor Design (LRFD) Bridge Design Specifications and Interims*
- *AASHTO LRFD Movable Highway Bridge Design Specifications and Interims*
- *AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires and Traffic Signals, and Interims*
- *AASHTO/-AWS-D1. 5M/D1.5: An American National Standard Bridge Welding Code*
- *AASHTO Guide Specifications for Structural Design of Sound Barriers*
- *AASHTO Manual for Condition Evaluation and Load and Resistance Factor Rating (LRF) of Highway Bridges*
- *FDOT Bridge Load Rating Manual*

- *FDOT Structures Manual*
- *FDOT Structures Design Bulletins (available on FDOT Structures web site only)*
- *Geotechnical*
- *FHWA Checklist and Guidelines for Review of Geotechnical Reports and Preliminary Specifications*
- *Manual of Florida Sampling and Testing Methods*
- *Soils and Foundation Handbook*

Landscape Architecture:

- *Florida Department of Agriculture and Consumer Services Grades and Standards for Nursery Plants*

Architectural:

- *Building Codes*
- *Florida Accessibility Code for Building Construction*
- *Rule Chapter 60D, F.A.C., Division of Building Construction*
- *Chapter 553, F.S. - Building Construction Standards*
- *ANSI A117.1 2003 Accessible and Usable Building and Facilities*
- *Titles II and III, Americans With Disabilities Act (ADA), Public Law 101-336; and the ADA Accessibility Guidelines (ADAAG)*
- *Florida Building Code:*
 - *Building*
 - *Fuel Gas*
 - *Mechanical*
 - *Plumbing*
 - *Existing Building*

Architectural - Fire Codes and Rules:

- *National Fire Protection Association (NFPA) - Life Safety Code*
- *NFPA 70 - National Electrical Code*
- *NFPA 101 - Life Safety Code*
- *NFPA 10 - Standard for Portable Fire Extinguishers*
- *NFPA 11 - Standard for Low-Expansion Foam Systems*
- *NFPA 11A - Standard for High- and Medium-Expansion Foam Systems*
- *NFPA 12 - Standard for Carbon Dioxide Extinguishing Systems*
- *NFPA 13 - Installation of Sprinkler Systems*
- *NFPA 30 - Flammable and Combustible Liquids Code*
- *NFPA 54 - National Gas Fuel Code*
- *NFPA 58 - LP-Gas Code*

- *Florida Fire Prevention Code as adopted by the State Fire Marshal - Consult with the Florida State Fire Marshal's office for other frequently used codes*

Architectural - Extinguishing Systems:

- *NFPA 10 - Fire Extinguishers*
- *NFPA 13 - Sprinkler*
- *NFPA 14 - Standpipe and Hose System*
- *NFPA 17 - Dry Chemical*
- *NFPA 20 - Centrifugal Fire Pump*
- *NFPA 24 - Private Fire Service Mains*
- *NFPA 200 - Standard on Clean Agent Fire Extinguishing Systems*

Architectural - Detection and Fire Alarm Systems:

- *NFPA 70 - Electrical Code*
- *NFPA 72 - Standard for the Installation, Maintenance and Use of Local Protective Signaling Systems*
- *NFPA 72E - Automatic Fire Detectors*
- *NFPA 72G - Installation, Maintenance, and Use of Notification Appliances*
- *NFPA 72H - Testing Procedures for Remote Station and Proprietary Systems*
- *NFPA 74 - Household Fire Warning Equipment*
- *NFPA 75 - Protection of Electronic Computer Equipment*

Architectural - Mechanical Systems:

- *NFPA 90A - Air Conditioning and Ventilating Systems*
- *NFPA 92A - Smoke Control Systems*
- *NFPA 96 - Removal of Smoke and Grease-Laden Vapors from Commercial Cooking Equipment*
- *NFPA 204M - Smoke and Heating Venting*

Architectural - Miscellaneous Systems:

- *NFPA 45 - Laboratories Using Chemicals*
- *NFPA 80 - Fire Doors and Windows*
- *NFPA 88A - Parking Structures*
- *NFPA 105- Smoke and Draft-control Door Assemblies*
- *NFPA 110 - Emergency and Standby Power Systems*
- *NFPA 220 - Types of Building Construction*
- *NFPA 241 - Safeguard Construction, Alteration, and Operations*
- *Rule Chapter 69A-47, F.A.C., Uniform Fire Safety For Elevators*
- *Rule Chapter 69A-51, F.A.C., Boiler Safety*

Architectural - Energy Conservation:

- *Rule Chapter 60D-4, F.A.C., Rules For Construction and Leasing of State Buildings To Insure Energy Conservation*
- *Section 255.255, F.S., Life-Cycle Costs*

Architectural - Elevators:

- *Rule Chapter 61C-5, F.A.C., Florida Elevator Safety Code*
- *ASME A-17.1, Safety Code for Elevators and Escalators*
- *Architectural - Floodplain Management Criteria*
- *Section 255.25, F.S., Approval Required Prior to Construction or Lease of Buildings*
- *Rules of the Federal Emergency Management Agency (FEMA)*

Architectural - Other:

- *Rule Chapter 64E-6, F.A.C., Standards for On Site Sewage Disposal Systems (Septic Tanks)*
- *Rule Chapter 62-600, F.A.C., Domestic Wastewater Facilities*
- *Rule Chapter 62-761, F.A.C., Underground Storage Tank Systems*
- *American Concrete Institute*
- *American Institute of Architects - Architect's Handbook of Professional Practice*
- *American Society for Testing and Materials - ASTM Standards*
- *Brick Institute of America*
- *DMS - Standards for Design of State Facilities*
- *Florida Concrete Products Association*
- *FDOT - ADA/Accessibility Procedure*
- *FDOT - Building Code Compliance Procedure*
- *FDOT - Design Build Procurement and Administration*
- *LEED (Leadership in Energy and Environmental Design) Green Building Rating System*
- *National Concrete Masonry Association*
- *National Electrical Code*
- *Portland Cement Association - Concrete Masonry Handbook*
- *United State Green Building Council (USGBC)*

2.22 Services to be Performed by the DEPARTMENT

When appropriate or available, the DEPARTMENT will provide project data including:

- *Numbers for field books*
- *Preliminary Horizontal Network Control*

- *Access for the CONSULTANT to utilize the DEPARTMENT's Information Technology Resources*
- *All Department agreements with Utility Agency Owner (UAO)*
- *All certifications necessary for project letting*
- *Building Construction Permit Coordination (Turnpike)*
- *All information that may come to the DEPARTMENT pertaining to future improvements*
- *All future information that may come to the DEPARTMENT during the term of the CONSULTANT's Agreement, which in the opinion of the DEPARTMENT is necessary for the prosecution of the work*
- *Available traffic and planning data*
- *All approved utility relocations*
- *Project utility certification to the DEPARTMENT's Central Office*
- *Any necessary title searches*
- *Engineering standards review services*
- *All available information in the possession of the DEPARTMENT pertaining to utility companies whose facilities may be affected by the proposed construction*
- *All future information that may come to the DEPARTMENT pertaining to subdivision plans so that the CONSULTANT may take advantage of additional areas that can be utilized as part of the existing right of way*
- *Systems traffic for Projected Design Year, with K, D, and T factors*
- *Previously constructed Highway Beautification or Landscape Construction Plans*
- *Landscape Opportunity Plan(s)*
- *Existing right of way maps*
- *Existing pavement evaluation report for all RRR projects*
- *PD&E Documents*
- *Design Reports*
- *Letters of authorization designating the CONSULTANT as an agent of the DEPARTMENT in accordance with F.S. 337.274*
- *Phase reviews of plans and engineering documents*
- *Regarding Environmental Permitting Services:*
 - *Approved Permit Document when available*
 - *Approval of all contacts with environmental agencies*
 - *General philosophies and guidelines of the DEPARTMENT to be used in the fulfillment of this contract. Objectives, constraints, budgetary limitations, and time constraints will be completely defined by the Project Manager.*
 - *Appropriate signatures on application forms*

3 PROJECT COMMON AND PROJECT GENERAL TASKS (AS NEEDED)

Project Common Tasks

Project Common Tasks, as listed below, are work efforts that are applicable to many project activities, 4 (Roadway Analysis) through 36 (3D Modeling). These tasks are to be included in the project scope in each applicable activity when the described work is to be performed by the CONSULTANT.

Cost Estimates: The CONSULTANT is responsible for producing a construction cost estimate and reviewing and updating the cost estimate when scope changes occur and/or at milestones of the project. Prior to 60% plans or completion of quantities, the DEPARTMENT's Long-Range Estimate (LRE) system will be used to produce a conceptual estimate, according to District policy. Once the quantities have been developed (beginning at 60% plans and no later than 90% plans) the CONSULTANT shall be responsible for inputting the pay items and quantities into AASHTOWare Project Preconstruction through the use of the DEPARTMENT's Designer Interface.

Technical Special Provisions: The CONSULTANT shall provide Technical Special Provisions for all items of work not covered by the Standard Specifications for Road and Bridge Construction and the workbook of implemented modifications.

A Technical Special Provision shall not modify the Standard Specifications and implemented modifications in any way.

The Technical Special Provisions shall provide a description of work, materials, equipment and specific requirements, method of measurement and basis of payment. Proposed Technical Special Provisions will be submitted to the District Specifications Office for initial review at the time of the Phase III plans review submission to the DEPARTMENT's Project Manager. This timing will allow for adequate processing time prior to final submittal. The Technical Special Provisions will be reviewed for suitability in accordance with the Handbook for Preparation of Specification Packages. The District Specifications Office will forward the Technical Special Provisions to the District Legal Office for their review and comment. All comments will be returned to the CONSULTANT for correction and resolution. Final Technical Special Provisions shall be digitally signed and sealed in accordance with applicable Florida Statutes.

The CONSULTANT shall contact the appropriate District Specifications Office for details of the current format to be used before starting preparations of Technical Special Provisions.

Modified Special Provisions: The CONSULTANT shall provide Modified Special Provisions as required by the project. Modified Special Provisions are defined in the Specifications Handbook.

A Modified Special Provision shall not modify the first nine sections of the Standard Specifications and implemented modifications in any way. All modifications to other sections must be justified to the appropriate District and Central Specifications Offices to be included in the project's specifications package.

Field Reviews: The CONSULTANT shall make as many trips to the project site as required to obtain necessary data for all elements of the project.

Technical Meetings: The CONSULTANT shall attend all technical meetings necessary to execute the Scope of Services of this contract. This includes meetings with DEPARTMENT and/or Agency staff, between disciplines and subconsultants, such as access management meetings, pavement design meetings, local governments, railroads, airports, progress review meetings (phase review), and miscellaneous meetings. The CONSULTANT shall prepare, and submit to the DEPARTMENT's Project Manager for review, the meeting minutes for all meetings attended by them. The meeting minutes are due within five (5) working days of attending the meeting.

Quality Assurance/Quality Control: It is the intention of the DEPARTMENT that design CONSULTANTS, including their subconsultant(s), are held responsible for their work, including plans review. The purpose of CONSULTANT plan reviews is to ensure that CONSULTANT plans follow the plan preparation procedures outlined in the FDOT Design Manual, that state and federal design criteria are followed with the DEPARTMENT concept, and that the CONSULTANT submittals are complete. All subconsultant document submittals shall be submitted by the subconsultant directly to the CONSULTANT for their independent Quality Assurance/Quality Control review and subsequent submittal to the DEPARTMENT.

It is the CONSULTANT'S responsibility to independently and continually QC their plans and other deliverables. The CONSULTANT should regularly communicate with the DEPARTMENT's Design Project Manager to discuss and resolve issues or solicit opinions from those within designated areas of expertise.

The CONSULTANT shall be responsible for the professional quality, technical accuracy and coordination of all surveys, designs, drawings, specifications and other services furnished by the CONSULTANT and their subconsultant(s) under this contract.

The CONSULTANT shall provide a Quality Control Plan that describes the procedures to be utilized to verify, independently check, and review all maps, design drawings, specifications, and other documentation prepared as a part of the contract. The CONSULTANT shall describe how the checking and review processes are to be documented to verify that the required procedures were followed. The Quality Control Plan shall be one specifically designed for this project. The CONSULTANT shall submit a Quality Control Plan for approval within twenty (20) business days of the written Notice to Proceed and it shall be signed by the CONSULTANT's Project Manager and the CONSULTANT QC Manager. The Quality Control Plan shall include the names of the

CONSULTANT's staff that will perform the quality control reviews. The Quality Control reviewer shall be a Florida Licensed Professional Engineer fully prequalified under F.A.C. 14-75 in the work type being reviewed. A marked up set of prints from a Quality Control Review indicating the reviewers for each component (structures, roadway, drainage, signals, geotechnical, signing and marking, lighting, landscape, surveys, etc.) and a written resolution of comments on a point-by-point basis will be required, if requested by the DEPARTMENT, with each phase submittal. The responsible Professional Engineer, Landscape Architect, or Professional Surveyor & Mapper that performed the Quality Control review will sign a statement certifying that the review was conducted and found to meet required specifications.

The CONSULTANT shall, without additional compensation, correct all errors or deficiencies in the designs, maps, drawings, specifications and/or other products and services.

Independent Peer Review: When directed by the DEPARTMENT, a subconsultant may perform Independent Peer Reviews.

Independent Peer Review and a Constructability/Bidability Review for design Phase Plans document submittals are required on this project. These separate reviews shall be completed by someone who has not worked on the plan component that is being reviewed. These could include, but are not limited to a separate office under the Prime's umbrella, a subconsultant that is qualified in the work group being reviewed, or a CEI. It does not include persons who have knowledge of the day to day design efforts. The Constructability/Bidability Review shall be performed by a person with experience working on Department construction projects (CEI, Contractor, etc.).

The Independent Peer Review for design Phase Plans submittals shall ensure the plans meet the FDM, Standard Plans and FDOT CADD Manual. The Constructability/Bidability Review shall ensure the project can be constructed and paid for as designed. Constructability/Bidability Reviews should be conducted prior to the Phase III and Phase IV submittals, using the Phase Review Checklist (Guidance Document 1-1-A) from the Construction Project Administration Manual (CPAM) as a minimum guideline. The CONSULTANT shall submit this checklist, as well as the "marked-up" set of plans during this review, and review comments and comment responses from any previous Constructability/Bidability reviews. These items will be reviewed by District Design and District Construction.

Supervision: The CONSULTANT shall supervise all technical design activities.

Coordination: The CONSULTANT shall coordinate with all disciplines of the project to produce a final set of construction documents.

Project General Tasks

Project General Tasks, described in Sections 3.1 through 3.7 below, represent work efforts that are applicable to the project as a whole and not to any one or more specific project activity. The work described in these tasks shall be performed by the CONSULTANT when included in the project scope.

3.1 Public Involvement

Public involvement includes communicating to all interested persons, groups, and government organizations information regarding the development of the project. The CONSULTANT shall provide to the DEPARTMENT drafts of all Public Involvement documents (e.g., newsletters, property owner letters, advertisements, etc.) associated with the following tasks for review and approval at least [*Number*] business days prior to printing and / or distribution.

3.1.1 Community Awareness Plan

Prepare a Community Awareness Plan (CAP) for review and approval by the DEPARTMENT within 30 calendar days after receiving Notice to Proceed. The objective of the plan is to notify local governments, affected property owners, tenants, and the public of the DEPARTMENT'S proposed construction and the anticipated impact of that construction. The CAP shall address timeframes for each review and shall include tentative dates for each public involvement requirement for the project. The CAP will also document all public involvement activities conducted throughout the project's duration. In addition to the benefits of advance notification, the process should allow the DEPARTMENT to resolve controversial issues during the design phase. This item shall be reviewed and updated periodically as directed by the DEPARTMENT throughout the life of the project.

3.1.2 Notifications

In addition to public involvement data collection, the CONSULTANT shall assist the DEPARTMENT or prepare notifications, flyers, and/or letters to elected officials and other public officials, private property owners, and tenants at intervals during plans production as identified by the DEPARTMENT. All letters and notices shall be reviewed by the [*DEPARTMENT/CONSULTANT*] to ensure that they are addressed to the correct and current public officials.

3.1.3 Preparing Mailing Lists

At the beginning of the project, The CONSULTANT shall identify all impacted property owners and tenants (within a minimum of 300 feet of the project corridor) The CONSULTANT shall prepare a mailing list of all such entities and shall update the mailing list as needed during the life of the project.

3.1.4 Median Modification Letters

The CONSULTANT shall prepare a median modification letter to be sent to property owners along the corridor. In addition, the CONSULTANT shall prepare a sketch of each proposed median modification for inclusion in the letter. The letters will be sent on DEPARTMENT letterhead by the [DEPARTMENT/CONSULTANT].

3.1.5 Driveway Modification Letters

The CONSULTANT shall prepare a driveway modification letter to be sent to property owners along the corridor. In addition, the CONSULTANT shall prepare a sketch of each proposed driveway modification for inclusion in the letter. The letters will be sent on DEPARTMENT letterhead.

3.1.6 Newsletters

The CONSULTANT shall prepare newsletters for distribution to elected officials, public officials, property owners along the corridor and other interested parties. The letters will be sent by the CONSULTANT.

3.1.7 Renderings and Fly-Throughs

The CONSULTANT shall prepare renderings and fly-throughs for use in public meetings.

3.1.8 PowerPoint Presentations

The CONSULTANT shall prepare PowerPoint presentations for use in public meetings.

3.1.9 Public Meeting Preparations

The CONSULTANT shall prepare the necessary materials for use in public meetings.

The CONSULTANT will investigate potential meeting sites to advise the DEPARTMENT on their suitability. The [DEPARTMENT/CONSULTANT] will pay all costs for meeting site rents and insurance. No DEPARTMENT meetings will be held on public school system properties.

3.1.10 Public Meeting Attendance and Follow-up

The CONSULTANT shall attend public meeting(s), assist with meeting setup and take down. The CONSULTANT shall also prepare a summary of the public meeting that includes all copies of all materials shown or provided at the public meeting. The summary shall also include a listing of all written comments made during or after the meeting and responses to those written comments.

The CONSULTANT will attend the meetings with an appropriate number of personnel to assist the DEPARTMENT'S Project Manager.

It is estimated for this project there will be [Number] Public meetings during the design.

3.1.11 Other Agency Meetings

In addition to scheduled public meetings the CONSULTANT may be required to participate in meetings with local governing authorities and/or Metropolitan Planning Organization (MPO). The CONSULTANT's participation may include, but not be limited to, presentations during the meeting, note taking, and summarizing the meeting in a memo to the file. It is estimated for this project there will be *NaN* meetings (as indicated in Section 2.1 above) with local governing authorities and/or MPOs during the design.

3.1.12 Web Site

The CONSULTANT shall create and/or maintain a web site for the project.

3.2 Joint Project Agreements

When the Joint Project Agreement (JPA) deliverable is not prepared by the CONSULTANT, services may include all coordination, meetings, etc., required to ensure compatibility, include JPA documents in the contract plans package and include the JPA documents in the digital delivery package.

3.3 Specifications & Estimates

3.3.1 Specifications Package Preparation

The CONSULTANT shall prepare and provide a specifications package in accordance with the DEPARTMENT'S Procedure Topic No. 630-010-005 Specifications Package Preparation and the Specifications Handbook. The CONSULTANT shall provide the DEPARTMENT names of at least two team members who have successfully completed the Specifications Package Preparation Training and will be responsible for preparing the Specifications Package for the project. The Specifications Package shall be prepared using the DEPARTMENT's Specs on the Web application. The CONSULTANT shall be able to document that the procedure defined in the Handbook for the Preparation of Specifications Packages is followed, which includes the quality assurance/quality control procedures. The specifications package shall address all items and areas of work and include any Mandatory Specifications, Modified Special Provisions, and Technical Special Provisions.

The specifications package must be submitted for review to the District Specifications Office at least 30 days prior to the contract package to Tallahassee or District due date, or sooner if required by the District Specifications Office. This submittal does not require signing and sealing and shall be coordinated through the District's Project Manager. The CONSULTANT shall coordinate with the DEPARTMENT on the submittal requirements, but at a minimum shall consist of (1) the complete specifications package, (2) a copy of the marked-up workbook used to prepare the package, and (3) a copy of the final project plans.

Final submittal of the specifications package must occur at least 10 working days prior to the contract package to Tallahassee due date. This submittal shall be digitally signed, dated, and sealed in accordance with applicable Florida Statutes.

3.3.2 Estimated Quantities Report Preparation

The CONSULTANT shall prepare an Estimated Quantities (EQ) Report in accordance with FDM 902. Includes loading quantities into Designer Interface for AASHTOWare Project Preconstruction (PrP), QA/QC efforts associated with AASHTOWare PrP and the EQ Report.

3.4 Contract Maintenance and Project Documentation

Contract maintenance includes project management effort for complete setup and maintenance of files, electronic folders and documents, developing technical monthly progress reports and schedule updates. Project documentation includes the compilation and delivery of final documents, reports or calculations that support the development of the contract plans; includes uploading files to Electronic Document Management System (EDMS) or Project Suite Enterprise Edition (PSEE).

3.5 Value Engineering (Multi-Discipline Team) Review

The design for this project will be subjected to a Value Engineering (VE) review. The VE review will be conducted by a multidiscipline, independent team of DEPARTMENT and CONSULTANT personnel for the improving the value of the project.

The CONSULTANT shall develop the design and contract documents using sound value engineering practices to the fullest extent possible, in order to support appropriate design decisions in producing the contract plans for the most efficient and economical design.

Value Engineering is an event-related activity and should occur at a time when it will provide the greatest opportunity for value improvement, as determined by the Department Project Manager and Value Engineering Coordinator. This opportune time during the design phase of a project will generally fall between completion of Phase I design plans and completion of Phase II design plans, but may occur at any time during the development of a project.

Activities required by the CONSULTANT in support of the VE team are:

Providing Materials and Information: The CONSULTANT shall allow ample time for the appropriate knowledgeable members of their staff to present current design documentation and data to the VE team, as deemed necessary for an effective project review.

The Consultant Project Manager and other key members of the design team shall meet with the VE team to explain the development of design features and how and why they were selected. The information will be provided in the form of a personal verbal presentation and the submittal of a package containing current plans and other documentation. This presentation

will take place at the location of the VE study and may be followed up with additional meetings, written communications and phone enquiries.

Information and data that should be available to the VE Team include, but is not limited to the following:

- One copy of all environmental documents
- One copy of the Preliminary Engineering Report
- Three copies of all plan drawings
- Drainage alternatives information
- One copy of Bridge Development Reports
- One copy of Pavement Type Selection Report
- One copy of Pavement Design Package
- One copy of other miscellaneous reports
- Project Cost Estimate

The Project Cost Estimate shall include a tabulation of estimated construction costs for the proposed design. This list shall, at a minimum, contain a breakdown of costs for each major element of the design.

The CONSULTANT shall provide, in the form of a matrix, all criteria and weighted impacts used in arriving at decisions for the selection of specific design features. These criteria must include Safety, Operation, Maintenance and Public Acceptance.

All reports provided by the CONSULTANT will be returned after the VE review has been completed. However, copies of plans and drawings may be kept by the VE team.

3.6 Prime Consultant Project Manager Meetings

Includes only the Prime Consultant Project Manager's time for travel and attendance at Activity Technical Meetings and other meetings listed in the meeting summary for Task 3.6 on tab 3 Project General Task of the staff hour forms. Staff hours for other personnel attending Activity Technical Meetings are included in the meeting task for that specific Activity.

3.7 Plans Update

The effort needed for Plans Update services will vary from project to project, depending on size and complexity of the project, as well as the duration of time spent "on the shelf".

Specific services will be negotiated as necessary as a contract amendment.

3.8 Post-Design Services

Post-Design Services may include, but not limited to, meetings, construction assistance, plans revisions, shop drawing review, survey services, as-built drawings, and load ratings. Specific services will be negotiated as necessary as a contract amendment.

Post-Design Services are not intended for instances of CONSULTANT errors or omissions.

3.9 Digital Delivery

The CONSULTANT shall deliver final contract plans and documents in digital format. The final contract plans and documents shall be digitally signed and sealed files delivered to the DEPARTMENT on acceptable electronic media, as determined by the DEPARTMENT.

3.10 Risk Assessment Workshop

This project will be subject to Risk Assessment (RA) and Management for the purpose of the identifying, quantifying and managing the potential cost and schedule risks of the project. The RA for this project will be managed by the Department Project Manager and supported by a multidiscipline team (RA Team) of DEPARTMENT and CONSULTANT personnel and subject-matter experts (SMEs). The Department Project Manager will be the lead for the RA Team.

There will be a Risk Assessment (RA) Workshop and workshop related meetings during the design. The Workshop will generally occur before completion of Phase I design plans, but may occur at any time during the development of a project as determined by the Department Project Manager. The Department Project Manager will develop a Risk Register following the RA Workshop, and utilize the Risk Register throughout the life of the project to mitigate and manage the risks.

The CONSULTANT (and key subconsultant(s) if applicable), and other key members of the design team will attend and participate in the Risk Assessment Workshop for this project. This will involve a Risk Preparatory Session (half-day to 1 day plus information assessment), a Risk Assessment Workshop (1 to 3 days), and Risk Follow-Up Meeting (half-day to 1 day).

The CONSULTANT and other key members of the design team will attend and participate in associated follow-up RA meetings (approximately one meeting every three to six months as deemed necessary) with the Department Project Manager (and RA team if applicable) to discuss the risks, mitigation strategies and any updates to the Risk Register. This includes written communications and phone inquiries. The CONSULTANT will coordinate with subconsultants who need to attend the Workshop and associated meetings.

CONSULTANT shall provide the RA Team meeting materials that are deemed necessary by the Department Project Manager to conduct the Workshop and associated meetings. The meeting materials include the following:

- One copy of all environmental documents
- One copy of the Preliminary Engineering Report
- One copy of all plan drawings (three copies if a workshop is applicable)
- Drainage alternatives information
- One copy of Bridge Development Reports
- One copy of Pavement Type Selection Report

- One copy of Pavement Design Package
- One copy of other miscellaneous reports
- Project Schedule
- Project Cost Estimate

Project Cost Estimate shall include a tabulation of estimated construction costs for the proposed design, and a breakdown of costs for each major element of the design, such as Right of Way, Design, CEI, Utilities, JPA/LAP funds, etc.

The CONSULTANT shall allow ample time for the appropriate knowledgeable members of their staff to prepare and provide current design documentation and data. All reports provided by the CONSULTANT will be returned after the RA Workshop has been completed; however, copies of plans and drawings may be kept by the RA team. The CONSULTANT will be responsible for providing follow-up actions as necessary.

3.11 Railroad, Transit and/or Airport Coordination

Proposed Grade Separated Bridge over FEC Railroad Spur Line.

3.11.1 Aeronautical Evaluation

The Consultant shall be responsible for complying with the requirements of Title 14 of the Code of Federal Regulations Part 77 (14 CFR Part 77), and for determining whether it is necessary to file any Notice of Proposed Construction or Alteration (FAA Form 7460-1) with the Federal Aviation Administration (FAA), utilizing the FAA Notice Criteria Tool. Place a copy of all pertinent documentation in the Project Documentation folder structure; e.g., Notice Criteria Tool inquiries and responses; FAA Form 7460-1 filed with the FAA; Letters of Determination (along with the records demonstrating compliance with the conditions and deadlines). Report any Letters of Determination, designated other than "Does Not Exceed", to the Central Office (Aviation Office, Airspace and Land Use Manager).

3.12 Landscape and Existing Vegetation Coordination

Coordinate to ensure preservation and protection of existing vegetation. Relocation of existing vegetation may be necessary in some cases. Space for proposed landscape should be preserved and conflicts with drainage, utilities, ITS, and signage should be minimized. Coordination with the District Landscape Architect may be necessary as defined in 4.12. Additionally, coordination with the Florida Scenic Highways program should be included to ensure any requirements of the FSH program are met.

3.13 Other Project General Tasks

4 ROADWAY ANALYSIS (AS NEEDED)

The CONSULTANT shall analyze and document Roadway Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

4.1 Typical Section Package

The CONSULTANT shall provide an approved Typical Section Package prior to the first plans submittal.

4.2 Pavement Type Selection Report

Pavement Type Selection Reports are required for every project one mile or greater in length where work includes a modification to the base materials. The Pavement Type Selection decision will again be reviewed by FDOT Design at the time the pavement is designed to warrant reconsideration. A letter to the Project Design File documenting the pavement type decision is required, even if no report is performed.

4.3 Pavement Design Package

The CONSULTANT shall provide an approved Pavement Design Package prior to the Phase II plans submittal date.

4.4 Cross-Slope Correction (N/A)

4.5 Horizontal/Vertical Master Design Files

The CONSULTANT shall design the geometrics using the Standard Plans that are most appropriate with proper consideration given to the design traffic volumes, design speed, capacity and levels of service, functional classification, adjacent land use, design consistency and driver expectancy, aesthetics, existing vegetation to be preserved, pedestrian and bicycle concerns, ADA requirements, Safe Mobility For Life Program, access management, PD&E documents and scope of work. The CONSULTANT shall also develop utility conflict information to be provided to project Utility Coordinator in the format requested by the DEPARTMENT.

Note: When the project includes a 3D Model deliverable, also include Activity 36 3D Modeling.

4.6 Access Management

The CONSULTANT shall incorporate access management standards for each project in coordination with DEPARTMENT staff. The CONSULTANT shall review adopted access management standards and the existing access conditions (interchange spacing, signalized

intersection spacing, median opening spacing, and connection spacing). Median openings that will be closed, relocated, or substantially altered shall be shown on plan sheets and submitted with supporting documentation for review with the first plans submittal.

The DEPARTMENT shall provide access management classification information and information derived from PD&E studies and public hearings to be used by the CONSULTANT.

4.7 Roundabout Evaluation

The CONSULTANT shall analyze and document Roundabout Evaluation Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

The CONSULTANT shall perform a Roundabout Screening for assessment of potential site impacts such as utility adjustments or relocations, right of way takes, environmental mitigation, and access management.

The CONSULTANT shall perform a Roundabout Benefit-Cost Evaluation comparing a roundabout with a traditional intersection (stop controlled or signal controlled). The benefit-cost analysis considers safety benefits associated with reduced crashes, delay, life cycle costs including right of way, utilities, construction, operation, and maintenance.

The CONSULTANT shall perform a Geometric and Operation Analysis to establish the roundabout alignment, geometry and lane requirements. Roundabout geometric and operational analysis must be documented in a preliminary report including data collection, conceptual layout, crash analysis, traffic counts, traffic forecast, and future design and opening year analysis.

The CONSULTANT shall perform all efforts required for traffic data collection and required design elements for all the above steps accordingly, including crash reports, 24-hour machine counts, peak hour turning movement counts, existing geometrics, pedestrian and bicycle volumes, posted speed limits, delay counts, design vehicle, access management, transit operations and physical and right of way limitations.

4.8 Roundabout Final Design Analysis

The CONSULTANT shall finalize the design of the roundabout in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

The CONSULTANT shall perform a final roundabout operational analysis that recommends a functional geometric layout that is cost effective, safe and meets the needs of the community. A final roundabout design will be recommended for implementation, and all geometric and operational analysis will be documented in a final roundabout report.

4.9 Cross Section Design Files

The CONSULTANT shall establish and develop cross section design files in accordance with the FDOT CADD Manual.

Note: If the Cross Sections are prepared using a 3D model, use Task 36.5 instead of Task 4.9 for the Cross Section Design Files.

4.10 Temporary Traffic Control Plan (TTCP) Analysis

The CONSULTANT shall design a safe and effective TTCP to move vehicular and pedestrian traffic during all phases of construction. The design shall include construction phasing of roadways ingress and egress to existing property owners and businesses, routing, signing and pavement markings, and detour quantity tabulations, roadway pavement, drainage structures, ditches, front slopes, back slopes, drop offs within clear zone, transit stops, and traffic monitoring sites. Special consideration shall be given to the construction of the drainage system when developing the construction phases. Positive drainage must be maintained at all times. The design shall include construction phasing of roadways to accommodate the construction or relocation of utilities when the contract includes Joint Project Agreements (JPAs).

The CONSULTANT shall investigate the need for temporary traffic signals, temporary highway lighting, detours, diversions, lane shifts, and the use of materials such as sheet piling in the analysis. The Traffic Control Plan shall be prepared by a certified designer who has completed training as required by the DEPARTMENT. Before proceeding with the TTCP, the CONSULTANT shall meet with the appropriate DEPARTMENT personnel. The purpose of this meeting is to provide information to the CONSULTANT that will better coordinate the Preliminary and Final TTCP efforts.

The CONSULTANT shall consider the local impact of any lane closures or alternate routes. When the need to close a road is identified during this analysis, the CONSULTANT shall notify the DEPARTMENT's Project Manager as soon as possible. Proposed road closings must be reviewed and approved by the DEPARTMENT. Diligence shall be used to minimize negative impacts by appropriate specifications, recommendations or plans development. Local impacts to consider will be local events, holidays, peak seasons, detour route deterioration and other eventualities. CONSULTANT shall be responsible to obtain local authorities permission for use of detour routes not on state highways.

4.11 Master TTCP Design Files

The CONSULTANT shall develop master TTCP files showing each phase of the TTCP. This includes all work necessary for designing lane configurations, diversions, lane shifts, signing and pavement markings, temporary traffic control devices, and temporary pedestrian ways.

4.12 Selective Clearing and Grubbing

Note: Utilize Activities 25 and 26 for Standalone Landscape Projects.

a) Selective Clearing and Grubbing of Existing Vegetation Field Assessment

The CONSULTANT shall review information from the DEPARTMENT and conduct a project field assessment(s) of existing vegetation. At least one field assessment visit is to be attended by the District Landscape Architect.

The Result of the Field Assessment(s) will determine the course of action for Selective Clearing and Grubbing and the extent of the Vegetation Survey under Task 2.10.

b) Selective Clearing and Grubbing Site Inventory Analysis of Existing Vegetation and Cross-Discipline Coordination (OPTIONAL SERVICES)

The CONSULTANT shall coordinate with the District Utility Office, drainage engineers, and traffic engineers to ensure that preservation of existing vegetation is coordinated between all disciplines. Coordinate with the District Landscape Architect.

Based on the field assessment, the CONSULTANT may be required do a site inventory analysis of existing vegetation, opportunities for preservation and protection of existing vegetation, relocation options, and selective removal of nuisance and/or non-nuisance vegetation. Coordinate with surveyor to have trees and vegetation tagged and surveyed, per tasks 27.28 or 27.29.

c) Selective Clearing and Grubbing- Existing Vegetation Maintenance Report

The CONSULTANT shall include in the plans instructions for the care and maintenance of the plant preservation areas, and selective clearing and grubbing areas throughout the construction period. The CONSULTANT will coordinate with the District Landscape Architect to ensure that the intent of the plant preservation areas is in alignment with future highway landscape plans. The CONSULTANT should be knowledgeable in arboricultural practices to the extent that they are able to deliver detailed and informed Selective Clearing and Grubbing Plans.

4.13 Tree Disposition Plans

Consultant will prepare a Tree Disposition Plan outlining the requirements for the relocation and protection of trees located within the project boundaries. Will utilize the information collected from the Vegetation Survey and information collected under task 4.12 for Selective Clearing and Grubbing.

4.14 Design Variations and Exceptions

If available, the DEPARTMENT shall furnish the Variation/Exception Report. The CONSULTANT shall prepare the documentation necessary to gain DEPARTMENT approval of all appropriate Design Variations and/or Design Exceptions before the first submittal.

4.15 Design Report

The CONSULTANT shall prepare all applicable report(s) as listed in the Project Description section of this scope. Reports are to be delivered as a signed and sealed pdf file.

4.16 Quantities for EQ Report

The CONSULTANT shall determine pay items and quantities and the supporting documentation, including construction days when required.

4.17 Cost Estimate

4.18 Technical Special Provisions and Modified Special Provisions

4.19 Other Roadway Analyses

4.20 Field Reviews

4.21 Monitor Existing Structures

The CONSULTANT shall perform field observations to visually identify existing structures within the project limits which may require settlement, vibration or groundwater monitoring by the contractor during construction in accordance with FDM Chapter 307. The CONSULTANT shall identify the necessary pay items to be included in the bid documents to monitor existing structures.

Optional Services (may be negotiated at a later date if needed): The CONSULTANT shall coordinate with and assist the geotechnical engineer and/or structural engineer to develop mitigation strategies (when applicable).

4.22 Technical Meetings

4.23 Quality Assurance/Quality Control

4.24 Independent Peer Review

4.25 Supervision

4.26 Coordination

5 ROADWAY PLANS (AS NEEDED)

The CONSULTANT shall prepare Roadway, TTCP, Utility Adjustment Sheets, plan sheets, notes, and details. The plans shall include the following sheets necessary to convey the intent and scope of the project for the purposes of construction.

- 5.1 Key Sheet**
- 5.2 Typical Section Sheets**
 - 5.2.1 Typical Sections**
 - 5.2.2 Typical Section Details**
- 5.3 General Notes/Pay Item Notes**
- 5.4 Project Layout**
- 5.5 Plan/Profile Sheet**
- 5.6 Profile Sheet**
- 5.7 Plan Sheet**
- 5.8 Special Profile**
- 5.9 Back-of-Sidewalk Profile Sheet (N/A)**
- 5.10 Interchange Layout Sheet**
- 5.11 Ramp Terminal Details (Plan View)**
- 5.12 Intersection Layout Details**
- 5.13 Special Details**
- 5.14 Cross-Section Pattern Sheets**
- 5.15 Roadway Soil Survey Sheets**
- 5.16 Cross Sections**
- 5.17 Temporary Traffic Control Plan Sheets**
- 5.18 Temporary Traffic Control Cross Section Sheets**
- 5.19 Temporary Traffic Control Detail Sheets**
- 5.20 Utility Adjustment Sheets**
- 5.21 Selective Clearing and Grubbing Sheets**
 - 5.21.1 Selective Clearing and Grubbing**
 - 5.21.2 Selective Clearing and Grubbing Details**
- 5.22 Tree Disposition Plan Sheets**
 - 5.22.1 Tree Disposition Plan Sheets**

Tree Disposition Plan Sheets will be signed and sealed drawings showing the location and vertical/horizontal landscape design of the vegetation to be relocated. The Tree Disposition

Plans will be produced at the scale of the roadway drawings or at a scale that best depicts the information. Interchange and details will be shown at no larger than a 1" =50" scale.

5.22.2 Tree Disposition Plan Tables and Schedules

5.23 Project Control Sheets

5.24 Environmental Detail Sheets

Preparation of detail sheets for potential environmental issues such as, underground fuel tanks and monitoring wells, septic tanks within the proposed right of way. All piping and pumps in association with the above referenced issues shall also be located and identified by the survey. The CONSULTANT shall relay to the DEPARTMENT any findings of contaminated soil, monitoring wells, or any features (particularly springs or sinks) relating to contamination or hazardous material.

Coordination with Permits/Environmental staff and preparing Dredge & Fill Detail sheets where applicable.

5.25 Utility Verification Sheets (SUE Data)

5.26 Quality Assurance/Quality Control

5.27 Supervision

6a DRAINAGE ANALYSIS (AS NEEDED)

The CONSULTANT shall analyze and document Drainage Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

The CONSULTANT shall be responsible for designing a drainage and stormwater management system. All design work shall comply with the requirements of the appropriate regulatory agencies and the DEPARTMENT's Drainage Manual.

The CONSULTANT shall coordinate fully with the appropriate permitting agencies and the DEPARTMENT's staff. All activities and submittals should be coordinated through the DEPARTMENT's Project Manager. The work will include the engineering analyses for any or all of the following:

6a.1 Drainage Map Hydrology

Create a (pre- and/or post-condition) working drainage basin map to be used in defining the system hydrology. This map shall incorporate drainage basin boundaries, existing survey and/or LiDAR and field observations, as necessary, to define the system. Basin delineations shall also include any existing collection systems in a logical manner to aid in the development of the hydraulic model. Include coordination hours needed to convey drainage hydrologic features onto produced drainage maps.

6a.2 Base Clearance Calculations

Analyze, determine, and document high water elevations per basin which will be used to set roadway profile grade and roadway materials. Determine surface water elevations at cross drains, floodplains, outfalls and adjacent stormwater ponds. Determine groundwater elevations at intervals between the above-mentioned surface waters. Document findings in a Base Clearance Report.

6a.3 Pond Siting Analysis and Report

Evaluate pond sites using a preliminary hydrologic analysis. Document the results and coordination for all the project's pond site analyses. The Drainage Manual provides specific documentation requirements.

6a.4 Design of Cross Drains

Analyze the hydraulic design and performance of cross drains. Check existing cross drains to determine if they are structurally sound and can be extended. Document the design as required. Determine and provide flood data as required.

6a.5 Design of Ditches

Design roadway conveyance and outfall ditches. This task includes capacity calculations, longitudinal grade adjustments, flow changes, additional adjustments for ditch convergences, selection of suitable channel lining, design of side drain pipes, and documentation. (Design of linear stormwater management facilities in separate task.)

6a.6 Design of Stormwater Management Facility (Offsite or Infield Pond)

Design stormwater management facilities to meet requirements for stormwater quality treatment, attenuation and aesthetics. Develop proposed pond layout (contributing drainage basin, shape, contours, slopes, volumes, tie-ins, aesthetics, etc.), perform routing, pollutant/nutrient loading calculations, recovery calculations, design the outlet control structure and buoyancy calculations for pond liners when necessary.

6a.7 Design of Stormwater Management Facility (Roadside Treatment Swales and Linear Ponds)

Design stormwater management facilities to meet requirements for stormwater quality treatment, attenuation and aesthetics. Develop proposed pond layout (contributing drainage basin, shape, contours, slopes, volumes, tie-ins, aesthetics, etc.), perform routing, pollutant/nutrient loading calculations, recovery calculations and design the outlet control structure.

6a.8 Design of Floodplain Compensation

Determine floodplain encroachments, coordinate with regulatory agencies, and develop proposed compensation area layout (shape, contours, slopes, volumes, etc.). Document the design following the requirements of the regulatory agency.

6a.9 Design of Storm Drains

Delineate contributing drainage areas, determine runoff, inlet locations, and spread. Calculate hydraulic losses (friction, utility conflict and, if necessary, minor losses). Determine design tailwater and, if necessary, outlet scour protection.

6a.10 Optional Culvert Material

Determine acceptable options for pipe materials using the Culvert Service Life Estimator.

6a.11 French Drain Systems

Design French Drain Systems to provide stormwater treatment and attenuation. Identify location for percolation tests and review these, determine the size and length of French Drains, design the control structure/weir, and model the system of inlets, conveyances, French Drains, and other outfalls using a routing program.

6a.11.1 Existing French Drain Systems

Include this task if French Drains are proposed and the existing systems must be analyzed for a pre- versus post comparison of the peak stages and/or discharges.

6a.12 Drainage Wells

Design the discharge into deep wells to comply with regulatory requirements. Identify the location of the well, design the control structure/weir, and model the system using a routing program.

6a.13 Drainage Design Documentation Report

Compile drainage design documentation into report format. Include documentation for all the drainage design tasks and associated meetings and decisions, except for stand-alone reports, such as the Pond Siting Analysis Report and Bridge Hydraulics Report.

6a.14 Bridge Hydraulic Report

Calculate hydrology, hydraulics, deck drainage, scour, and appropriate counter measures. Prepare report and the information for the Bridge Hydraulics Recommendation Sheet.

6a.15 Temporary Drainage Analysis

Evaluate and address drainage to adequately drain the road and maintain existing offsite drainage during all construction phases. Provide documentation.

6a.16 Quantities for EQ Report

The CONSULTANT shall determine pay items and quantities and the supporting documentation.

6a.17 Cost Estimate

Prepare cost estimates for the drainage components, except bridges and earthwork for stormwater management and flood compensation sites.

6a.18 Technical Special Provisions / Modified Special Provisions

6a.19 Hydroplaning Analysis

Perform a hydroplaning analysis to assist in the determination of the appropriate roadway geometry for all necessary locations (both typical sections and critical cross sections) as needed. See the FDOT Hydroplaning Guidance and FDOT Design Manual (FDM) Chapters 210 and 211 for more information.

6a.20 Existing Permit Analysis

Data gathering including desktop analysis of local, state and federal Drainage permits.

6a.21 Other Drainage Analysis

Includes all efforts for a drainage task not covered by an existing defined task.

6a.22 Noise Barrier Evaluation

Evaluate the capacity of drainage openings in noise barriers and locate them to ensure flows are accommodated.

6a.23 Field Reviews

6a.24 Technical Meetings

Meetings with Department staff, regulatory agencies, local governments such as meetings with District Drainage Engineer, the Water Management District, FDEP, etc.

6a.25 Environmental Look-Around Meetings

Convene a meeting with Department staff, regulatory agencies, local governments and other stakeholders to explore watershed wide stormwater needs and alternative permitting approaches.

6a.26 Quality Assurance/Quality Control

6a.27 Independent Peer Review

6a.28 Supervision

6a.29 Coordination

6b DRAINAGE PLANS (AS NEEDED)

The CONSULTANT shall prepare Drainage plan sheets, notes, and details. The plans shall include the following sheets necessary to convey the intent and scope of the project for the purposes of construction.

6b.1 Drainage Map (Including Interchanges)

6b.2 Bridge Hydraulics Recommendation Sheets

6b.3 Drainage Structures

6b.4 Lateral Ditch Plan/Profile

6b.5 Lateral Ditch Cross Sections

6b.6 Retention/Detention Pond Detail Sheets

6b.7 Retention Pond Cross Sections

6b.8 Erosion Control Plan Sheets

6b.9 SWPPP Sheets

6b.10 Quality Assurance/Quality Control

6b.11 Supervision

7 UTILITIES (AS NEEDED)

Utility Coordination by FDOT with CONSULTANT assistance.

The CONSULTANT shall identify utility facilities and secure agreements, utility work schedules, and plans from the Utility Agency Owners (UAO) ensuring all conflicts that exist between utility facilities and the DEPARTMENT's construction project are addressed. The CONSULTANT shall certify all utility negotiations have been completed and that arrangements have been made for utility work to be undertaken.

7.1 Utility Kickoff Meeting

Before any contact with the UAO(s), the CONSULTANT shall meet with the District Utility Office (DUO) to receive guidance, as may be required, to assure that all necessary coordination will be accomplished in accordance with DEPARTMENT procedures. CONSULTANT shall bring a copy of the design project work schedule reflecting utility activities.

7.2 Identify Existing Utility Agency Owner(s)

The Consultant shall identify all utilities within and adjacent to the project limits that may be impacted by the project.

7.3 Make Utility Contacts

First Contact: The CONSULTANT shall send letters and two sets of plans to each utility, one set for the utility office, and one set to the DEPARTMENT Offices as required by the District. Includes contact by phone for meeting coordination. Request type, size, location, easements, and cost for relocation if reimbursement is claimed. Request the voltage level for power lines in the project area. Send UAO requests for reimbursement to FDOT for a legal opinion. Include the meeting schedule (if applicable) and the design schedule. Include typical meeting agenda. If scheduling a meeting, give a 4-week notice.

Second Contact: At a minimum of 4 weeks prior to the meeting, the CONSULTANT shall transmit two complete sets of Phase II plans and the utility conflict information (when applicable and in the format requested by the DEPARTMENT) to each UAO having facilities located within the project limits, and one set to the DEPARTMENT Offices as required by the District.

Third Contact: Identify agreements and assemble packages. The CONSULTANT shall send agreements, letters, the utility conflict information (when applicable and in the format requested by the DEPARTMENT) and two sets of plans to the UAO(s) including all component sets, one set for the utility office, one set to construction and maintenance if required. Include the design schedule.

Not all projects will have all contacts as described above.

7.4 Exception Processing

The CONSULTANT shall be responsible for transmitting/coordinating the appropriate design reports including, but not limited to, the Resurfacing, Restoration and Rehabilitation (RRR) report, Preliminary Engineering Report, Project Scope and/or the Concept Report (if applicable) to each UAO to identify any condition that may require a Utility Exception. The CONSULTANT shall identify and communicate to the UAO any facilities in conflict with their location or project schedule. The CONSULTANT shall assist with the processing of design exceptions involving Utilities with the UAO and the DEPARTMENT. Assist with processing per the UAM.

7.5 Preliminary Utility Meeting

The CONSULTANT shall schedule (time and place), notify participants, and conduct a preliminary utility meeting with all UAO(s) having facilities located within the project limits for the purpose of presenting the project, review the current design schedule, evaluate the utility information collected, provide follow-up information on compensable property rights from the FDOT Legal Office, discuss the utility work by highway contractor option with each utility, and discuss any future design issues that may impact utilities. This is also an opportunity for the UAO(s) to present proposed facilities. The CONSULTANT shall keep accurate minutes and distribute a copy to all attendees.

7.6 Individual/Field Meetings

The CONSULTANT shall meet with each UAO as necessary, separately or together, throughout the project design duration to provide guidance in the interpretation of plans, review changes to the plans and schedules, standard or selective clearing and grubbing work, and assist in the development of the UAO(s) plans and work schedules. The CONSULTANT is responsible for motivating the UAO to complete and return the necessary documents after each Utility Contact or Meeting.

7.7 Collect and Review Plans and Data from UAO(s)

The CONSULTANT shall review utility marked plans and data individually as they are received for content. Ensure information from the UAO (utility type, material and size) is sent to the designer for inclusion in the plans. Forward all requests for utility reimbursement and supporting documentation to the DUO.

7.8 Subordination of Easements Coordination

The CONSULTANT, if requested by the DEPARTMENT, shall transmit to and secure from the UAO the executed subordination agreements prepared by the appropriate DEPARTMENT office. The CONSULTANT shall coordinate with the DUO the programming of the necessary work program funds to compensate the UAO.

7.9 Utility Design Meeting

The CONSULTANT shall schedule (time and place), notify participants, and conduct a Utility meeting with all affected UAO(s). The CONSULTANT shall be prepared to discuss impacts to existing trees/vegetation and proposed landscape, drainage, traffic signalization, temporary traffic control plans (TTCP) (construction phasing), review the current design schedule and letting date, evaluate the utility information collected, provide follow-up information on compensable property rights from FDOT Legal Office, discuss with each UAO the utility work by highway contractor option, discuss any future design issues that may impact utilities, etc., to the extent that they may have an effect on existing or proposed utility facilities with particular emphasis on drainage and TTCP with each UAO. The intent of this meeting shall be to assist the UAOs in identifying and resolving conflicts between utilities and proposed construction before completion of the plans, including utility adjustment details. Also, to work

with the UAOs to recommend potential resolution between known utility conflicts with proposed construction plans as may be deemed practical by the UAO. The CONSULTANT shall keep accurate minutes of all meetings and distribute a copy to all attendees within 3 days. See Task 4.5 (Horizontal/Vertical Master Design File) and Task 4.9 (Cross Section Design Files) for utility conflict location identification and adjustments.

7.10 Review Utility Markups & Work Schedules and Processing of Schedules & Agreements

The CONSULTANT shall review utility marked up plans and work schedules as they are received for content and coordinate review with the designer. Send color markups and schedules to the appropriate DEPARTMENT office(s) such as survey, geotechnical, drainage, structures, lighting, roadway, signals, utilities, landscape architecture, municipalities, maintaining agency, and District Traffic Operations for review and comment if required by the District. Coordinate with the District for execution. Distribute Executed Final Documents. Prepare Work Order for UAO(s). The CONSULTANT shall coordinate with the DUO the programming of necessary Work Program funds.

7.11 Utility Coordination/Follow-up

The CONSULTANT shall provide utility coordination and follow up. This includes follow-up, interpreting plans, and assisting the UAOs with completion of their work schedules and agreements. Includes phone calls, face-to-face meetings, etc., to motivate and ensure the UAO(s) complete and return the required documents in accordance with the project schedule. Ensure the resolution of all known conflicts. The CONSULTANT shall keep accurate minutes of all meetings and distribute a copy to all attendees. This task can be applied to all phases of the project.

7.12 Utility Constructability Review

The CONSULTANT shall review utility schedules against construction contract time, and phasing for compatibility. Coordinate with and obtain written concurrence from the construction office. See Task 4.5 (Horizontal/Vertical Master Design File) and Task 4.9 (Cross Section Design Files) for utility conflict identification and adjustments.

7.13 Additional Utility Services

The CONSULTANT shall provide additional utility services. Additional services will be determined when the services are required and requested. This item is not usually included in the scope at the time of negotiation. It is normally added as a supplemental agreement when the need is identified.

7.14 Processing Utility Work by Highway Contractor (UWHC)

This includes coordination of utility design effort between the DEPARTMENT and the UAO(s). The CONSULTANT shall conduct additional coordination meetings, prepare and process the agreements, review tabulation of quantities, perform UWHC constructability and

bidability review, review pay items, cost estimates and Technical Special Provisions (TSP) or Modified Special Provision (MSP) prepared by the UAO. This does not include utility the utility design effort. This item is not usually included in the scope at the time of negotiation. It is normally added as a supplemental agreement when the need is identified. Effort for the EOR is not included in this task, see Roadway Analysis Task Group 4.

7.15 Contract Plans to UAO(s)

If requested by the District, the CONSULTANT shall transmit the contract plans as processed for letting to the UAO(s). Transmittals to UAO(s) may be by certified mail, return receipt requested.

7.16 Certification/Close-Out

This includes hours for transmitting utility files to the DUO and preparation of the Utility Certification Letter. The CONSULTANT shall certify to the appropriate DEPARTMENT representative the following:

All utility negotiations (Full execution of each agreement, approved Utility Work Schedules, Technical Special Provisions or Modified Special Provisions written, etc.) have been completed with arrangements made for utility work to be undertaken and completed as required for proper coordination with the physical construction schedule.

OR

An on-site inspection was made and no utility work will be involved.

OR

Plans were sent to the Utility Companies/Agencies and no utility work is required.

7.17 Other Utilities

The CONSULTANT shall provide other utility services. This includes all efforts for a utility task not covered by an existing defined task. Required work will be defined in the scope and negotiated on a case-by-case basis.

8 ENVIRONMENTAL PERMITS and ENVIRONMENTAL CLEARANCES (AS NEEDED)

The CONSULTANT shall notify the DEPARTMENT Project Manager, Environmental Permit Coordinator, and other appropriate DEPARTMENT personnel in advance of all scheduled meetings with the regulatory agencies to allow a DEPARTMENT representative to attend. The CONSULTANT shall copy in the Project Manager and the Environmental Permit Coordinator on all permit related correspondence and meetings. The Consultant shall use current regulatory guidelines and policies for all permits required as identified in Section 2.4.

8.1 Preliminary Project Research

The CONSULTANT shall perform preliminary project research and shall be responsible for regulatory agency coordination to assure that design efforts are properly directed toward permit requirements. The research shall include but should not be limited to a review of the project's PD&E documents including the Environmental Document, Natural Resources Evaluation Report, and Cultural Resources Assessment Survey Report.

The CONSULTANT shall research any existing easements or other restrictions that may exist both within or adjacent to the proposed project boundary. Project research may include but should not be limited to review of available: federal, state, and local permit files and databases; and local government information including county and property appraiser data. The CONSULTANT shall determine if any Sovereign Submerged Lands easements need to be modified or acquired. Any applicable information will be shown on the plans as appropriate.

8.2 Field Work

8.2.1 Pond Site Alternatives:

The CONSULTANT shall review alternative pond sites as directed by the DEPARTMENT and information shall be included in the Pond Siting Report.

8.2.2 Establish Wetland Jurisdictional Lines and Assessments:

The CONSULTANT shall be responsible for, but not limited to, the following activities:

- Determine landward extent of wetlands and other surface waters as detailed in Rule Chapter 62-340, F.A.C., as ratified in Section 373.4211, F.S.; United States Army Corps of Engineers (USACE) Wetland Delineation Manual (Technical Report Y-87-1); Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Atlantic and Gulf Coastal Plain Region (ERD/EL TR-10-20).
- Collect all data and information necessary to determine the jurisdictional boundaries of wetlands and other surface waters as defined by the rules or regulations of each permitting agency processing a DEPARTMENT permit application for the project.
- Set seasonal high-water levels in adjacent wetlands with biological indicators
- Obtain a jurisdictional determination as defined by the rules or regulations of each permitting agency processing a DEPARTMENT permit application for the project.
- Prepare aerial maps showing the jurisdictional boundaries of wetlands and other surface waters. Aerial maps shall be reproducible, of a scale of 1"=400' or more detailed and be recent photography. The maps shall show the jurisdictional boundaries of each agency. Photo copies of aerials are not acceptable. When necessary, a wetland specific survey will be prepared by a registered surveyor and mapper. All surveyed jurisdictional boundaries are to be tied to the project's baseline of survey.
- Prepare a written assessment of the current condition and functional value of the wetlands and other surface waters. Prepare data in tabular form which includes the ID

number for each wetland (and other surface water, if necessary) impacted, size of wetland to be impacted, type of impact, and identify any wetland (by ID number and size) within the project limits that will not be impacted by the project.

- Prepare appropriate agency forms to obtain required permits. Forms may include but are not limited to the USACE "Wetland Determination Data Form - Atlantic and Gulf Coastal Plain Region"; the USACE "Approved Jurisdictional Determination Form"; Uniform Mitigation Assessment Method forms and/or project specific data forms.

8.2.3 Species Surveys:

The CONSULTANT shall conduct wildlife surveys as defined by rules or regulations of any permitting agency, or commenting agency that is processing a DEPARTMENT permit.

8.3 Agency Verification of Wetland Data

The CONSULTANT shall be responsible for verification of wetland and other surface water data identified in Section 8.2 and coordinating regulatory agency field reviews, including finalization of assessments and jurisdictional determinations with applicable agencies.

8.4 Complete and Submit All Required Permit Applications

The CONSULTANT shall collect the data and information necessary to prepare the permit applications and obtain the environmental permits required to construct the project as identified in the Project Description and as described in 8.4.1, 8.4.2, and 8.12 (Other Permits). The CONSULTANT shall prepare each permit application in accordance with the rules and/or regulations of the regulatory agency responsible for issuing a specific permit and/or authorization to perform work. The permit application packages must be approved by the DEPARTMENT prior to submittal to regulatory agencies.

The CONSULTANT will submit all permit applications, as directed by the DEPARTMENT, and be responsible for payment of all permit and public noticing fees.

8.4.1 Complete and Submit all Required Wetland Permit Applications:

The CONSULTANT shall prepare, complete, and submit required wetland permit (i.e. ERP, Section 404) application packages to the appropriate regulatory agencies. This includes, but is not limited to, applications submitted to WMDs and/or DEP, and USACE. The application package may include but is not limited to attachments (e.g. project location map, aerials, affidavit of ownership, pictures, additional technical analysis, etc.), a cover letter with project description as well as completion of applicable agency forms. The CONSULTANT shall prepare and respond to agency Requests for Additional Information (RAIs), including necessary revisions to the application package. All responses and completed application packages must be approved by the District Permit Coordinator prior to submittal to the regulatory agencies. Geotechnical permitting should also be prepared, submitted, and obtained.

8.4.2 Complete and Submit all Required Species Permit Applications:

The CONSULTANT shall prepare, complete and submit required species permit applications to the appropriate agencies. This includes federal and state protected species permit application packages as required. The work includes completion of application package (e.g. project location map, aerials, affidavit of ownership, pictures, additional technical analysis, etc.), and cover letter with project description as well as completion of applicable forms. The CONSULTANT shall respond to agency RAIs, including necessary revisions to the application package. All responses and completed applications must be approved by the District Permit Coordinator prior to submittal to the regulatory agency.

8.5 Coordinate and Review Dredge and Fill Sketches

The CONSULTANT shall review Dredge and Fill Detail sheets to ensure information on the sketch(es) meet the requirements of the regulatory agencies and are appropriate for environmental permit application submittal and acquisition. The CONSULTANT will also provide environmental data/information as needed to support the preparation of the Dredge and Fill sketches.

8.6 Prepare USCG Permit Application

8.7 Prepare Water Management District or Local Water Control District Right of Way Occupancy Permit Application

The CONSULTANT shall be responsible for the preparation of the ROW Occupancy permit application in accordance with the regulatory agency requirements. The CONSULTANT shall be responsible for acquiring the ROW Occupancy permit.

8.8 Prepare Coastal Construction Control Line (CCCL) Permit Application

The CONSULTANT shall be responsible for the preparation of the CCCL permit application and acquire the final "Notice to Proceed" authorization from the Florida Department of Environmental Protection (FDEP). Legal advertisements shall be published one time in a newspaper that meets the notification requirements of the FDEP.

8.9 Prepare USACE Section 408 Application to Alter a Civil Works Project

The CONSULTANT shall be responsible for the preparation of the Section 408 (33 USC 408) application and obtaining Section 408 permission.

8.10 Compensatory Mitigation Plan

If impacts cannot be avoided, the CONSULTANT shall prepare a mitigation plan to be included as a part of the application(s).

Prior to the development of mitigation alternatives, the CONSULTANT shall meet with the Project Manager and Environmental Permit Coordinator to determine the DEPARTMENT's

policies in proposing mitigation. The CONSULTANT shall develop a mitigation plan based upon the general guidelines provided by the DEPARTMENT.

The CONSULTANT will be directed by the DEPARTMENT to investigate the mitigation options that meet federal and state requirements in accordance with section 373.4137, F.S. Below are mitigation options:

- Purchase of mitigation credits from a mitigation bank
- Payment to DEP/WMD for mitigation services
- Monetary participation in offsite regional mitigation plans
- Creation/restoration of wetlands

In the event that physical creation or restoration is the only feasible alternative to offset wetland impacts, the CONSULTANT shall collect all of the data and information necessary to prepare mitigation plans acceptable to all permitting agencies and commenting agencies who are processing or reviewing a permit application for a DEPARTMENT project.

Prior to selection of a final creation/restoration mitigation site, the CONSULTANT will provide the following services in the development of a mitigation plan:

- Preliminary jurisdictional determination for each proposed site
- Selection of alternative sites
- Coordination of alternative sites with the DEPARTMENT/all environmental agencies
- Written narrative listing potential sites with justifications for both recommended and non-recommended sites.

8.11 Mitigation Coordination and Meetings

The CONSULTANT shall coordinate with DEPARTMENT personnel prior to approaching any environmental permitting or commenting agencies. Once a mitigation plan has been reviewed and approved by the DEPARTMENT, the CONSULTANT will be responsible for coordinating the proposed mitigation plan with the environmental agencies. The CONSULTANT will provide mitigation information needed to update the FDOT Environmental Impact Inventory.

8.12 Other Environmental Permits

Environmental Clearances, Re-evaluations, and Technical Support

8.13 Technical Support to the DEPARTMENT for Environmental Clearances and Re-evaluations (use when CONSULTANT provides technical support only)

The CONSULTANT shall provide engineering and environmental support for the DEPARTMENT to obtain environmental clearances for all changes to the project after the PD&E study was approved. These changes include but are not limited to pond or mitigation sites identified, land use or environmental changes, and major design changes.

8.13.1 NEPA or SEIR Re-evaluation

During the development of the final design plans, the CONSULTANT shall be responsible for coordinating with the District Project Manager to provide necessary engineering information required in the preparation of the re-evaluation by the DEPARTMENT. The preparation of environmental re-evaluations includes those as listed in Part 1, Chapter 13 of the DEPARTMENT's PD&E Manual: Right of Way, Design Change, and Construction Advertisement.

Re-evaluations will be completed in accordance with Part 1, Chapter 13 of the PD&E Manual. The CONSULTANT shall provide information to update the Project Commitment Record for incorporation into the re-evaluation.

It is the responsibility of the CONSULTANT to provide the District Project Manager with engineering information on major design changes including changes in typical section, roadway alignment, pond site selection, right of way requirements, bridge to box culvert, drainage, and traffic volumes that may affect noise models.

8.13.2 Archaeological and Historical Resources

The CONSULTANT shall provide necessary technical information to the District's Project Manager to analyze the impacts to all cultural and historical resources due to changes in the project in accordance with Part 2, Chapter 8 of the PD&E Manual.

8.13.3 Wetland Impact Analysis

The CONSULTANT shall provide necessary technical information to the District's Project Manager to analyze the impacts to wetlands and other surface waters in accordance with Part 2, Chapter 9 of the PD&E Manual due to changes in the project.

8.13.4 Essential Fish Habitat Impact Analysis

The CONSULTANT shall provide necessary technical information to the District's Project Manager to analyze the impacts to essential fish habitat in accordance Part 2, Chapter 17 of the PD&E Manual due to changes in the project.

8.13.5 Protected Species and Habitat Impact Analysis

The CONSULTANT shall provide necessary technical information to the District's Project Manager to analyze the impacts to all protected species and habitat in accordance with Part 2, Chapter 16 of the PD&E Manual due to changes in the project. The CONSULTANT shall perform the necessary analysis to complete agency consultation in accordance with Section 7 or Section 10 of the Endangered Species Act.

8.14 Preparation of Environmental Clearances and Re-evaluations (use when CONSULTANT prepares all documents associated with a re-evaluation)

The CONSULTANT shall prepare reports and clearances for all the changes to the project that occurred after the PD&E study was approved. These changes could include but are not limited to pond and/or mitigation sites identified, land use or environmental changes, and major design changes.

8.14.1 NEPA or SEIR Re-evaluation

During the development of the final design plans, the CONSULTANT shall be responsible for collecting the data and preparing a re-evaluation in accordance with Part 1, Chapter 13 of the PD&E Manual.

8.14.2 Archaeological and Historical Resources

The CONSULTANT shall collect data necessary to completely analyze the impacts, due to changes in the project or project area, to all cultural and historic resources, and prepare a Cultural Resource Assessment Survey Report, in accordance with Part 2, Chapter 8 of the PD&E Manual.

8.14.3 Wetland Impact Analysis

The CONSULTANT shall analyze the impacts to wetlands due to changes to the project and complete the wetlands section of a Natural Resources Evaluation Report, in accordance with Part 2, Chapter 9 of the PD&E Manual.

8.14.4 Essential Fish Habitat Impact Analysis

The CONSULTANT shall analyze the impacts to essential fish habitat due to changes to the project and complete the Essential Fish Habitat section of a Natural Resources Evaluation Report, in accordance with Part 2, Chapter 17 of the PD&E Manual.

8.14.5 Protected Species and Habitat Impact Analysis

The CONSULTANT shall collect data necessary to prepare the protected species and habitat section of the Natural Resources Evaluation Report, and analyze the impacts to protected species and habitat by the changes to the project, in accordance with Part 2, Chapter 16 of the PD&E Manual. The CONSULTANT shall perform the necessary analysis to complete agency consultation in accordance with Section 7 or Section 10 of the Endangered Species Act.

8.15 Contamination Impact Analysis

The CONSULTANT shall prepare Contamination Screening Evaluation for the project limits including stormwater ponds and floodplain compensation sites as described in Part 2, Chapter 20, of the PD&E Manual. The appropriate level of analysis and deliverable type will be approved by the DEPARTMENT's Project Manager and District Contamination Impact

Coordinator. The draft Level 1 Contamination Screening Evaluation document shall be submitted to the DEPARTMENT's Project Manager and District Contamination Impact Coordinator for review and final approval. The CONSULTANT shall include an evaluation of any new contamination impacts due to changes to the project from the PD&E design concept, if applicable, and any new discharges or new potential contamination impacts not evaluated in any previously completed Contamination Screening Evaluation. The project impacts, conclusions and recommendations, figures, tables and appendices will be provided in a Level I Contamination Screening Evaluation Report.

The DEPARTMENT will provide Level II assessment services. If contamination is identified within the limits of construction, the CONSULTANT shall coordinate with the District Contamination Impact Coordinator to properly mark identified contamination areas in the plans and develop specifications as appropriate.

8.16 Asbestos Survey

The Department will provide asbestos and metal based coatings survey services.

If asbestos or metal based coatings above threshold levels are found on the bridge(s), the CONSULTANT shall coordinate with the District Contamination Impact Coordinator to obtain plan notes, general notes, specifications, pay item notes, and Operation and Maintenance (O&M) plan for any asbestos to remain in place.

8.17 Technical Meetings

8.18 Quality Assurance/Quality Control

8.19 Supervision

8.20 Coordination

9 STRUCTURES - SUMMARY AND MISCELLANEOUS TASKS AND DRAWINGS (AS NEEDED)

The CONSULTANT shall analyze, design, and develop contract documents for all structures in accordance with applicable provisions as defined in Section 2.19, Provisions for Work. Individual tasks identified in Sections 9 through 18 are defined in the Staff Hour Estimation Handbook and within the provision defined in Section 2. 20, Provisions for Work. Contract documents shall display economical solutions for the given conditions.

The CONSULTANT shall provide Design Documentation to the DEPARTMENT with each submittal consisting of structural design calculations and other supporting documentation developed during the development of the plans. The design calculations submitted shall adequately address the complete design of all structural elements. These calculations shall be neatly and logically presented on digital media or, at the DEPARTMENT's request, on 8 ½"x11" paper and all sheets shall be numbered. The final design calculations shall be signed and sealed by a Florida-

licensed professional engineer. A cover sheet indexing the contents of the calculations shall be included and the engineer shall sign and seal that sheet. All computer programs and parameters used in the design calculations shall include sufficient backup information to facilitate the review task.

9.1 Key Sheet and Index of Drawings

9.2 Project Layout

9.3 General Notes and Bid Item Notes

9.4 Miscellaneous Common Details

9.5 Incorporate Report of Core Borings

9.6 Standard Plans- Bridges

9.7 Existing Bridge Plans

9.8 Quantities for EQ Report

9.9 Cost Estimate

9.10 Technical Special Provisions and Modified Special Provisions

9.11 Field Reviews

9.12 Technical Meetings

9.13 Quality Assurance/Quality Control

9.14 Independent Peer Review

9.15 Supervision

9.16 Coordination

10 STRUCTURES - BRIDGE DEVELOPMENT REPORT (AS NEEDED)

The Consultant shall prepare a Bridge Development Report (BDR). The BDR shall be submitted as part of the Phase I Roadway Submittal, General Requirements.

General Requirements

10.1 Bridge Geometry

10.2 Ship Impact Data Collection

10.3 Ship Impact Criteria

Superstructure Alternatives

10.4 Short-Span Concrete

10.5 Medium-Span Concrete

10.6 Long Span Concrete

10.7 Structural Steel

Foundation and Substructure Alternatives

10.8 Pier/Bent

10.9 Shallow Foundations / GRS Abutments

10.10 Deep Foundations

Movable Span

10.11 Data Collection and Design Criteria

10.12 Movable Span Geometrics and Clearances

10.13 Deck System Evaluation

10.14 Framing Plan Development

10.15 Main Girder Preliminary Design

10.16 Conceptual Span Balance/Counterweight

10.17 Support System Development

10.18 Drive Power Calculations

10.19 Drive System Development

10.20 Power and Control Development

10.21 Conceptual Pier Design

10.22 Foundation Analysis (FL PIER)

10.23 Tender Visibility Study

Other BDR Issues

10.24 Aesthetics

10.25 TTCP/Staged Construction Requirements

10.26 Constructability Requirements

10.27 Load Rating for Damaged/Widened Structures

10.28 Quantity and Cost Estimates

10.29 Quantity and Cost Estimates - Movable Span

10.30 Wall Type Justification

Report Preparation

10.31 Exhibits

10.32 Exhibits - Movable Span

10.33 Report Preparation

10.34 Report Preparation - Movable Span

10.35 BDR Submittal Package

Preliminary Plans

When ONLY Phase I plans are final deliverable, use Task Nos. as shown for applicable bridge types for project Activities 12 thru 16. Staffhours to be negotiated and scaled appropriately.

11 STRUCTURES - TEMPORARY BRIDGE (N/A)

12 STRUCTURES - SHORT SPAN CONCRETE BRIDGE (N/A)

13 STRUCTURES - MEDIUM SPAN CONCRETE BRIDGE (AS NEEDED)

The CONSULTANT shall prepare plans for Medium Span Concrete Bridge(s) at the location(s) specified in Section 2.5.

General Layout Design and Plans

13.1 Overall Bridge Final Geometry

13.2 Expansion/Contraction Analysis

13.3 General Plan and Elevation

13.4 Construction Staging

13.5 Approach Slab Plan and Details

13.6 Miscellaneous Details

End Bent Design and Plans

13.7 End Bent Geometry

13.8 Wingwall Design and Geometry

13.9 End Bent Structural Design

13.10 End Bent Plan and Elevation

13.11 End Bent Details

Intermediate Bent Design and Plans

13.12 Bent Geometry

13.13 Bent Stability Analysis

13.14 Bent Structural Design

13.15 Bent Plan and Elevation

13.16 Bent Details

Pier Design and Plans

13.17 Pier Geometry

13.18 Pier Stability Analysis

13.19 Pier Structural Design

13.20 Pier Plan and Elevation

13.21 Pier Details

Miscellaneous Substructure Design and Plans

13.22 Foundation Layout

Superstructure Deck Design and Plans

- 13.23 Finish Grade Elevation (FGE) Calculation**
- 13.24 Finish Grade Elevations**
- 13.25 Bridge Deck Design**
- 13.26 Bridge Deck Reinforcing and Concrete Quantities**
- 13.27 Diaphragm Design**
- 13.28 Superstructure Plan**
- 13.29 Superstructure Section**
- 13.30 Miscellaneous Superstructure Details**
 - Reinforcing Bar Lists
- 13.31 Preparation of Reinforcing Bar List**
 - Continuous Concrete Girder Design
- 13.32 Section Properties**
- 13.33 Material Properties**
- 13.34 Construction Sequence**
- 13.35 Tendon Layouts**
- 13.36 Live Load Analysis**
- 13.37 Temperature Gradient**
- 13.38 Time Dependent Analysis**
- 13.39 Stress Summary**
- 13.40 Ultimate Moments**
- 13.41 Ultimate Shear**
- 13.42 Construction Loading**
- 13.43 Framing Plan**
- 13.44 Girder Elevation, including Grouting Plan and Vent Locations**
- 13.45 Girder Details**
- 13.46 Erection Sequence**
- 13.47 Splice Details**
- 13.48 Girder Deflections and Camber**

Simple Span Concrete Design

13.49 Prestressed Beam

13.50 Prestressed Beam Schedules

13.51 Framing Plan

Beam Stability

13.52 Beam/Girder Stability

Bearing

13.53 Bearing Pad and Bearing Plate Design

13.54 Bearing Pad and Bearing Plate Details

Load Rating

13.55 Load Ratings

14 STRUCTURES - STRUCTURAL STEEL BRIDGE (N/A)

15 STRUCTURES - SEGMENTAL CONCRETE BRIDGE (N/A)

16 STRUCTURES - MOVABLE SPAN (N/A)

17 STRUCTURES - RETAINING WALLS (AS NEEDED)

The CONSULTANT shall prepare plans for Retaining Wall(s) as specified in Section 2.5.

General Requirements

17.1 Key Sheet

17.2 Horizontal Wall Geometry

Permanent Proprietary Walls

17.3 Vertical Wall Geometry

17.4 Semi-Standard Drawings

17.5 Wall Plan and Elevations (Control Drawings)

17.6 Details

Temporary Proprietary Walls

17.7 Vertical Wall Geometry

17.8 Semi-Standard Drawings

17.9 Wall Plan and Elevations (Control Drawings)

17.10 Details

Cast-In-Place Retaining Walls

17.11 Design

17.12 Vertical Wall Geometry

17.13 General Notes

17.14 Wall Plan and Elevations (Control Drawings)

17.15 Sections and Details

17.16 Reinforcing Bar List

Other Retaining Walls and Bulkheads

17.17 Design

17.18 Vertical Wall Geometry

17.19 General Notes, Tables and Miscellaneous Details

17.20 Wall Plan and Elevations

17.21 Details

18 STRUCTURES – MISCELLANEOUS (AS NEEDED)

The CONSULTANT shall prepare plans for Miscellaneous Structure(s) as specified in Section 2.5.

Concrete Box Culverts

18.1 Concrete Box Culverts

18.2 Concrete Box Culverts Extensions

18.3 Concrete Box Culvert Data Table Plan Sheets

18.4 Concrete Box Culvert Special Details Plan Sheets

Strain Poles

18.5 Steel Strain Poles

18.6 Concrete Strain Poles

18.7 Strain Pole Data Table Plan Sheets

18.8 Strain Pole Special Details Plan Sheets

Mast Arms

18.9 Mast Arms

18.10 Mast Arms Data Table Plan Sheets

18.11 Mast Arms Special Details Plan Sheets

Overhead/Cantilever Sign Structure

18.12 Cantilever Sign Structures

18.13 Overhead Span Sign Structures

18.14 Special (Long Span) Overhead Sign Structures

18.15 Monotube Overhead Sign Structure

18.16 Bridge Mounted Signs (Attached to Superstructure)

18.17 Overhead/Cantilever Sign Structures Data Table Plan Sheets

18.18 Overhead/Cantilever Sign Structures Special Details Plan Sheets

High Mast Lighting

18.19 Non-Standard High Mast Lighting Structures

18.20 High Mast Lighting Special Details Plan Sheets

Noise Barrier Walls (Ground Mount)

18.21 Horizontal Wall Geometry

18.22 Vertical Wall Geometry

18.23 Summary of Quantities - Aesthetic Requirements

18.24 Control Drawings

18.25 Design of Noise Barrier Walls Covered by Standards

18.26 Design of Noise Barrier Walls not Covered by Standards

18.27 Aesthetic Details

Special Structures

18.28 Fender System

18.29 Fender System Access

18.30 Special Structures

18.31 Other Structures

18.32 Condition Evaluation of Signal and Sign Structures, and High Mast Light Poles

18.33 Condition Evaluation of Signal and Sign Structures, and High Mast Light Poles (No As built or Design Plans Available)

18.34 Analytical Evaluation of Signal and Sign Structures, and High Mast Light Poles

18.35 Ancillary Structures Report

19 SIGNING AND PAVEMENT MARKING ANALYSIS (AS NEEDED)

The CONSULTANT shall analyze and document Signing and Pavement Markings Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

19.1 Traffic Data Analysis

The CONSULTANT shall review the approved preliminary engineering report, typical section package, traffic technical memorandum and proposed geometric design alignment to identify proposed sign placements and roadway markings. Perform queue analysis.

19.2 No Passing Zone Study

The CONSULTANT shall perform all effort required for field data collection, and investigation in accordance with the DEPARTMENT's Manual on Uniform Traffic Studies.

The CONSULTANT shall submit the signed and sealed report to the DEPARTMENT for review and approval.

19.3 Signing and Pavement Marking Master Design File

The CONSULTANT shall prepare the Signing & Marking Design file to include all necessary design elements and all associated reference files.

19.4 Multi-Post Sign Support Calculations

The CONSULTANT shall determine the appropriate column size from the DEPARTMENT's Multi-Post Sign Program(s).

19.5 Sign Panel Design Analysis

Establish sign layout, letter size and series for non-standard signs.

19.6 Sign Lighting/Electrical Calculations

The CONSULTANT shall analyze and document Lighting/Electrical Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

The CONSULTANT shall prepare a photometric analysis to be submitted as part of the Lighting Design Analysis Report. An analysis shall be provided for each new and/or modified sign panel which requires lighting.

The Consultant shall submit voltage drop calculations and load analysis for each new and/or modified sign panel which requires lighting.

19.7 Quantities for EQ Report

The CONSULTANT shall determine pay items and quantities and the supporting documentation.

19.8 Cost Estimate

19.9 Technical Special Provisions and Modified Special Provisions

19.10 Other Signing and Pavement Marking Analysis

19.11 Field Reviews

19.12 Technical Meetings

19.13 Quality Assurance/Quality Control

19.14 Independent Peer Review

19.15 Supervision

19.16 Coordination

20 SIGNING AND PAVEMENT MARKING PLANS (AS NEEDED)

The CONSULTANT shall prepare a set of Signing and Pavement Marking Plans in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums that includes the following.

20.1 Key Sheet

20.2 General Notes/Pay Item Notes

20.3 Project Layout

20.4 Plan Sheet

20.5 Typical Details

20.6 Guide Sign Work Sheets

20.7 Traffic Monitoring Site

20.8 Cross Sections

20.9 Special Service Point Details

20.10 Special Details

20.11 Interim Standards

20.12 Quality Assurance/Quality Control

The CONSULTANT shall be responsible for the professional quality, technical accuracy and coordination of traffic design drawings, specifications and other services furnished by the CONSULTANT under this contract.

The CONSULTANT shall provide a Quality Control Plan that describes the procedures to be utilized to verify, independently check, and review all design drawings, specifications and other services prepared as a part of the contract. The CONSULTANT shall describe how the checking and review processes are to be documented to verify that the required procedures were followed. The Quality Control Plan may be one utilized by the CONSULTANT as part of their normal operation or it may be one specifically designed for this project.

20.13 Supervision

21 SIGNALIZATION ANALYSIS (AS NEEDED)

The CONSULTANT shall analyze and document Signalization Analysis Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

21.1 Traffic Data Collection

The CONSULTANT shall perform all effort required for traffic data collection, including crash reports, 24 hr. machine counts, 8 hr. turning movement counts, 7 day machine counts, and speed & delay studies.

21.2 Traffic Data Analysis

The CONSULTANT shall determine signal operation plan, intersection geometry, local signal timings, pre-emption phasing & timings, forecasting traffic, and intersection analysis run.

21.3 Signal Warrant Study

21.4 Systems Timings

The CONSULTANT shall determine proper coordination timing plans including splits, force offs, offsets, and preparation of Time Space Diagram.

21.5 Reference and Master Signalization Design File

The CONSULTANT shall prepare the Signalization Design file to include all necessary design elements and all associated reference files.

21.6 Reference and Master Interconnect Communication Design File

The CONSULTANT shall prepare the Interconnect Communication Design file to include all necessary design elements and all associated reference files.

21.7 Overhead Street Name Sign Design

The CONSULTANT shall design Signal Mounted Overhead Street Name signs.

21.8 Pole Elevation Analysis

21.9 Traffic Signal Operation Report

21.10 Quantities for EQ Report

The CONSULTANT shall determine pay items and quantities and the supporting documentation.

21.11 Cost Estimate

21.12 Technical Special Provisions and Modified Special Provisions

21.13 Other Signalization Analysis

21.14 Field Reviews

The CONSULTANT shall collect information from the maintaining agencies and conduct a field review. The review should include, but is not limited to, the following:

- Existing Signal and Pedestrian Phasing
- Controller Make, Model, Capabilities and Condition/Age
- Condition of Signal Structure(s)
- Type of Detection as Compared with Current District Standards
- Interconnect Media
- Controller Timing Data

21.15 Technical Meetings

21.16 Quality Assurance/Quality Control

The CONSULTANT shall be responsible for the professional quality, technical accuracy and coordination of traffic design drawings, specifications and other services furnished by the CONSULTANT under this contract.

The CONSULTANT shall provide a Quality Control Plan that describes the procedures to be utilized to verify, independently check, and review all design drawings, specifications and other services prepared as a part of the contract. The CONSULTANT shall describe how the checking and review processes are to be documented to verify that the required procedures were followed. The Quality Control Plan may be one utilized by the CONSULTANT as part of their normal operation or it may be one specifically designed for this project.

21.17 Independent Peer Review

21.18 Supervision

21.19 Coordination

22 SIGNALIZATION PLANS (AS NEEDED)

The CONSULTANT shall prepare a set of Signalization Plans in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums, which includes the following:

- 22.1 Key Sheet**
- 22.2 General Notes/Pay Item Notes**
- 22.3 Plan Sheet**
- 22.4 Interconnect Plans**
- 22.5 Traffic Monitoring Site**
- 22.6 Guide Sign Worksheet**
- 22.7 Special Details**
- 22.8 Special Service Point Details**
- 22.9 Mast Arm/Monotube Tabulation Sheet**
- 22.10 Strain Pole Schedule**
- 22.11 TTCP Signal (Temporary)**
- 22.12 Temporary Detection Sheet**
- 22.13 Utility Conflict Sheet**
- 22.14 Interim Standards**
- 22.15 Quality Assurance/Quality Control**

The CONSULTANT shall be responsible for the professional quality, technical accuracy and coordination of traffic design drawings, specifications and other services furnished by the CONSULTANT under this contract.

The CONSULTANT shall provide a Quality Control Plan that describes the procedures to be utilized to verify, independently check, and review all design drawings, specifications and other services prepared as a part of the contract. The CONSULTANT shall describe how the checking and review processes are to be documented to verify that the required procedures were followed. The Quality Control Plan may be one utilized by the CONSULTANT as part of their normal operation or it may be one specifically designed for this project.

22.16 Supervision

23 LIGHTING ANALYSIS (AS NEEDED)

The CONSULTANT shall analyze and document Lighting Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

23.1 Lighting Justification Report

The CONSULTANT shall prepare a Lighting Justification Report. The report shall be submitted under a separate cover with the Phase I plans submittal, titled Lighting Justification Report. The report shall provide analyses for mainlines, interchanges, and arterial roads and shall include all back-up data such that the report stands on its own. Back up data shall include current ADT's, general crash data average cost from the Florida Highway Safety Improvement Manual, crash details data from the last three years, and preliminary lighting calculations.

The report shall address warrants to determine if lighting warrants are met, and shall include a benefit-cost analysis to determine if lighting is justified. The report shall include calculations for the night-to-day crash ratio as well as a table summarizing the day-time and the night-time crashes. The report shall follow the procedures outlined in the FDOT Manual on Uniform Traffic Studies (MUTS) manual which utilize ADT, Three Year Crash Data, night/day crash ratio, percentage of night ADT, etc.

23.2 Lighting Design Analysis Report (LDAR)

The CONSULTANT shall prepare a Preliminary Lighting Design Analysis Report in accordance with the requirements of the FDOT Design Manual. The report shall be submitted under a separate cover with the Phase II plans submittal. After approval of the preliminary report, the CONSULTANT shall submit a revised report for each submittal.

23.3 Voltage Drop Calculations

The CONSULTANT shall submit voltage drop calculations showing the equation or equations used along with the number of luminaires per circuit, the length of each circuit, the size conductor or conductors used and their ohm resistance values. The voltage drop incurred on each circuit (total volts and percentage of drop) shall be calculated, and all work necessary to calculate the voltage drop values for each circuit should be presented in such a manner as to be duplicated by the District.

The Voltage Drop Calculations shall be submitted as part of the Lighting Design Analysis Report.

23.4 FDEP Coordination and Report

23.5 Reference and Master Design Files

The CONSULTANT shall prepare the Lighting Design file to include all necessary design elements and all associated reference files.

23.6 Temporary Highway Lighting

The CONSULTANT shall develop a Temporary Highway Lighting design and, when required, a Temporary Highway Lighting design file. The Temporary Highway Lighting design must account for all phases of the TTCF and includes the analysis, calculations, and placement of luminaires, supports, conductors, conduits, pull boxes, and electrical power service.

23.7 Design Documentation

The CONSULTANT shall submit a Design Documentation with each plans submittal under a separate cover and not part of the roadway documentation book. At a minimum, the design documentation shall include:

- Phase submittal checklist.
- Structural calculations for special conventional pole concrete foundations.
- Correspondence with the power company concerning new electrical service.

23.8 Quantities for EQ Report

The CONSULTANT shall determine pay items and quantities and the supporting documentation.

23.9 Cost Estimate

23.10 Technical Special Provisions and Modified Special Provisions

23.11 Other Lighting Analysis

23.12 Field Reviews

The CONSULTANT shall collect information from the maintaining agencies and conduct a field review. The review should include but is not limited to the following:

- Existing Lighting Equipment
- Load Center, Capabilities and Condition/Age
- Condition of Lighting Structure(s)
- Verification of horizontal clearances
- Verification of breakaway requirements

23.13 Technical Meetings

23.14 Quality Assurance/Quality Control

23.15 Independent Peer Review

23.16 Supervision

23.17 Coordination

24 LIGHTING PLANS (AS NEEDED)

The CONSULTANT shall prepare a set of Lighting Plans in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

24.1 Key Sheet

24.2 General Notes/Pay Item Notes

24.3 Pole Data, Legend & Criteria

24.4 Service Point Details

24.5 Project Layout

24.6 Plan Sheet

24.7 Special Details

24.8 Temporary Highway Lighting Detail Sheets

24.9 Temporary Highway Lighting Plan Sheets

24.10 Interim Standards

24.11 Quality Assurance/Quality Control

The CONSULTANT shall be responsible for the professional quality, technical accuracy and coordination of traffic design drawings, specifications and other services furnished by the CONSULTANT under this contract.

The CONSULTANT shall provide a Quality Control Plan that describes the procedures to be utilized to verify, independently check, and review all design drawings, specifications and other services prepared as a part of the contract. The CONSULTANT shall describe how the checking and review processes are to be documented to verify that the required procedures were followed. The Quality Control Plan may be one utilized by the CONSULTANT as part of their normal operation or it may be one specifically designed for this project.

24.12 Supervision

25 LANDSCAPE ANALYSIS (N/A)

26 LANDSCAPE PLANS (N/A)

27 SURVEY (AS NEEDED)

The CONSULTANT shall perform survey tasks in accordance with all applicable statutes, manuals, guidelines, standards, handbooks, procedures, and current design memoranda.

The CONSULTANT shall submit all survey notes and computations to document the surveys. All field survey work shall be recorded in approved media and submitted to the DEPARTMENT. Field

books submitted to the DEPARTMENT must be of an approved type. The field books shall be certified by the surveyor in responsible charge of work being performed before the final product is submitted.

The survey notes shall include documentation of decisions reached from meetings, telephone conversations or site visits. All like work (such as bench lines, reference points, etc.) shall be recorded contiguously. The DEPARTMENT may not accept field survey radial locations of section corners, platted subdivision lot and block corners, alignment control points, alignment control reference points and certified section corner references. The DEPARTMENT may instead require that these points be surveyed by true line, traverse or parallel offset.

27.1 Horizontal Project Control (HPC)

Establish or recover HPC, for the purpose of establishing horizontal control on the Florida State Plane Coordinate System or datum approved by the District Surveyor (DS) or District Location Surveyor (DLS); may include primary or secondary control points. Includes analysis and processing of all field collected data, and preparation of forms.

27.2 Vertical Project Control (VPC)

Establish or recover VPC, for the purpose of establishing vertical control on datum approved by the District Surveyor (DS) or the District Location Surveyor (DLS).; may include primary or secondary vertical control points. Includes analysis and processing of all field collected data, and preparation of forms.

27.3 Alignment and/or Existing Right of Way (R/W) Lines

Establish, recover or re-establish project alignment. Also includes analysis and processing of all field collected data, existing maps, and/or reports for identifying mainline, ramp, offset, or secondary alignments. Depict alignment and/or existing R/W lines (in required format) per DEPARTMENT R/W Maps, platted or dedicated rights of way.

27.4 Aerial Targets

Place, locate, and maintain required aerial targets and/or photo identifiable points. Includes analysis and processing of all field collected data, existing maps, and/or reports. Placement of the targets will be at the discretion of the aerial firm.

27.5 Reference Points

Reference Horizontal Project Control (HPC) points, project alignment, vertical control points, section, ¼ section, center of section corners and General Land Office (G.L.O.) corners as required.

27.6 Topography/Digital Terrain Model (DTM) (3D)

Locate all above ground features and improvements for the limits of the project by collecting the required data for the purpose of creating a DTM with sufficient density. Shoot all break

lines, high and low points. Effort includes field edits, analysis and processing of all field collected data, existing maps, and/or reports.

27.7 Planimetric (2D)

Locate all above ground features and improvements. Deliver in appropriate electronic format. Effort includes field edits, analysis and processing of all field collected data, existing maps, and/or reports.

27.8 Roadway Cross Sections/Profiles

Perform cross sections or profiles. May include analysis and processing of all field-collected data for comparison with DTM.

27.9 Side Street Surveys

Refer to tasks of this document as applicable.

27.10 Underground Utilities

Designation includes 2-dimensional collection of existing utilities and selected 3-dimensional verification as needed for designation. Location includes non-destructive excavation to determine size, type and location of existing utility, as necessary for final 3-dimensional verification. Survey includes collection of data on points as needed for designates and locates. Includes analysis and processing of all field collected data, and delivery of all appropriate electronic files.

27.11 Outfall Survey

Locate all above ground features and improvements for the limits of the project by collecting the required data for the purpose of a DTM. Survey with sufficient density of shots. Shoot all break lines, high and low points. Includes field edits, analysis and processing of all field collected data, existing maps, and/or reports.

27.12 Drainage Survey

Locate underground data (XYZ, pipe size, type, condition and flow line) that relates to above ground data. Includes field edits, analysis and processing of all field collected data, existing maps, and/or reports.

27.13 Bridge Survey (Minor/Major)

Locate required above ground features and improvements for the limits of the bridge. Includes field edits, analysis and processing of all field collected data, existing maps, and/or reports.

27.14 Channel Survey

Locate all topographic features and improvements for the limits of the project by collecting the required data. Includes field edits, analysis and processing of all field collected data, maps, and/or reports.

27.15 Pond Site Survey

Refer to tasks of this document as applicable.

27.16 Mitigation Survey

Refer to tasks of this document as applicable.

27.17 Jurisdiction Line Survey

Perform field location (2-dimensional) of jurisdiction limits as defined by respective authorities, also includes field edits, analysis and processing of all field collected data, preparation of reports.

27.18 Geotechnical Support

Perform 3-dimensional (X,Y,Z) field location, or stakeout, of boring sites established by geotechnical engineer. Includes field edits, analysis and processing of all field collected data and/or reports.

27.19 Sectional/Grant Survey

Perform field location/placement of section corners, 1/4 section corners, and fractional corners where pertinent. Includes analysis and processing of all field-collected data and/or reports.

27.20 Subdivision Location

Survey all existing recorded subdivision/condominium boundaries, tracts, units, phases, blocks, street R/W lines, common areas. Includes analysis and processing of all field collected data and/or reports. If unrecorded subdivision is on file in the public records of the subject county, tie existing monumentation of the beginning and end of unrecorded subdivision.

27.21 Maintained R/W

Perform field location (2-dimensional) of maintained R/W limits as defined by respective authorities, if needed. Also includes field edits, analysis and processing of all field collected data, preparation of reports.

27.22 Boundary Survey

Perform boundary survey as defined by DEPARTMENT standards. Includes analysis and processing of all field-collected data, preparation of reports.

27.23 Water Boundary Survey

Perform Mean High Water, Ordinary High Water and Safe Upland Line surveys as required by DEPARTMENT standards.

27.24 Right of Way Staking, Parcel / Right of Way Line

Perform field staking and calculations of existing/proposed R/W lines for on-site review purposes.

27.25 Right of Way Monumentation

Set R/W monumentation as depicted on final R/W maps for corridor and water retention areas.

27.26 Line Cutting

Perform all efforts required to clear vegetation from the line of sight.

27.27 Work Zone Safety

Provide work zone as required by DEPARTMENT standards.

27.28 Vegetation Survey (N/A)

27.29 Tree Survey

Locate individual trees or palms within the project limits.

27.30 Miscellaneous Surveys

Refer to tasks of this document, as applicable, to perform surveys not described herein. The percent for Supplemental will be determined at negotiations. This item can only be used if authorized in writing by the District Surveyor (DS), District Location Surveyor (DLS) or their representative.

27.31 Supplemental Surveys

Supplemental survey days and hours are to be approved in advance by DS or DLS. Refer to tasks of this document, as applicable, to perform surveys not described herein.

27.32 Document Research

Perform research of documentation to support field and office efforts involving surveying and mapping.

27.33 Field Review

Perform verification of the field conditions as related to the collected survey data.

27.34 Technical Meetings

Attend meetings as required and negotiated by the Surveying and Mapping Department.

27.35 Quality Assurance/Quality Control (QA/QC)

Establish and implement a QA/QC plan. Also includes subconsultant review, response to comments and any resolution meetings if required, preparation of submittals for review, etc.

27.36 Supervision

Perform all activities required to supervise and coordinate project. These activities must be performed by the project supervisor, a Florida P.S.M. or their delegate as approved by the District Surveying Office.

27.37 Coordination

Coordinate survey activities with other disciplines. These activities must be performed by the project supervisor, a Florida P.S.M. or their delegate as approved by the District Surveying Office.

28 PHOTOGRAMMETRY (N/A)

29 MAPPING (AS NEEDED)

The CONSULTANT will be responsible for the preparation of control survey maps, right of way maps, maintenance maps, sketches, other miscellaneous survey maps, and legal descriptions as required for this project in accordance with all applicable DEPARTMENT Manuals, Procedures, Handbooks, District specific requirements, and Florida Statutes. All maps, surveys and legal descriptions will be prepared under the direction of a Florida Professional Surveyor and Mapper (PSM) to DEPARTMENT size and format requirements utilizing DEPARTMENT approved software, and will be designed to provide a high degree of uniformity and maximum readability. The CONSULTANT will submit maps, legal descriptions, quality assurance check prints, checklists, electronic media files and any other documents as required for this project to the DEPARTMENT for review at stages of completion as negotiated.

Master CADD File

29.1 Alignment

29.2 Section and 1/4 Section Lines

29.3 Subdivisions / Property Lines

29.4 Existing Right of Way

29.5 Topography

29.6 Parent Tract Properties and Existing Easements

29.7 Proposed Right of Way Requirements

The ENGINEER OF RECORD (EOR) will provide the proposed requirements. The PSM is responsible for calculating the final geometry. Notification of Final Right of Way Requirements along with the purpose and duration of all easements will be specified in writing.

29.8 Limits of Construction

The limits of construction DGN file as provided by the EOR will be imported or referenced to the master CADD file. Additional labeling will be added as required. The PSM is required to advise the EOR of any noted discrepancies between the limits of construction line and the existing/proposed right of way lines, and for making adjustments as needed when a resolution is determined.

29.9 Jurisdictional/Agency Lines

These lines may include, but are not limited to, jurisdictional, wetland, water boundaries, and city/county limit lines.

Sheet Files

29.10 Control Survey Cover Sheet

29.11 Control Survey Key Sheet

29.12 Control Survey Detail Sheet

29.13 Right of Way Map Cover Sheet

29.14 Right of Way Map Key Sheet

29.15 Right of Way Map Detail Sheet

29.16 Maintenance Map Cover Sheet (N/A)

29.17 Maintenance Map Key Sheet (N/A)

29.18 Maintenance Map Detail Sheet (N/A)

29.19 Reference Point Sheet

This sheet(s) will be included with the Control Survey Map, Right of Way Map and Maintenance Map.

29.20 Project Control Sheet

This sheet depicts the baseline, the benchmarks, the primary and secondary control points and their reference points including the type of material used for each point, their XYZ coordinates, scale factors and convergence angles. This sheet(s) may be included with the Control Survey Map, Right of Way Map and Maintenance Map.

29.21 Table of Ownerships Sheet

Miscellaneous Surveys and Sketches

29.22 Parcel Sketches

29.23 TITF Sketches

29.24 Other Specific Purpose Survey(s)

29.25 Boundary Survey(s) Map

29.26 Right of Way Monumentation Map

29.27 Title Search Map

29.28 Title Search Report

29.29 Legal Descriptions

29.30 Final Map/Plans Comparison

The PSM will perform a comparison of the final right of way maps with the available construction plans to review the correctness of the type of parcel to be acquired and the stations/offsets to the required right of way. The PSM will coordinate with the EOR to resolve any conflicts or discrepancies and provide documentation of the review.

29.31 Field Reviews

29.32 Technical Meetings

29.33 Quality Assurance/Quality Control

29.34 Supervision

29.35 Coordination

29.36 Supplemental Mapping

This task is to cover efforts resulting from major design and/or development changes after 60% map development that affect the right of way requirements/parent tract property lines and may include any number of tasks. Request and approval to utilize the Supplemental Mapping hours will be in writing and approved by the District Right of Way Surveyor prior to any work being done under this task.

30 TERRESTRIAL MOBILE LiDAR (N/A)

31 ARCHITECTURE DEVELOPMENT (N/A)

32 NOISE BARRIERS IMPACT DESIGN ASSESSMENT IN THE DESIGN PHASE (AS NEEDED)

The CONSULTANT shall fulfill the commitments resulting from the traffic noise analysis and noise barrier evaluation performed during the Project Development and Environment (PD&E) Phase, as directed and clarified by the DEPARTMENT.

The noise analysis shall be performed in accordance with the FDOT's Noise Policy (Part 2, Chapter 17 of the FDOT's PD&E Manual) and the FDOT's Traffic Noise Modeling and Analysis Guidelines. The noise analysis and noise abatement evaluation shall be performed by or supervised/reviewed by a person(s) who has attended the Department's Traffic Noise Analysis training course or has attended and successfully completed the National Highway Institute's Highway Traffic Noise Course (FHWA-NHI-142051). The Federal Highway Administration (FHWA) approved noise model, the Traffic Noise Model (TNM) Version 2.5 (or most current version) shall be used for the noise analysis, unless otherwise directed by the DEPARTMENT.

32.1 Noise Analysis

The CONSULTANT shall review the preferred PD&E alternative to identify any design changes that would require a reanalysis of traffic noise. Coordination will be held with the District Environmental Management Office, prior to initiating any reanalysis, to discuss possible effects of design changes on the validity of in the noise study performed during PD&E.

The CONSULTANT shall perform a land use review to identify noise sensitive sites that may have received a building permit subsequent to the PD&E noise study but prior to the Date of Public Knowledge (DPK), or to identify areas where the land use may have changed or is subject to change. New noise sensitive sites meeting DPK requirements that were not considered during the PD&E phase will be subject to a traffic noise analysis to be performed by the CONSULTANT. Additionally, noise sensitive sites analyzed in the PD&E phase may have to be re-analyzed if affected by design changes.

The CONSULTANT shall review any commitments made during the PD&E phase regarding possible traffic noise impacts to special use locations. Analysis of special use locations shall be performed using the DEPARTMENT's "A Method to Determine Reasonableness and Feasibility of Noise Abatement at Special Use Locations" document and shall be coordinated with the District Environmental Management Office.

The CONSULTANT shall review the commitments made during the PD&E phase regarding noise barrier concepts determined to be potentially feasible and reasonable. The

CONSULTANT will update the analysis of feasibility and reasonableness for noise barriers recommended for further consideration during the design phase and for any additional noise barriers required, using design information (e.g., profile data, horizontal alignment data, etc.) and incorporate into the analysis any new conditions or additional costs related to noise barrier construction that have been identified during design. A design phase noise analysis will be performed at any additional locations required (based on DPK requirements or roadway design changes). Additional survey may also be required at proposed barrier locations.

Changes to, or fulfillment of, the original noise abatement commitments made during PD&E shall be documented in a Noise Study Report (NSR) Addendum to be prepared by the CONSULTANT in coordination with the District Environmental Management Office. A copy of the final NSR Addendum shall be provided to the District Environmental Management Office.

Traffic Data: The CONSULTANT shall review the traffic data obtained during the PD&E phase to determine if the data remains valid for design phase reanalysis. If the traffic data is no longer valid, the CONSULTANT shall provide to the noise analyst the following data for each road segment (i.e. intersection to intersection) for the design year with the proposed improvements to the road:

- Level of Service C (LOS C) directional volumes
- Demand peak hour volumes (peak and off-peak directions)
- Posted speed
- Percentage of heavy trucks (HT) in the design hour
- Percentage of medium trucks (MT) in the design hour
- Percentage of buses in the design hour
- Percentage of motorcycles (MC) in the design hour

Except for LOS C volumes, the data above shall also be provided for all interchange/highway ramps. The District Noise Specialist may also identify cross streets for which the same data is necessary. (i.e., a cross street for which noise sensitive sites are in close proximity to the project). The CONSULTANT shall contact the District Noise Specialist for direction on the format to be used for providing the traffic data and any requirements regarding approval of the data prior to its use for noise analysis. The traffic data to be used in the noise analysis must be generated by a qualified traffic engineer/planner who works for the DEPARTMENT or is a DEPARTMENT consultant.

32.2 Noise Barrier Evaluation

The CONSULTANT will present the data along with recommendations to the DEPARTMENT for selection of the noise barrier's locations, barriers heights and lengths to be incorporated into the design plans. These recommendations shall consider the noise barrier feasibility and reasonableness.

An evaluation of proposed noise barriers will be performed to identify any engineering conflicts or constraints. The CONSULTANT will be responsible for documenting any resolutions to engineering conflicts or issues that require modification to or preclude construction of a noise barrier. At a minimum, the engineering review will consider the following:

- Right of way needs including access rights (air, light, view, ingress/egress, outdoor advertising conflicts)
- Limited access issues
- Necessary construction and maintenance easements
- Safety issues (e.g., line of sight)
- Maintenance issues
- Structural and vegetative restrictions within easement
- Utility conflicts
- Drainage issues
- Environmental issues
- Other criteria as applicable

The CONSULTANT shall re-analyze noise barrier(s) for feasibility and reasonableness and re-establish barrier height and length if design constraints require alteration in a barrier's location or dimensions.

After reestablishing the recommended height and length of the barrier(s), the CONSULTANT shall coordinate with design engineers and the District Planning and Environmental Office to include the barrier(s) on the design plans. In addition, the CONSULTANT will present a memo to the DEPARTMENT Project Manager containing a recommendation for selection of the barrier height and length to be carried forward for public input. This recommendation shall consider amount of noise reduction provided, engineering constraints and cost (reasonableness). In addition, the CONSULTANT will also consider the overall visual appearance in relation to the existing and proposed site conditions. This includes smoothing the profile along the top of a noise barrier to the extent possible while minimizing any loss in the amount of noise reduction provided and extending the ends of a noise barrier to cover additional receivers. Extending the ends of a noise barrier will not exceed the cost criteria and will only be performed when it is appropriate and in the public interest.

32.3 Public Involvement

If noise barriers are determined to be feasible and cost reasonable, the CONSULTANT shall carry out the public involvement and surveys necessary to report to the DEPARTMENT whether or not the majority of the impacted and/or benefited receptors desire the construction of a noise barrier. Input shall also be obtained from the public regarding barrier aesthetics (color and texture) on one or both sides of the barrier. The CONSULTANT shall be responsible for coordinating with local government officials.

As a minimum, the following tasks shall be completed by the CONSULTANT for public involvement purposes:

- Identification of impacted and/or benefited property owners
- Identification of renters and non-residing property owners (for a property that may be rented)
- Preparation of a mailing list (property owners, renters and non-residing property owners)
- Preparation of a summary package (including an information letter, aerial showing the noise barrier location and a survey form to document the recipients position to be sent to property owners, and occupants/non-residing property owners informing them of the proposed noise barrier
- If necessary, preparation of additional mailings and/or door-to-door/telephone surveys until a majority decision is obtained or until directed by the District Noise Specialist
- Tallying of survey results
- Noise barrier aesthetics coordination
- Public meetings coordination (including arranging the meeting location, advertisements, displays, etc.)
- Responding to public inquiries on an individual basis in coordination with the DEPARTMENT.

The CONSULTANT shall bring to the attention of the DEPARTMENT unforeseen conditions and issues which are relevant to the project decision. Other than noise barrier length, height and location, the CONSULTANT shall abstain from indicating preferences for any of the barrier options prior to or during contact with the property owners unless specifically requested to do so by the DEPARTMENT. Following the public involvement process, the CONSULTANT shall produce a final noise barrier recommendation that identifies the starting and ending points for all noise barriers, the top elevation(s), and the aesthetic elements to be provided (e.g. - color, texture, graphics).

32.4 Outdoor Advertising Identification

The CONSULTANT shall identify potential noise barriers that may block the view of an existing lawfully erected sign that is governed by and conforms to state and federal requirements for land use, size, height and spacing consistent with the requirements of Florida Statute (FS) 479.25 and the FDOT Noise Policy (Part 2, Chapter 17 of the PD&E Manual). The CONSULTANT shall notify the Department's Project Manager of a potential noise barrier(s) that may affect the visibility of a legally permitted outdoor advertising sign. Resolution of the potential conflict shall be documented in the NSR and included in the environmental document.

32.5 Noise Study Report (NSR) Addendum

The results of noise barrier evaluations performed by the CONSULTANT shall be documented in the NSR Addendum (in accordance with Chapter 264 of the FDOT Design Manual (FDM))

and shall include the results of the computer modeling (electronically), public involvement activities and final noise abatement commitments.

32.6 Technical Meetings

Prior to proceeding with the noise barrier analysis, the CONSULTANT shall discuss and coordinate with the appropriate District Project Manager and the District Environmental Management Office staff. The purpose of this discussion will be for the DEPARTMENT to provide the CONSULTANT with all pertinent project information and to confirm the methodologies to be used to conduct the noise analysis. This meeting is mandatory and should occur after the Notice to Proceed is given to the CONSULTANT. It is the responsibility of the CONSULTANT to undertake the necessary action (e.g. phone calls, meetings, correspondence, etc.) to ensure that District Project Manager and the District Environmental Management Office staff is kept informed of the noise analysis efforts so that these tasks are accomplished in a manner that will enhance the overall success of the project.

32.7 Quality Assurance/Quality Control

QA/QC reviews will be performed for all NSR Addendums submitted to the DEPARTMENT. Documentation of the QA/QC will be provided to the District Project Manager.

The CONSULTANT shall ensure that the noise barrier(s) location(s), length, height and aesthetics as shown on the final design plans are consistent with the results of the noise barrier evaluation and recommendation documented in the original NSR and/or the NSR Addendum.

32.8 Supervision

32.9 Coordination

33 INTELLIGENT TRANSPORTATION SYSTEMS ANALYSIS (N/A)

34 INTELLIGENT TRANSPORTATION SYSTEMS PLANS (N/A)

35 GEOTECHNICAL (AS NEEDED)

The CONSULTANT shall, for each project, be responsible for a complete geotechnical investigation. All work performed by the CONSULTANT shall be in accordance with DEPARTMENT standards, or as otherwise directed by the District Geotechnical Engineer. The District Geotechnical Engineer will make interpretations and changes regarding geotechnical standards, policies and procedures and provide guidance to the CONSULTANT.

Before beginning each phase of investigation and after the Notice to Proceed is given, the CONSULTANT shall submit an investigation plan for approval and meet with the

DEPARTMENT's Geotechnical Engineer or representative to review the project scope and DEPARTMENT requirements. The investigation plan shall include, but not be limited to, the proposed boring locations and depths, and all existing geotechnical information from available sources to generally describe the surface and subsurface conditions of the project site. Additional meetings may be required to plan any additional field efforts, review plans, resolve plans/report comments, resolve responses to comments, and/or any other meetings necessary to facilitate the project.

The CONSULTANT shall notify the DEPARTMENT in adequate time to schedule a representative to attend all related meetings and field activities.

35.1 Document Collection and Review

CONSULTANT will review printed literature including topographic maps, county agricultural maps, aerial photography (including historic photos), ground water resources, geology bulletins, potentiometric maps, pile driving records, historic construction records and other geotechnical related resources. Prior to field reconnaissance, CONSULTANT shall review U.S.G.S., S.C.S. and potentiometric maps, and identify areas with problematic soil and groundwater conditions.

Roadway

The CONSULTANT shall be responsible for coordination of all geotechnical related field work activities. The CONSULTANT shall retain all samples until acceptance of Phase IV plans. Rock cores shall be retained as directed in writing by the District Geotechnical Engineer.

Obtain pavement cores as directed in writing by the District Geotechnical Engineer.

If required by the District Geotechnical Engineer, a preliminary roadway exploration shall be performed before the Phase I plans submittal. The preliminary roadway exploration will be performed and results provided to the Engineer of Record to assist in setting roadway grades and locating potential problem areas. The preliminary roadway exploration shall be performed as directed in writing by the District Geotechnical Engineer.

CONSULTANT shall perform specialized field-testing as required by project needs and as directed in writing by the District Geotechnical Engineer.

All laboratory testing and classification will be performed in accordance with applicable DEPARTMENT standards, ASTM Standards or AASHTO Standards, unless otherwise specified in the Contract Documents.

35.2 Develop Detailed Boring Location Plan

Develop a detailed boring location plan. Meet with DEPARTMENT Geotechnical Project Manager for boring plan approval. If the drilling program expects to encounter artesian conditions, the CONSULTANT shall submit a methodology(s) for plugging the borehole to the DEPARTMENT for approval prior to commencing with the boring program.

35.3 Stake Borings/Utility Clearance

Stake borings and obtain utility clearance.

35.4 Muck Probing

Probe standing water and surficial muck in a detailed pattern sufficient for determining removal limits to be shown in the Plans.

35.5 Coordinate and Develop TTCP for Field Investigation

Coordinate and develop Temporary Traffic Control Plan (TTCP). All work zone traffic control will be performed in accordance with the DEPARTMENT's Standard Plans Index 102 series.

35.6 Drilling Access Permits

Obtain all State, County, City, and Water Management District permits for performing geotechnical borings, as needed.

35.7 Property Clearances

Notify property tenants in person of drilling and field activities, if applicable. Written notification to property owners/tenants is the responsibility of the DEPARTMENT's Project Manager.

35.8 Groundwater Monitoring

Monitor groundwater, using piezometers.

35.9 LBR / Resilient Modulus Sampling

Collect appropriate samples for Limerock Bearing Ratio (LBR) testing. Deliver Resilient Modulus samples to the District Materials Office or the State Materials Office in Gainesville, as directed by the DEPARTMENT.

35.10 Coordination of Field Work

Coordinate all field work required to provide geotechnical data for the project.

35.11 Soil and Rock Classification - Roadway

Refine soil profiles recorded in the field, based on results of laboratory testing.

35.12 Design LBR

Determine design LBR values from the 90% and mean methods when LBR testing is required by the DEPARTMENT.

35.13 Laboratory Data

Tabulate laboratory test results for inclusion in the geotechnical report, the report of tests sheet (Roadway Soil Survey Sheet), and for any necessary calculations and analyses.

35.14 Seasonal High Water Table

Review the encountered ground water levels and estimate seasonal high ground water levels. Estimate seasonal low ground water levels, if requested.

35.15 Parameters for Water Retention Areas

Calculate parameters for water retention areas, exfiltration trenches, and/or swales.

35.16 Delineate Limits of Unsuitable Material

Delineate limits of unsuitable material(s) in both horizontal and vertical directions. Assist the Engineer of Record with detailing these limits on the cross-sections. If requested, prepare a plan view of the limits of unsuitable material.

35.17 Electronic Files for Cross-Sections

Create electronic files of boring data for cross-sections.

35.18 Embankment Settlement and Stability

Estimate the total magnitude and time rate of embankment settlements. Calculate the factor of safety against slope stability failure.

35.19 Monitor Existing Structures

Provide Roadway EOR guidance on the radius to review existing structures for monitoring.

Optional services (may be negotiated at a later date if needed): Identify existing structures in need of settlement, vibration and/or groundwater monitoring by the contractor during construction and coordinate with the EOR and structural engineer (when applicable) to develop mitigation strategies. When there is risk of damage to the structure or facility, provide recommendations in the geotechnical report addressing project specific needs and coordinate those locations with the EOR. See FDM Chapter 307 and Chapter 9 of the Soils and Foundations Handbook.

35.20 Stormwater Volume Recovery and/or Background Seepage Analysis

Perform stormwater volume recovery analysis as directed by the DEPARTMENT.

35.21 Geotechnical Recommendations

Provide geotechnical recommendations regarding the proposed roadway construction project including the following: description of the site/alignment, design recommendations and discussion of any special considerations (e.g. removal of unsuitable material, consolidation of

weak soils, estimated settlement time/amount, groundwater control, high groundwater conditions relative to pavement base, etc.) Evaluate and recommend types of geosynthetics and properties for various applications, as required.

35.22 Pavement Condition Survey and Pavement Evaluation Report

If a pavement evaluation is performed, submit the report in accordance with Section 3.2 of the Materials Manual: Flexible Pavement Coring and Evaluation. Enter all core information into the Pavement Coring and Reporting (PCR) system.

35.23 Preliminary Roadway Report

If a preliminary roadway investigation is performed, submit a preliminary roadway report before the Phase I plans submittal. The purpose of the preliminary roadway report will be to assist in setting road grades and locating potential problems.

- Copies of U.S.G.S. and S.C.S. maps with project limits shown.
- A report of tests sheet that summarizes the laboratory test results, the soil stratification (i.e. soils grouped into layers of similar materials) and construction recommendations relative to Standard Plans Indices 120-001 and 120-002.
- The results of all tasks discussed in all previous sections regarding data interpretation and analysis.
- An appendix that contains stratified soil boring profiles, laboratory test data sheets, sample embankment settlement and stability calculations, design LBR calculation/graphs, and other pertinent calculations.
- The CONSULTANT will respond in writing to any changes and/or comments from the DEPARTMENT and submit any responses and revised reports.

35.24 Final Report

The Final Roadway Report shall include the following:

- Copies of U.S.G.S. and S.C.S. maps with project limits shown.
- A report of tests sheet that summarizes the laboratory test results, the soil stratification (i.e. soils grouped into layers of similar materials) and construction recommendations relative to Standard Plans Indices 120-001 and 120-002.
- The results of all tasks discussed in all previous sections regarding data interpretation and analysis.
- An appendix that contains stratified soil boring profiles, laboratory test data sheets, sample embankment settlement and stability calculations, design LBR calculation/graphs, and other pertinent calculations.
- The CONSULTANT will respond in writing to any changes and/or comments from the DEPARTMENT and submit any responses and revised reports.

35.25 Auger Boring Drafting

Draft auger borings as directed by the DEPARTMENT.

35.26 SPT Boring Drafting

Draft SPT borings as directed by the DEPARTMENT.

Structures

The CONSULTANT shall be responsible for coordination of all geotechnical related fieldwork activities. The CONSULTANT shall retain all samples until acceptance of Phase IV plans. Rock cores shall be retained as directed in writing by the District Geotechnical Engineer.

CONSULTANT shall perform specialized field-testing as required by needs of project and as directed in writing by the District Geotechnical Engineer.

All laboratory testing and classification will be performed in accordance with applicable DEPARTMENT standards, ASTM Standards or AASHTO Standards, unless otherwise specified in the Contract Documents.

The staff hour tasks for high embankment fills and structural foundations for bridges, box culverts, walls, high-mast lighting, overhead signs, mast arm signals, strain poles, buildings, and other structures include the following:

35.27 Develop Detailed Boring Location Plan

Develop a detailed boring location plan. Meet with DEPARTMENT Geotechnical Project Manager for boring plan approval. If the drilling program expects to encounter artesian conditions, the CONSULTANT shall submit a methodology(s) for plugging the borehole to the DEPARTMENT for approval prior to commencing with the boring program.

35.28 Stake Borings/Utility Clearance

Stake borings and obtain utility clearance.

35.29 Coordinate and Develop TTCP for Field Investigation

Coordinate and develop TTCP plan. All work zone traffic control will be performed in accordance with the DEPARTMENT's Standard Plans Index 102 series.

35.30 Drilling Access Permits

Obtain all State, County, City, and Water Management District permits for performing geotechnical borings, as needed.

35.31 Property Clearances

Notify property tenants in person of drilling and field activities, if applicable. Written notification to property owners/tenants is the responsibility of the DEPARTMENT's Project Manager.

35.32 Collection of Corrosion Samples

Collect corrosion samples for determination of environmental classifications.

35.33 Coordination of Field Work

Coordinate all field work required to provide geotechnical data for the project.

35.34 Soil and Rock Classification - Structures

Soil profiles recorded in the field should be refined based on the results of laboratory testing.

35.35 Tabulation of Laboratory Data

Laboratory test results should be tabulated for inclusion in the geotechnical report and for the necessary calculations and analyses.

35.36 Estimate Design Groundwater Level for Structures

Review encountered groundwater levels, estimate seasonal high groundwater levels, and evaluate groundwater levels for structure design.

35.37 Selection of Foundation Alternatives (BDR)

Evaluation and selection of foundation alternative, including the following:

- GRS-IBS
- Spread footings
- Prestressed concrete piling - various sizes
- Steel H- piles
- Steel pipe piles
- Drilled shafts
- Foundation analyses shall be performed using approved DEPARTMENT methods. Assist in selection of the most economical, feasible foundation alternative.

35.38 Detailed Analysis of Selected Foundation Alternate(s)

Detailed analysis and basis for the selected foundation alternative. Foundation analyses shall be performed using approved DEPARTMENT methods and shall include:

- GRS-IBS (including the parameters identified in the Instructions for Developmental Design Standard D6025 to be provided by the Geotechnical Engineer)

- Spread footings (including soil bearing capacity, minimum footing width, and minimum embedment depth).
- For pile and drilled shaft foundations, provide graphs of ultimate axial soil resistance versus tip elevations. Calculate scour resistance and/or downdrag (negative skin friction), if applicable.
- CONSULTANT shall assist the Engineer of Record in preparing the Pile Data Table (including test pile lengths, scour resistance, downdrag, minimum tip elevation, etc.)
- Provide the design soil profile(s), which include the soil model/type of each layer and all soil-engineering properties required for the Engineer of Record to run the FBPIer computer program. Review lateral analysis of selected foundation for geotechnical compatibility.
- Estimated maximum driving resistance anticipated for pile foundations.
- Provide settlement analysis.

35.39 Bridge Construction and Testing Recommendations

Provide construction and testing recommendations including potential constructability problems.

35.40 Lateral Load Analysis (Optional)

Perform lateral load analyses as directed by the DEPARTMENT.

35.41 Walls

Provide the design soil profile(s), which include the soil model/type of each layer and all soil engineering properties required by the Engineer of Record for conventional wall analyses and recommendations. Review wall design for geotechnical compatibility and constructability.

Evaluate the external stability of conventional retaining walls and retained earth wall systems. For retained earth wall systems, calculate and provide minimum soil reinforcement lengths versus wall heights, and soil parameters assumed in analysis. Estimate differential and total (long term and short term) settlements.

Provide wall construction recommendations.

35.42 Sheet Pile Wall Analysis (Optional)

Analyze sheet pile walls as directed by the DEPARTMENT.

35.43 Design Soil Parameters for Signs, Signals, High Mast Lights, and Strain Poles and Geotechnical Recommendations

- Provide the design soil profile(s) that include the soil model/type of each layer and all soil properties required by the Engineer of Record for foundation design. Review design for geotechnical compatibility and constructability.

35.44 Box Culvert Analysis

- Provide the design soil profile(s) that include the soil model/type of each layer and all soil properties required by the Engineer of Record for foundation design. Review design for geotechnical compatibility and constructability.
- Provide lateral earth pressure coefficients.
- Provide box culvert construction and design recommendations.
- Estimate differential and total (long term and short term) settlements.
- Evaluate wingwall stability.

35.45 Preliminary Report - BDR

The preliminary structures report shall contain the following discussions as appropriate for the assigned project:

- Copies of U.S.G.S. and S.C.S. maps with project limits shown.
- Summary of structure background data, S.C.S., U.S.G.S., geologic and potentiometric data.
- The results of all tasks discussed in all previous sections regarding data interpretation and analysis).
- Recommendations for foundation installation, or other site preparation soils-related construction considerations with plan sheets as necessary.
- Any special provisions required for construction that are not addressed in the DEPARTMENT's Standard specification.
- An Appendix which includes SPT and CPT boring/sounding profiles, data from any specialized field tests, engineering analysis, notes/sample calculations, sheets showing ultimate bearing capacity curves versus elevation for piles and drilled shafts, a complete FHWA check list, pile driving records (if available), and any other pertinent information.

35.46 Final Report - Bridge and Associated Walls

The final structures report shall include the following:

- Copies of U.S.G.S. and S.C.S. maps with project limits shown.
- Summary of structure background data, S.C.S., U.S.G.S., geologic and potentiometric data.
- The results of all tasks discussed in all previous sections regarding data interpretation and analysis.
- Recommendations for foundation installation, or other site preparation soils-related construction considerations with plan sheets as necessary.
- Any special provisions required for construction that are not addressed in the DEPARTMENT's Standard specification.
- An Appendix which includes SPT and CPT boring/sounding profiles, data from any specialized field tests, engineering analysis, notes/sample calculations, sheets showing

ultimate bearing capacity curves versus elevation for piles and drilled shafts, a complete FHWA check list, pile driving records (if available), and any other pertinent information.

35.47 Final Reports - Signs, Signals, Box Culvert, Walls, and High Mast Lights

The final reports shall include the following:

- Copies of U.S.G.S. and S.C.S. maps with project limits shown.
- Summary of structure background data, S.C.S., U.S.G.S., geologic and potentiometric data.
- The results of all tasks discussed in all previous sections regarding data interpretation and analysis).
- Recommendations for foundation installation, or other site preparation soils-related construction considerations with plan sheets as necessary.
- Any special provisions required for construction that are not addressed in the DEPARTMENT's Standard specification.
- An Appendix which includes SPT and CPT boring/sounding profiles, data from any specialized field tests, engineering analysis, notes/sample calculations, sheets showing ultimate bearing capacity curves versus elevation for piles and drilled shafts, a complete FHWA check list, pile driving records (if available), and any other pertinent information.

Final reports will incorporate comments from the DEPARTMENT and contain any additional field or laboratory test results, recommended foundation alternatives along with design parameters and special provisions for the contract plans. These reports will be submitted to the District Geotechnical Engineer for review prior to project completion. After review by the District Geotechnical Engineer, the reports will be submitted to the District Geotechnical Engineer in final form and will include the following:

- All original plan sheets (11" x 17")
- One set of all plan and specification documents, in electronic format, according to DEPARTMENT requirements
- Two sets of record prints
- Six sets of any special provisions
- All reference and support documentation used in preparation of contract plans package

Additional final reports (up to four), aside from stated above, may be needed and requested for the DEPARTMENT's Project Manager and other disciplines.

The final reports, special provisions, as well as record prints, will be signed and sealed by a Professional Engineer licensed in the State of Florida.

Draft the detailed boring/sounding standard sheet, including environmental classification, results of laboratory testing, and specialized construction requirements, for inclusion in final plans.

35.48 SPT Boring Drafting

Prepare a complete set of drawings to include all SPT borings, auger borings and other pertinent soils information in the plans. Include these drawings in the Final Geotechnical Report. Draft borings, location map, S.C.S. map and U.S.D.A. map as directed by the DEPARTMENT. Soil symbols must be consistent with those presented in the latest Florida Department of Transportation Soils and Foundations Handbook.

35.49 Other Geotechnical

Other geotechnical effort specifically required for the project as determined by the Department, and included in the geotechnical upset limit.

35.50 Technical Special Provisions and Modified Special Provisions

35.51 Field Reviews

Identify and note surface soil and rock conditions, surface water conditions and locations, and preliminary utility conflicts. Observe and note nearby structures and foundation types.

35.52 Technical Meetings

35.53 Quality Assurance/Quality Control

35.54 Supervision

35.55 Coordination

36 3D MODELING (AS NEEDED)

The CONSULTANT shall analyze and document Roadway Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

The CONSULTANT shall deliver all master design files, 3D surface design models, and all supporting digital files for the development of plans as required in the FDOT CADD Manual.

The CONSULTANT shall prepare a 3D model using the latest FDOT software in accordance with the FDOT CADD Manual. Includes all efforts required for developing files for 3D deliverables supporting automated machine guidance for design models. This includes importing survey data and creation of existing 3D surface features and models, and developing proposed corridor models with necessary detail of features to depict the proposed project in 3D to comply with the FDOT CADD Manual.

The CONSULTANT shall add detail to the corridor and design model for 3D design. Includes many elements that contribute to this including but not limited to slope transitions, typical section transitions, changes in pavement depth, berms, swales/ditches, and other feature transitions. Extra corridor structure leads to extra assemblies, extra targeting, etc.

The CONSULTANT shall create an accurate roadway design model which includes modeling the intersections.

The CONSULTANT shall submit .dgn files associated with the 3D Model and their respective components.

36.1 Phase I 3D Design Model

The CONSULTANT shall prepare, submit and present for approval by the DEPARTMENT, Phase I 3D interactive model, comprised of, but not limited to: Existing features (pavement, shoulders, sidewalk, curb/gutter, utilities-if required per scope, drainage - if required per scope) and proposed corridor(s).

36.2 Phase II 3D Design Model

The CONSULTANT shall prepare, submit and present for approval by the DEPARTMENT, Phase II 3D model, comprised of, but not limited to: Modification of the Phase I model to update the model to comply with changes based on the Phase I review comments and to include the addition of ponds, floodplain compensation sites, retaining walls, barrier walls, guardrail terminals, cross overs, gore areas, side street connections, roundabouts, and driveways.

[List optional services to be included, e.g. Curb Ramps, Closed Drainage Network, Bridge Modeling, Bridge Abutment, Overhead sign post/structures with foundation, Toll gantry and overhead DMS structures with foundation, proposed utilities (pressure pipe/gravity), etc.].

36.3 Phase III 3D Design Model

The CONSULTANT shall prepare, submit and present for approval by the DEPARTMENT, Phase III 3D model and deliverables files for review, comprised of, but not limited to: Modification of the Phase II model to update the model to comply with changes based on the Phase II review comments and to further refine areas of transition between templates, detailed grading areas, bridge approaches and end bents, median noses, shoulder transition areas, retaining walls, barrier walls and guardrail.

36.4 Final 3D Model Design

The CONSULTANT shall prepare for approval by DEPARTMENT, the Phase IV 3D model, comprised of, but not limited to: Modification of the Phase III model to update the model to comply with changes based on the phase III review comments and to accurately generate, export and otherwise prepare the final 3D deliverable files as described in the FDOT CADD Manual.

36.5 Cross Section Design Files

The CONSULTANT shall establish and develop cross section design files in accordance with the FDOT CADD manual and FDOT Design Manual. Includes all work required to establish and utilize intelligent/automated methods for creating cross sections including determining the locations for which all cross sections will be shown, existing and proposed features, cross

section refinement, placement of utilities and drainage, soil boxes, R/W lines, earthwork calculations, and other required labeling.

36.6 Template and Assembly Development (Optional)

The CONSULTANT shall prepare for approval by DEPARTMENT, project specific templates/assemblies needed to develop the features required to deliver the 3D model.

36.7 Quality Assurance/Quality Control

36.8 Supervision

36.9 Coordination

37 PROJECT REQUIREMENTS

37.1 Liaison Office

The DEPARTMENT and the CONSULTANT will designate a Liaison Office and a Project Manager who shall be the representative of their respective organizations for the Project. While it is expected the CONSULTANT shall seek and receive advice from various state, regional, and local agencies, the final direction on all matters of this project remain with the DEPARTMENT Project Manager.

37.2 Key Personnel

The CONSULTANT's work shall be performed and directed by the key personnel identified in the proposal presentations by the CONSULTANT. Any changes in the indicated personnel shall be subject to review and approval by DEPARTMENT.

37.3 Progress Reporting

The CONSULTANT shall meet with the DEPARTMENT as required and shall provide a written monthly progress report with approved schedule, schedule status, and payout curve or by using the earned value method that describe the work performed on each task. The report will include assessing project risk through monthly documentation of identifying and updating the risk category and approach for monitoring those tasks. Invoices shall be submitted after the DEPARTMENT approves the monthly progress report and the payout curve or with earned value analysis. The Project Manager will make judgment on whether work of sufficient quality and quantity has been accomplished by comparing the reported percent complete against actual work accomplished.

37.4 Correspondence

Copies of all written correspondence between the CONSULTANT and any party pertaining specifically to this contract shall be provided to the DEPARTMENT for their records within one (1) week of the receipt or mailing of said correspondence.

37.5 Professional Endorsement

The CONSULTANT shall have a Licensed Professional Engineer in the State of Florida sign and seal all reports, documents, Technical Special Provisions and Modified Special Provisions, and plans as required by DEPARTMENT standards.

37.6 Computer Automation

The project will be developed utilizing Computer Aided Drafting and Design (CADD) systems. The DEPARTMENT makes available software to help assure quality and conformance with policy and procedures regarding CADD. It is the responsibility of the CONSULTANT to meet the requirements in the FDOT CADD Manual. The CONSULTANT shall submit final documents and files as described therein.

37.7 Coordination with Other Consultants

The CONSULTANT is to coordinate his work with any and all adjacent and integral consultants so as to effect complete and homogenous plans and specifications for the project(s) described herein.

37.8 Optional Services

At the DEPARTMENT's option, the CONSULTANT may be requested to provide optional services. The fee for these services shall be negotiated in accordance with the terms detailed in Exhibit B, Method of Compensation, for a fair, competitive and reasonable cost, considering the scope and complexity of the project(s). Additional services may be authorized by Letter of Authorization or supplemental amendment in accordance with paragraph 2.00 of the Standard Consultant Agreement. The additional services may include Construction Assistance, Review of Shop Drawings, Final Bridge Load Rating, update (Category II) bridge plans electronically (CADD) for the Final "As-Built" conditions, based on documents provided by the DEPARTMENT (CADD Services Only) or other Services as required.

38 INVOICING LIMITS

Payment for the work accomplished shall be in accordance with Method of Compensation of this contract. Invoices shall be submitted to the DEPARTMENT, in a format prescribed by the DEPARTMENT. The DEPARTMENT Project Manager and the CONSULTANT shall monitor the cumulative invoiced billings to ensure the reasonableness of the billings compared to the project schedule and the work accomplished and accepted by the DEPARTMENT.

The CONSULTANT shall provide a list of key events and the associated total percentage of work considered to be complete at each event. This list shall be used to control invoicing. Payments will not be made that exceed the percentage of work for any event until those events have actually occurred and the results are acceptable to the DEPARTMENT.