

January 24, 2023

EXHIBIT A



SCOPE OF SERVICES

FOR

Financial Project ID: 444316-1-32-03

FDOT District 1

DIST/ST-WIDE

Table of Contents

1 PURPOSE.....	5
2 PROJECT DESCRIPTION.....	7
3 PROJECT COMMON AND PROJECT GENERAL TASKS	17
4 ROADWAY ANALYSIS (TBD)	24
5 ROADWAY PLANS (TBD)	28
6a DRAINAGE ANALYSIS	30
6b DRAINAGE PLANS	33
7 UTILITIES.....	33
8 ENVIRONMENTAL PERMITS and ENVIRONMENTAL CLEARANCES	37
9 STRUCTURES - SUMMARY AND MISCELLANEOUS TASKS AND DRAWINGS	41
10 STRUCTURES - BRIDGE DEVELOPMENT REPORT	42
11 STRUCTURES - TEMPORARY BRIDGE (N/A).....	44
12 STRUCTURES - SHORT SPAN CONCRETE BRIDGE	44
13 STRUCTURES - MEDIUM SPAN CONCRETE BRIDGE (N/A)	45
14 STRUCTURES - STRUCTURAL STEEL BRIDGE (N/A).....	45
15 STRUCTURES - SEGMENTAL CONCRETE BRIDGE (N/A).....	45
16 STRUCTURES - MOVABLE SPAN (N/A)	45
17 STRUCTURES - RETAINING WALLS	45
18 STRUCTURES - MISCELLANEOUS	47
19 SIGNING AND PAVEMENT MARKING ANALYSIS.....	48
20 SIGNING AND PAVEMENT MARKING PLANS.....	50
21 SIGNALIZATION ANALYSIS.....	50
22 SIGNALIZATION PLANS.....	52
23 LIGHTING ANALYSIS.....	53
24 LIGHTING PLANS.....	55
25 LANDSCAPE ANALYSIS	56
26 LANDSCAPE PLANS	58
27 SURVEY.....	59
28 PHOTOGRAMMETRY	63
29 MAPPING.....	65
30 TERRESTRIAL MOBILE LiDAR.....	67
31 ARCHITECTURE DEVELOPMENT (N/A)	69
32 NOISE BARRIERS IMPACT DESIGN ASSESSMENT IN THE DESIGN PHASE (N/A). 70	
33 INTELLIGENT TRANSPORTATION SYSTEMS ANALYSIS	70

34 INTELLIGENT TRANSPORTATION SYSTEMS PLANS	84
35 GEOTECHNICAL (N/A)	90
36 3D MODELING	90
37 PROJECT REQUIREMENTS	92
38 INVOICING LIMITS	93
1 PURPOSE	5
2 PROJECT DESCRIPTION	7
3 PROJECT COMMON AND PROJECT GENERAL TASKS	17
4 ROADWAY ANALYSIS (TBD)	24
5 ROADWAY PLANS (TBD)	28
6a DRAINAGE ANALYSIS	30
6b DRAINAGE PLANS	33
7 UTILITIES	33
8 ENVIRONMENTAL PERMITS and ENVIRONMENTAL CLEARANCES	37
9 STRUCTURES - SUMMARY AND MISCELLANEOUS TASKS AND DRAWINGS	41
10 STRUCTURES - BRIDGE DEVELOPMENT REPORT	42
11 STRUCTURES - TEMPORARY BRIDGE (N/A)	44
12 STRUCTURES - SHORT SPAN CONCRETE BRIDGE	44
13 STRUCTURES - MEDIUM SPAN CONCRETE BRIDGE (N/A)	45
14 STRUCTURES - STRUCTURAL STEEL BRIDGE (N/A)	45
15 STRUCTURES - SEGMENTAL CONCRETE BRIDGE (N/A)	45
16 STRUCTURES - MOVABLE SPAN (N/A)	45
17 STRUCTURES - RETAINING WALLS	45
18 STRUCTURES - MISCELLANEOUS	47
19 SIGNING AND PAVEMENT MARKING ANALYSIS	48
20 SIGNING AND PAVEMENT MARKING PLANS	50
21 SIGNALIZATION ANALYSIS	50
22 SIGNALIZATION PLANS	52
23 LIGHTING ANALYSIS	53
24 LIGHTING PLANS	55
25 LANDSCAPE ANALYSIS	56
26 LANDSCAPE PLANS	58
27 SURVEY	59
28 PHOTOGRAMMETRY	63

29 MAPPING.....	65
30 TERRESTRIAL MOBILE LiDAR.....	67
31 ARCHITECTURE DEVELOPMENT (N/A)	69
32 NOISE BARRIERS IMPACT DESIGN ASSESSMENT IN THE DESIGN PHASE (N/A) .	70
33 INTELLIGENT TRANSPORTATION SYSTEMS ANALYSIS	70
34 INTELLIGENT TRANSPORTATION SYSTEMS PLANS	84
35 GEOTECHNICAL (N/A)	90
36 3D MODELING	90
37 PROJECT REQUIREMENTS.....	92
38 INVOICING LIMITS	93

SCOPE OF SERVICES FOR CONSULTING ENGINEERING SERVICES

HIGHWAY AND BRIDGE/STRUCTURAL DESIGN

This Exhibit forms an integral part of the agreement between the State of Florida Department of Transportation (hereinafter referred to as the DEPARTMENT or FDOT) and [*Consultant Name or leave blank until CONSULTANT is selected*] (hereinafter referred to as the CONSULTANT) relative to the transportation facility described as follows:

Financial Project ID: 444316-1-32-03

Related Financial Project ID(s): [*Related FM Numbers*]

Federal Aid Project No.:

Roadway: Not Available.

Project Description: RESURFACING - CSC

Bridge No(s).:

- ***TBD***

Railroad Crossing No.: ***TBD***

Context Classification:

- [*List applicable classification(s)*]

TBD

1 PURPOSE

The purpose of this Exhibit is to describe the scope of work and the responsibilities of the CONSULTANT and the DEPARTMENT in connection with the design and preparation of a complete set of construction contract documents and incidental engineering services, as necessary, for improvements to the transportation facility described herein.

- Major work groups include:
 - ***3.1 - Minor Highway Design***
- Minor work groups include:
 - ***4.1.1 - Miscellaneous Structures***
 - ***4.1.2 - Minor Bridge Design***
 - ***6.1 - Traffic Engineering Studies***
 - ***6.2 - Traffic Signal Timing***
 - ***6.3.1 - Intelligent Transportation Systems Analysis and Design***
 - ***6.3.2 - Intelligent Transportation Systems Implementation***
 - ***6.3.3 - Intelligent Transportation Traffic Engineering Systems Communications***
 - ***7.1 - Signing, Pavement Marking and Channelization***
 - ***7.2 - Lighting***

- *7.3 - Signalization*
- *8.1 - Control Surveying*
- *8.2 - Design, Right of Way & Construction Surveying*
- *8.4 - Right of Way Mapping*
- *15.0 - Landscape Architect*

Known alternative contracting methods include: *N/A*

The general objective is for the CONSULTANT to prepare a set of contract documents including plans, specifications, supporting engineering analysis, calculations and other technical documents in accordance with FDOT policy, procedures and requirements. These Contract documents will be used by the contractor to build the project and test the project components. These Contract documents will be used by the DEPARTMENT or its Construction Engineering Inspection (CEI) representatives for inspection and final acceptance of the project. The CONSULTANT shall follow a systems engineering process to ensure that all required project components are included in the development of the Contract documents and the project can be built as designed and to specifications.

The Scope of Services establishes which items of work in the FDOT Design Manual and other pertinent manuals are specifically prescribed to accomplish the work included in this contract, and also indicate which items of work will be the responsibility of the CONSULTANT and/or the DEPARTMENT.

The CONSULTANT shall be aware that as a project is developed, certain modifications and/or improvements to the original concepts may be required. The CONSULTANT shall incorporate these refinements into the design and consider such refinements to be an anticipated and integral part of the work. This shall not be a basis for any supplemental fee request(s).

The CONSULTANT shall demonstrate good project management practices while working on this project. These include communication with the DEPARTMENT and others as necessary, management of time and resources, and documentation. The CONSULTANT shall set up and maintain throughout the design of the project a contract file in accordance with DEPARTMENT procedures. CONSULTANTS are expected to know the laws and rules governing their professions and are expected to provide services in accordance with current regulations, codes and ordinances and recognized standards applicable to such professional services. The CONSULTANT shall provide qualified technical and professional personnel to perform to Department standards and procedures, the duties and responsibilities assigned under the terms of this agreement. The CONSULTANT shall minimize to the maximum extent possible the DEPARTMENT's need to apply its own resources to assignments authorized by the Department.

The DEPARTMENT will provide contract administration, management services, and technical reviews of all work associated with the development and preparation of contract documents, including Construction documents. The DEPARTMENT's technical reviews are for high-level conformance and are not meant to be comprehensive reviews. The CONSULTANT shall be fully responsible for all work performed and work products developed under this Scope of Services. The DEPARTMENT may provide job-specific information and/or functions as outlined in this contract, if favorable.

2 PROJECT DESCRIPTION

The CONSULTANT shall investigate the status of the project and become familiar with concepts and commitments (typical sections, alignments, etc.) developed from prior studies and/or activities. If a Preliminary Engineering Report is available from a prior or current Project Development and Environment (PD&E) study, the CONSULTANT shall use the approved concepts as a basis for the design unless otherwise directed by the DEPARTMENT.

RESURFACING - CSC

2.1 Project General and Roadway (Activities 3, 4, and 5)

Public Involvement:

CAP Level: **2**

Public Involvement CAP Level to be determined on a case by case basis.

Other Agency Presentations/Meetings:

Agency	Number of Meetings
TBD	TBD

Specifications Package Preparation:

TBD

Estimated Quantities Report Preparation:

TBD

Plan Type:

TBD

Typical Section:

Number of Typical Sections: ***TBD***

TBD

Pavement Designs:

Number of Pavement Designs: ***TBD***

TBD

Cross-Slope Correction:

TBD

Access Management Classification:

- ***Select an Access Management Classification Number***

TBD

Major Intersections and Interchanges:

Number of Major Intersections and Interchanges: ***TBD***

TBD

Roadway Alternative Analysis:

TBD Level of Temporary Traffic Control Plan (TTCP): [*Level of TTCP*]

TBD

Temporary Lighting:

TBD

Temporary Signals:

TBD

Temporary Drainage:

TBD

Design Variations:

- *Others*
- *American with Disabilities Act (ADA)*
- *Sight Distance*
- *Clear Zone*

Others: **TBD**

TBD

Design Exceptions:

- *Design Speed*
- *Design Loading Structural Capacity*
- *Superelevation*
- *Lane Width*
- *Vertical Clearance*
- *Horizontal Curve Radius*
- *Shoulder Width*
- *Maximum Grade*
- *Cross Slope*
- *Stopping sight Distance*
- *Others*

Others: **TBD**

TBD

Back of Sidewalk Profiles:

Number of Back of Sidewalk Profiles: **TBD**

TBD

Selective Clearing and Grubbing:

Number of acres of Selective Clearing and Grubbing and/or Plant Preservation Area: **TBD** acres.

TBD

2.2 Drainage (Activities 6a and 6b)

Drainage System Type:

TBD

Number of stormwater management facility sites: ***TBD***

Number of cross drains: ***TBD***

TBD

2.3 Utilities Coordination (Activity 7)

The CONSULTANT is responsible to certify that all necessary arrangements for utility work on this project have been made and will not conflict with the physical construction schedule. The CONSULTANT should coordinate with DEPARTMENT personnel to coordinate transmittals to Utility Companies and meet production schedules.

The CONSULTANT shall ensure FDOT standards, policies, procedures, practices, and design criteria are followed concerning utility coordination.

The CONSULTANT may employ more than one individual or utility engineering consultant to provide utility coordination and engineering design expertise. The CONSULTANT shall identify a dedicated person responsible for managing all utility coordination activities. This person shall be contractually referred to as the Utility Coordination Manager and shall be identified in the CONSULTANT proposal. The Utility Coordination Manager shall be required to satisfactorily demonstrate to the FDOT District Utilities Administrator that they have the following knowledge, skills, and expertise:

- A minimum of 4 years of experience performing utility coordination in accordance with FDOT, Federal Highway Administration (FHWA), and American Association of State Highway and Transportation Officials (AASHTO) standards, policies, and procedures.
- A thorough knowledge of the FDOT plans production process and District utility coordination process.
- A thorough knowledge of FDOT agreements, standards, policies, and procedures.

The Utility Coordination Manager shall be responsible for managing all utility coordination, including the following:

- Assuring that Utility Coordination and accommodation is in accordance to the FDOT, FHWA, and AASHTO standards, policies, procedures, and design criteria.
- Assisting the engineer of record in identifying all existing utilities and coordinating any new installations. Assisting the Engineer of Record with resolving utility conflicts.
- Scheduling and performing utility coordination meetings, keeping and distribution of minutes/action items of all utility meetings, and ensuring expedient follow-up on all unresolved issues.
- Distributing all plans, conflict matrixes and changes to affected utility owners and making sure this information is properly coordinated and documented.
- Identifying and coordinating the completion of any FDOT or utility owner agreement that is required for reimbursement, or accommodation of the utility facilities associated with the project.

- Review and certify to the District Utilities Administrator that all Utility Work Schedules are correct and in accordance with the DEPARTMENT's standards, policies, and procedures.
- Prepare, review and process all utility related reimbursable paperwork inclusive of betterment and salvage determination.

The CONSULTANT's utility coordination work shall be performed and directed by the Utility Coordination Manager that was identified and approved by FDOT's Project Manager. Any proposed change of the approved Utility Coordination Manager shall be subject to review and approval by FDOT's Project Manager prior to any change being made in this contract.

Expected Utilities:

- *List utilities anticipated on the project*

2.4 Environmental Permits and Environmental Clearances (Activity 8)

Expected Permits:

- *List expected permits, e.g., USCG, USACE, WMD, etc.*

The DEPARTMENT will provide compensatory wetland mitigation in accordance with Section 373.4137, Florida Statutes.

TBD

2.5 Structures (Activities 9 - 18)

Bridge:

No.	Bridge Number	Length	Description
1	TBD	TBD	TBD

Type of Bridge Structure Work

- BDR (Activity 10)

TBD

- Temporary Bridge (Activity 11): *N/A*
- Short Span Concrete (Activity 12)

TBD

- Medium Span Concrete (Activity 13): *N/A*
- Structural Steel (Activity 14): *N/A*
- Segmental Concrete (Activity 15): *N/A*
- Movable Span (Activity 16): *N/A*

Retaining Walls:

No.	Location	Temp Type	Temp Length	Perm Type	Perm Length
1	TBD	TBD	TBD	TBD	TBD

Miscellaneous Structures:

- ***Box Culverts***
- ***Box Culvert Extensions***
- ***Strain Poles***
- ***Mast Arms***
- ***Overhead Sign Structures***
- ***High-mast Lighting***
- ***Noise Barrier Walls***
- ***Special Structures***
- ***Ancillary Structures***
- ***Other Structures***
- ***Fender System***

Noise Barrier Walls:

No.	Location	Temp Type	Temp Length	Perm Type	Perm Length
1	TBD	TBD	TBD	TBD	TBD

TBD

2.6 Signing and Pavement Markings (Activities 19 & 20)

No.	Type	Number	Location
1	TBD	TBD	TBD

TBD

2.7 Signalization (Activities 21 & 22)

Intersections:

TBD

Traffic Data Collection:

TBD

Traffic Studies:

TBD

Count Stations:

TBD

Traffic Monitoring Sites:

TBD

2.8 Lighting (Activities 23 & 24)

Limits and Proposed Type of Lighting:

Type	Limit
TBD	TBD

TBD

2.9 Landscape (Activities 25 & 26)

Include coordination with existing and/or proposed underground utilities including but not limited to FDOT lighting, drainage and Intelligent Transportation Systems (ITS). Landscape coordination with ITS shall include both underground conflicts and above-ground impacts to existing and/or proposed ITS coverage. The CONSULTANT shall closely coordinate with the Department's ITS units to ensure that all conflicts are identified, addressed and mitigated in the Contract Documents.

Planting Plans:

TBD

Irrigation Plans:

TBD

Hardscape Plans:

TBD

Outdoor Advertising:

TBD

2.10 Survey (Activity 27)

Design Survey:

TBD

Subsurface Utility Exploration:

TBD

Right of Way Survey:

TBD

Vegetation Survey:

TBD

2.11 Photogrammetry (Activity 28)

TBD

2.12 Mapping (Activity 29)

Control Survey Map:

TBD

Right of Way Map:

TBD

Legal Descriptions: *N/A*

Maintenance Map:

TBD

Miscellaneous Items:

TBD

2.13 Terrestrial Mobile LiDAR (Activity 30)

TBD

2.14 Architecture (Activity 31) (N/A)

2.15 Noise Barriers (Activity 32) (N/A)

2.16 Intelligent Transportation Systems (Activities 33 & 34)

TBD

The Federal Highway Administration issued Rule 940 entitled Intelligent Transportation Systems (ITS) Architecture and Standards to ensure new projects conform to the National ITS Architecture and standards as well as with a regional ITS architecture developed to reflect the local needs, issues, problems, and objectives for implementation.

For all projects with ITS activities, the CONSULTANT shall follow the Rule 940 requirements and use a Systems Engineering approach for determining the requirements for the project. The CONSULTANT shall develop all necessary documents to support the Rule 940 requirements like Concept of Operations (ConOPS), Systems Engineering Management Plan (SEMP), Requirements Traceability Verification Matrix (RTVM) and others as deemed necessary by the Department.

[Describe the hardware configuration analysis and design including system architecture, interfaces, communications, equipment, devices and computers.]

[If relevant, mention any prior reports done such as concept reports, etc.]

The ITS shall operate from the **TBD** TMC located at **TBD** using the SunGuide® (SunGuide) Software, or if SunGuide is not in use at **TBD** TMC, using the appropriate **TBD**.

Traffic Data Collection:
TBD

Geographical Information System (GIS) Requirements: CONSULTANT shall include in the design the GIS data collection requirements and deliverables for integration with SunGuide software and other Department GIS based asset management applications like ITS FM software.

All design efforts shall be based on deploying "open architecture" subsystems, while remaining fully compatible with previous designs (as applicable) and the FDOT ITS Specifications. All ITS field devices and support systems shall be designed and located outside of the clear zone, or behind protective barrier, within the right of way. This includes cabinets, poles, and support hardware. Utility conflicts shall be identified and resolved during the design phase. The location of design elements will be coordinated with the District Landscape Architect to optimize landscape opportunities. The design shall minimize theft and vandalism. The CONSULTANT shall include in the design vandal resistant mechanisms to minimize theft. The CONSULTANT shall provide additional redundant power and communications systems to minimize system downtime due to vandalism.

The CONSULTANT shall design the project subsystems such that they will be monitored and controlled from the FDOT's TMC facilities located at **TBD**. The CONSULTANT shall ensure that all ITS field devices and ancillary components comply with the FDOT's Approved Product List (APL) and are supported within the SunGuide software or other specified software, unless otherwise approved by the DEPARTMENT.

The CONSULTANT shall include in the design any required upgrade to the TMC central hardware, equipment racks, and equipment wiring, as directed by the FDOT project manager, to make the subsystems fully operations from the TMC facilities.

For projects with existing ITS, the CONSULTANT shall include in the design any required upgrade to existing ITS equipment to meet the latest FDOT standards, NEC requirements or as directed by the FDOT project manager and to make the subsystems fully operations from the TMC facilities.

ITS coordination with Landscape Architecture shall include both underground conflicts and above-ground impacts to existing and/or proposed Landscaping. The CONSULTANT shall closely coordinate with the Landscape Architect to ensure that all conflicts are identified, addressed and mitigated in the Contract Documents.

TBD

2.17 Geotechnical (Activity 35) (N/A)

2.18 3D Modeling (Activity 36)

TBD

2.19 Project Schedule

Within ten (10) days after the Notice-To-Proceed, and prior to the CONSULTANT beginning work, the CONSULTANT shall provide a detailed project activity/event schedule for DEPARTMENT and CONSULTANT scheduled activities required to meet the current DEPARTMENT Production Date. The schedule shall be based upon the **TBD**. The current production date is [Date]. The schedule shall be accompanied by an anticipated payout and fiscal progress curve. For the purpose of scheduling, the CONSULTANT shall allow for a **TBD** week review time for each phase submittal and any other submittals as appropriate.

The schedule shall indicate all required submittals.

All fees and price proposals are to be based on the negotiated schedule of **TBD** months for final construction contract documents. However, the contract deadline is **TBD** months from the Notice to Proceed.

Periodically, throughout the life of the contract, the project schedule and payout and fiscal progress curves shall be reviewed and, with the approval of the DEPARTMENT, adjusted as necessary to incorporate changes in the Scope of Services and progress to date.

The approved schedule and schedule status report, along with progress and payout curves, shall be submitted with the monthly progress report.

The schedule shall be submitted in an FDOT system-compatible format.

TBD

2.20 Submittals

The CONSULTANT shall furnish construction contract documents as required by the DEPARTMENT to adequately control, coordinate, and approve the work concepts. The CONSULTANT shall distribute submittals as directed by the DEPARTMENT. The DEPARTMENT will determine the specific number of copies required prior to each submittal.

2.21 Provisions for Work

The services performed by the CONSULTANT must comply with all applicable DEPARTMENT's manuals, procedure, policies, and guidelines. Specifically, the CONSULTANT must comply with DEPARTMENT's Project Development and Environmental (PD&E) Manual, FDOT Design Manual (FDM), Structures Manual, and Computer Aided Design and Drafting (CADD) Manual. The DEPARTMENT's manuals and guidelines incorporate, by requirement or reference, all applicable federal and state laws, regulations, and Executive Orders. The CONSULTANT will use the latest editions of the manuals, procedures, and guidelines to perform work for this project.

All work shall be prepared with English units (unless otherwise specified) in accordance with the latest editions of standards and requirements utilized by the DEPARTMENT.

2.22 Services to be Performed by the DEPARTMENT

When appropriate or available, the DEPARTMENT will provide project data including:

- *Numbers for field books*
- *Preliminary Horizontal Network Control*
- *Access for the CONSULTANT to utilize the DEPARTMENT's Information Technology Resources*
- *All Department agreements with Utility Agency Owner (UAO)*
- *All certifications necessary for project letting*
- *Building Construction Permit Coordination (Turnpike)*
- *All information that may come to the DEPARTMENT pertaining to future improvements*
- *All future information that may come to the DEPARTMENT during the term of the CONSULTANT's Agreement, which in the opinion of the DEPARTMENT is necessary for the prosecution of the work*
- *Available traffic and planning data*
- *All approved utility relocations*
- *Project utility certification to the DEPARTMENT's Central Office*
- *Any necessary title searches*
- *Engineering standards review services*
- *All available information in the possession of the DEPARTMENT pertaining to utility companies whose facilities may be affected by the proposed construction*
- *All future information that may come to the DEPARTMENT pertaining to subdivision plans so that the CONSULTANT may take advantage of additional areas that can be utilized as part of the existing right of way*
- *Systems traffic for Projected Design Year, with K, D, and T factors*
- *Previously constructed Highway Beautification or Landscape Construction Plans*
- *Landscape Opportunity Plan(s)*
- *Existing right of way maps*
- *Existing cross slope data for all RRR projects*
- *Existing pavement evaluation report for all RRR projects*
- *PD&E Documents*
- *Design Reports*
- *Letters of authorization designating the CONSULTANT as an agent of the DEPARTMENT in accordance with F.S. 337.274*
- *Phase reviews of plans and engineering documents*
- *Regarding Environmental Permitting Services:*
 - *Approved Permit Document when available*
 - *Approval of all contacts with environmental agencies*
 - *General philosophies and guidelines of the DEPARTMENT to be used in the fulfillment of this contract. Objectives, constraints, budgetary limitations, and time constraints will be completely defined by the Project Manager.*

- *Appropriate signatures on application forms*

3 PROJECT COMMON AND PROJECT GENERAL TASKS

Project Common Tasks

Project Common Tasks, as listed below, are work efforts that are applicable to many project activities, 4 (Roadway Analysis) through 36 (3D Modeling). These tasks are to be included in the project scope in each applicable activity when the described work is to be performed by the CONSULTANT.

Cost Estimates: The CONSULTANT is responsible for producing a construction cost estimate and reviewing and updating the cost estimate when scope changes occur and/or at milestones of the project. Prior to Phase II plans or completion of quantities, the DEPARTMENT's Long-Range Estimate (LRE) system will be used to produce a conceptual estimate, according to District policy. Once the quantities have been developed (beginning at Phase II plans and no later than Phase III plans) the CONSULTANT shall be responsible for inputting the category information, pay items and quantities into AASHTOWare Project Preconstruction through the use of the DEPARTMENT's Designer Interface.

Technical Special Provisions: The CONSULTANT shall provide Technical Special Provisions for all items of work not covered by the Standard Specifications for Road and Bridge Construction and the workbook of implemented modifications.

A Technical Special Provision shall not modify the Standard Specifications and implemented modifications in any way.

The Technical Special Provisions shall provide a description of work, materials, equipment and specific requirements, method of measurement and basis of payment. Proposed Technical Special Provisions will be submitted to the District Specifications Office for initial review at the time of the Phase III plans review submission to the DEPARTMENT's Project Manager. This timing will allow for adequate processing time prior to final submittal. The Technical Special Provisions will be reviewed for suitability in accordance with the Handbook for Preparation of Specification Packages. The District Specifications Office will forward the Technical Special Provisions to the District Legal Office for their review and comment. All comments will be returned to the CONSULTANT for correction and resolution. Final Technical Special Provisions shall be digitally signed and sealed in accordance with applicable Florida Statutes.

The CONSULTANT shall contact the appropriate District Specifications Office for details of the current format to be used before starting preparations of Technical Special Provisions.

Modified Special Provisions: The CONSULTANT shall provide Modified Special Provisions as required by the project. Modified Special Provisions are defined in the Specifications Handbook.

A Modified Special Provision shall not modify the first nine sections of the Standard Specifications and implemented modifications in any way. All modifications to other sections must be justified to the appropriate District and Central Specifications Offices to be included in the project's specifications package.

Field Reviews: The CONSULTANT shall make as many trips to the project site as required to obtain necessary data for all elements of the project.

Technical Meetings: The CONSULTANT shall attend all technical meetings necessary to execute the Scope of Services of this contract. This includes meetings with DEPARTMENT and/or Agency staff, between disciplines and subconsultants, such as access management meetings, pavement design meetings, local governments, railroads, airports, progress review meetings (phase review), and miscellaneous meetings. The CONSULTANT shall prepare, and submit to the DEPARTMENT's Project Manager for review, the meeting minutes for all meetings attended by them. The meeting minutes are due within five (5) working days of attending the meeting.

Quality Assurance/Quality Control: It is the intention of the DEPARTMENT that design CONSULTANTS, including their subconsultant(s), are held responsible for their work, including plans review. The purpose of CONSULTANT plan reviews is to ensure that CONSULTANT plans follow the plan preparation procedures outlined in the FDOT Design Manual, that state and federal design criteria are followed with the DEPARTMENT concept, and that the CONSULTANT submittals are complete. All subconsultant document submittals shall be submitted by the subconsultant directly to the CONSULTANT for their independent Quality Assurance/Quality Control review and subsequent submittal to the DEPARTMENT.

It is the CONSULTANT'S responsibility to independently and continually QC their plans and other deliverables. The CONSULTANT should regularly communicate with the DEPARTMENT's Design Project Manager to discuss and resolve issues or solicit opinions from those within designated areas of expertise.

The CONSULTANT shall be responsible for the professional quality, technical accuracy and coordination of all surveys, designs, drawings, specifications and other services furnished by the CONSULTANT and their subconsultant(s) under this contract.

The CONSULTANT shall provide a Quality Control Plan that describes the procedures to be utilized to verify, independently check, and review all maps, design drawings, specifications, and other documentation prepared as a part of the contract. The CONSULTANT shall describe how the checking and review processes are to be documented to verify that the required procedures were followed. The Quality Control Plan shall be one specifically designed for this project. The CONSULTANT shall submit a Quality Control Plan for approval within twenty (20) business days of the written Notice to Proceed and it shall be signed by the CONSULTANT's Project Manager and the CONSULTANT QC Manager. The Quality Control Plan shall include the names of the CONSULTANT's staff that will perform the quality control reviews. The Quality Control reviewer shall be a Florida Licensed Professional Engineer fully prequalified under F.A.C. 14-75 in the work type being reviewed. A marked up set of prints from a Quality Control Review indicating the reviewers for each component (structures, roadway, drainage, signals, geotechnical, signing and marking, lighting, landscape,

surveys, etc.) and a written resolution of comments on a point-by-point basis will be required, if requested by the DEPARTMENT, with each phase submittal. The responsible Professional Engineer, Landscape Architect, or Professional Surveyor & Mapper that performed the Quality Control review will sign a statement certifying that the review was conducted and found to meet required specifications.

The CONSULTANT shall, without additional compensation, correct all errors or deficiencies in the designs, maps, drawings, specifications and/or other products and services.

Independent Peer Review: When directed by the DEPARTMENT, a subconsultant may perform Independent Peer Reviews.

Independent Peer Review and a Constructability/Bidability Review for design Phase Plans document submittals are required on this project. These separate reviews shall be completed by someone who has not worked on the plan component that is being reviewed. These could include, but are not limited to a separate office under the Prime's umbrella, a subconsultant that is qualified in the work group being reviewed, or a CEI. It does not include persons who have knowledge of the day to day design efforts. The Constructability/Bidability Review shall be performed by a person with experience working on Department construction projects (CEI, Contractor, etc.).

The Independent Peer Review for design Phase Plans submittals shall ensure the plans meet the FDM, Standard Plans and FDOT CADD Manual. The Constructability/Bidability Review shall ensure the project can be constructed and paid for as designed. Constructability/Bidability Reviews should be conducted prior to the Phase III and Phase IV submittals, using the Phase Review Checklist (Guidance Document 1-1-A) from the Construction Project Administration Manual (CPAM) as a minimum guideline. The CONSULTANT shall submit this checklist, as well as the "marked-up" set of plans during this review, and review comments and comment responses from any previous Constructability/Bidability reviews. These items will be reviewed by District Design and District Construction.

Supervision: The CONSULTANT shall supervise all technical design activities.

Coordination: The CONSULTANT shall coordinate with all disciplines of the project to produce a final set of construction documents.

Project General Tasks

Project General Tasks, described in Sections 3.1 through 3.7 below, represent work efforts that are applicable to the project as a whole and not to any one or more specific project activity. The work described in these tasks shall be performed by the CONSULTANT when included in the project scope.

3.1 Public Involvement

Public involvement includes communicating to all interested persons, groups, and government organizations information regarding the development of the project. The CONSULTANT shall provide to the DEPARTMENT drafts of all Public Involvement documents (e.g., newsletters, property owner letters, advertisements, etc.) associated with

the following tasks for review and approval at least **60** business days prior to printing and / or distribution.

TBD

3.1.1 Community Awareness Plan

Prepare a Community Awareness Plan (CAP) for review and approval by the DEPARTMENT within 30 calendar days after receiving Notice to Proceed. The objective of the plan is to notify local governments, affected property owners, tenants, and the public of the DEPARTMENT'S proposed construction and the anticipated impact of that construction. The CAP shall address timeframes for each review and shall include tentative dates for each public involvement requirement for the project. The CAP will also document all public involvement activities conducted throughout the project's duration. In addition to the benefits of advance notification, the process should allow the DEPARTMENT to resolve controversial issues during the design phase. This item shall be reviewed and updated periodically as directed by the DEPARTMENT throughout the life of the project.

3.1.2 Notifications

In addition to public involvement data collection, the CONSULTANT shall assist the DEPARTMENT or prepare notifications, flyers, and/or letters to elected officials and other public officials, private property owners, and tenants at intervals during plans production as identified by the DEPARTMENT. All letters and notices shall be reviewed by the [DEPARTMENT/CONSULTANT] to ensure that they are addressed to the correct and current public officials.

3.1.3 Preparing Mailing Lists

At the beginning of the project, The CONSULTANT shall identify all impacted property owners and tenants (within a minimum of 300 feet of the project corridor) The CONSULTANT shall prepare a mailing list of all such entities and shall update the mailing list as needed during the life of the project.

3.1.4 Median Modification Letters

The CONSULTANT shall prepare a median modification letter to be sent to property owners along the corridor. In addition, the CONSULTANT shall prepare a sketch of each proposed median modification for inclusion in the letter. The letters will be sent on DEPARTMENT letterhead by the [DEPARTMENT/CONSULTANT].

3.1.5 Driveway Modification Letters

The CONSULTANT shall prepare a driveway modification letter to be sent to property owners along the corridor. In addition, the CONSULTANT shall prepare a sketch of each proposed driveway modification for inclusion in the letter. The letters will be sent on DEPARTMENT letterhead.

3.1.6 Newsletters

The CONSULTANT shall prepare newsletters for distribution to elected officials, public officials, property owners along the corridor and other interested parties. The letters will be sent by the CONSULTANT.

3.1.7 Renderings and Fly-Throughs

The CONSULTANT shall prepare renderings and fly-throughs for use in public meetings.

3.1.8 PowerPoint Presentations

The CONSULTANT shall prepare PowerPoint presentations for use in public meetings.

3.1.9 Public Meeting Preparations

The CONSULTANT shall prepare the necessary materials for use in public meetings.

The CONSULTANT will investigate potential meeting sites to advise the DEPARTMENT on their suitability. The [DEPARTMENT/CONSULTANT] will pay all costs for meeting site rents and insurance. No DEPARTMENT meetings will be held on public school system properties.

3.1.10 Public Meeting Attendance and Follow-up

The CONSULTANT shall attend public meeting(s), assist with meeting setup and take down. The CONSULTANT shall also prepare a summary of the public meeting that includes all copies of all materials shown or provided at the public meeting. The summary shall also include a listing of all written comments made during or after the meeting and responses to those written comments.

The CONSULTANT will attend the meetings with an appropriate number of personnel to assist the DEPARTMENT'S Project Manager.

It is estimated for this project there will be [Number] Public meetings during the design.

3.1.11 Other Agency Meetings

In addition to scheduled public meetings the CONSULTANT may be required to participate in meetings with local governing authorities and/or Metropolitan Planning Organization (MPO). The CONSULTANT's participation may include, but not be limited to, presentations during the meeting, note taking, and summarizing the meeting in a memo to the file. It is estimated for this project there will be *NaN* meetings (as indicated in Section 2.1 above) with local governing authorities and/or MPOs during the design.

3.1.12 Web Site

The CONSULTANT shall create and/or maintain a web site for the project.

3.2 Joint Project Agreements

3.3 Specifications & Estimates

3.3.1 Specifications Package Preparation

The CONSULTANT shall prepare and provide a specifications package in accordance with the DEPARTMENT'S Procedure Topic No. 630-010-005 Specifications Package Preparation and the Specifications Handbook. The CONSULTANT shall provide the DEPARTMENT names of at least two team members who have successfully completed the Specifications Package Preparation Training and will be responsible for preparing the Specifications Package for the project. The Specifications Package shall be prepared using the DEPARTMENT's Specs on the Web application. The CONSULTANT shall be able to document that the procedure defined in the Handbook for the Preparation of Specifications Packages is followed, which includes the quality assurance/quality control procedures. The specifications package shall address all items and areas of work and include any Mandatory Specifications, Modified Special Provisions, and Technical Special Provisions.

The specifications package must be submitted for review to the District Specifications Office at least 30 days prior to the contract package to Tallahassee or District due date, or sooner if required by the District Specifications Office. This submittal does not require signing and sealing and shall be coordinated through the District's Project Manager. The CONSULTANT shall coordinate with the DEPARTMENT on the submittal requirements, but at a minimum shall consist of (1) the complete specifications package, (2) a copy of the marked-up workbook used to prepare the package, and (3) a copy of the final project plans.

Final submittal of the specifications package must occur at least 10 working days prior to the contract package to Tallahassee due date. This submittal shall be digitally signed, dated, and sealed in accordance with applicable Florida Statutes.

3.3.2 Estimated Quantities Report Preparation

The CONSULTANT shall prepare an Estimated Quantities (EQ) Report in accordance with FDM 902. Includes loading category information, pay items, and quantities into Designer Interface for AASHTOWare Project Preconstruction (PrP), QA/QC efforts associated with AASHTOWare PrP and the EQ Report.

3.4 Contract Maintenance and Project Documentation

Contract maintenance includes project management effort for complete setup and maintenance of files, electronic folders and documents, developing technical monthly progress reports and schedule updates. Project documentation includes the compilation and delivery of final documents, reports or calculations that support the development of the contract plans; includes uploading files to Electronic Document Management System (EDMS) or Project Suite Enterprise Edition (PSEE).

3.5 Value Engineering (Multi-Discipline Team) Review

3.6 Prime Consultant Project Manager Meetings

Includes only the Prime Consultant Project Manager's time for travel and attendance at Activity Technical Meetings and other meetings listed in the meeting summary for Task 3.6 on tab 3 Project General Task of the staff hour forms. Staff hours for other personnel attending Activity Technical Meetings are included in the meeting task for that specific Activity.

3.7 Plans Update

The effort needed for Plans Update services will vary from project to project, depending on size and complexity of the project, as well as the duration of time spent "on the shelf".

Specific services will be negotiated as necessary as a contract amendment.

3.8 Post-Design Services

Post-Design Services may include, but not limited to, meetings, construction assistance, plans revisions, shop drawing review, survey services, as-built drawings, and load ratings. Specific services will be negotiated as necessary as a contract amendment.

Post-Design Services are not intended for instances of CONSULTANT errors or omissions.

3.9 Digital Delivery

The CONSULTANT shall deliver final contract plans and documents in digital format. The final contract plans and documents shall be digitally signed and sealed files delivered to the DEPARTMENT on acceptable electronic media, as determined by the DEPARTMENT.

3.10 Risk Assessment Workshop

3.11 Railroad, Transit and/or Airport Coordination

[Provide project-specific information]

3.11.1 Aeronautical Evaluation

The Consultant shall be responsible for complying with the requirements of Title 14 of the Code of Federal Regulations Part 77 (14 CFR Part 77), and for determining whether it is necessary to file any Notice of Proposed Construction or Alteration (FAA Form 7460-1) with the Federal Aviation Administration (FAA), utilizing the FAA Notice Criteria Tool. Place a copy of all pertinent documentation in the Project Documentation folder structure; e.g., Notice Criteria Tool inquiries and responses; FAA Form 7460-1 filed with the FAA; Letters of Determination (along with the records demonstrating compliance with the conditions and deadlines). Report any Letters of Determination, designated other than "Does Not Exceed", to the Central Office (Aviation Office, Airspace and Land Use Manager).

3.12 Landscape and Existing Vegetation Coordination

Coordinate to ensure preservation and protection of existing vegetation. Relocation of existing vegetation may be necessary in some cases. Space for proposed landscape should be preserved and conflicts with drainage, utilities, ITS, and signage should be minimized. Coordination with the District Landscape Architect may be necessary as defined in 4.12. Additionally, coordination with the Florida Scenic Highways program should be included to ensure any requirements of the FSH program are met.

3.13 Other Project General Tasks

[Describe other project general tasks]

4 ROADWAY ANALYSIS (TBD)

The CONSULTANT shall analyze and document Roadway Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

4.1 Typical Section Package

The CONSULTANT shall prepare a Typical Section Package.

4.2 Pavement Type Selection Report

4.3 Pavement Design Package

The CONSULTANT shall prepare a Pavement Design Package.

4.4 Cross-Slope Correction

The CONSULTANT shall coordinate with the DEPARTMENT to obtain existing cross slope data, determine roadway limits where cross slope is potentially out of tolerance and determine a resolution.

4.5 Horizontal/Vertical Master Design Files

The CONSULTANT shall design the geometrics using the Standard Plans that are most appropriate with proper consideration given to the design traffic volumes, design speed, capacity and levels of service, functional classification, adjacent land use, design consistency and driver expectancy, aesthetics, existing vegetation to be preserved, pedestrian and bicycle concerns, ADA requirements, Safe Mobility For Life Program, access management, PD&E documents and scope of work. The CONSULTANT shall also develop utility conflict information to be provided to project Utility Coordinator in the format requested by the DEPARTMENT.

Note: When the project includes a 3D Model deliverable, also include Activity 36 3D Modeling.

4.6 Access Management

The CONSULTANT shall incorporate access management standards for each project in coordination with DEPARTMENT staff. The CONSULTANT shall review adopted access

management standards and the existing access conditions (interchange spacing, signalized intersection spacing, median opening spacing, and connection spacing). Median openings that will be closed, relocated, or substantially altered shall be shown on plan sheets and submitted with supporting documentation for review with the first plans submittal.

The DEPARTMENT shall provide access management classification information and information derived from PD&E studies and public hearings to be used by the CONSULTANT.

4.7 Roundabout Final Design Analysis

The CONSULTANT shall finalize the design of the roundabout in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

The CONSULTANT shall perform a final roundabout operational analysis that recommends a functional geometric layout that is cost effective, safe and meets the needs of the community. A final roundabout design will be recommended for implementation, and all geometric and operational analysis will be documented in a final roundabout report.

4.8 Cross Section Design Files

The CONSULTANT shall establish and develop cross section design files in accordance with the FDOT CADD Manual.

Note: If the Cross Sections are prepared using a 3D model, use Task 36.5 instead of Task 4.9 for the Cross Section Design Files.

4.9 Temporary Traffic Control Plan (TTCP) Analysis

The CONSULTANT shall design a safe and effective TTCP to move vehicular and pedestrian traffic during all phases of construction. The design shall include construction phasing of roadways ingress and egress to existing property owners and businesses, routing, signing and pavement markings, and detour quantity tabulations, roadway pavement, drainage structures, ditches, front slopes, back slopes, drop offs within clear zone, transit stops, and traffic monitoring sites. Special consideration shall be given to the construction of the drainage system when developing the construction phases. Positive drainage must be maintained at all times. The design shall include construction phasing of roadways to accommodate the construction or relocation of utilities when the contract includes Joint Project Agreements (JPAs).

The CONSULTANT shall investigate the need for temporary traffic signals, temporary highway lighting, detours, diversions, lane shifts, and the use of materials such as sheet piling in the analysis. The Traffic Control Plan shall be prepared by a certified designer who has completed training as required by the DEPARTMENT. Before proceeding with the TTCP, the CONSULTANT shall meet with the appropriate DEPARTMENT personnel. The purpose of this meeting is to provide information to the CONSULTANT that will better coordinate the Preliminary and Final TTCP efforts.

The CONSULTANT shall consider the local impact of any lane closures or alternate routes. When the need to close a road is identified during this analysis, the CONSULTANT shall notify the DEPARTMENT's Project Manager as soon as possible. Proposed road closings must be reviewed and approved by the DEPARTMENT. Diligence shall be used to minimize negative impacts by appropriate specifications, recommendations or plans development. Local impacts to consider will be local events, holidays, peak seasons, detour route deterioration and other eventualities. CONSULTANT shall be responsible to obtain local authorities permission for use of detour routes not on state highways.

4.10 Master TTCP Design Files

The CONSULTANT shall develop master TTCP files showing each phase of the TTCP. This includes all work necessary for designing lane configurations, diversions, lane shifts, signing and pavement markings, temporary traffic control devices, and temporary pedestrian ways.

4.11 Selective Clearing and Grubbing

Note: Utilize Activities 25 and 26 for Standalone Landscape Projects.

a) Selective Clearing and Grubbing of Existing Vegetation Field Assessment

The CONSULTANT shall review information from the DEPARTMENT and conduct a project field assessment(s) of existing vegetation. At least one field assessment visit is to be attended by the District Landscape Architect.

The Result of the Field Assessment(s) will determine the course of action for Selective Clearing and Grubbing and the extent of the Vegetation Survey under Task 2.10.

b) Selective Clearing and Grubbing Site Inventory Analysis of Existing Vegetation and Cross-Discipline Coordination (OPTIONAL SERVICES)

The CONSULTANT shall coordinate with the District Utility Office, drainage engineers, and traffic engineers to ensure that preservation of existing vegetation is coordinated between all disciplines. Coordinate with the District Landscape Architect.

Based on the field assessment, the CONSULTANT may be required do a site inventory analysis of existing vegetation, opportunities for preservation and protection of existing vegetation, relocation options, and selective removal of nuisance and/or non-nuisance vegetation. Coordinate with surveyor to have trees and vegetation tagged and surveyed, per tasks 27.28 or 27.29.

c) Selective Clearing and Grubbing- Existing Vegetation Maintenance Report

The CONSULTANT shall include in the plans instructions for the care and maintenance of the plant preservation areas, and selective clearing and grubbing areas throughout the construction period. The CONSULTANT will coordinate with the District Landscape Architect to ensure that the intent of the plant preservation areas is in alignment with future highway landscape plans. The CONSULTANT should be knowledgeable in arboricultural

practices to the extent that they are able to deliver detailed and informed Selective Clearing and Grubbing Plans.

4.12 Tree Disposition Plans

Consultant will prepare a Tree Disposition Plan outlining the requirements for the relocation and protection of trees located within the project boundaries. Will utilize the information collected from the Vegetation Survey and information collected under task 4.12 for Selective Clearing and Grubbing.

4.13 Design Variations and Exceptions

The CONSULTANT shall prepare the documentation necessary to gain DEPARTMENT approval of all appropriate Design Variation Memorandums, Formal Design Variations and/or Design Exceptions.

A Project Design Variation Memorandum (FDM Form 122-B) shall be prepared to document all non-controlling design elements for a project that do not meet Department criteria. Those elements requiring a more detailed analysis, as per FDM Section 122.2, shall be submitted as Formal Design Variations or Design Exceptions.

4.14 Design Report

The CONSULTANT shall prepare all applicable report(s) as listed in the Project Description section of this scope. Reports are to be delivered as a signed and sealed pdf file.

4.15 Roadway Quantities for EQ Report

The CONSULTANT shall determine roadway pay items and quantities and the supporting documentation.

4.16 TTCP Quantities for EQ Report

The CONSULTANT shall determine temporary traffic control pay items and quantities and the supporting documentation.

4.17 Cost Estimate

4.18 Technical Special Provisions and Modified Special Provisions

4.19 Other Roadway Analyses

4.20 Field Reviews

4.21 Monitor Existing Structures

The CONSULTANT shall perform field observations to visually identify existing structures within the project limits which may require settlement, vibration or groundwater monitoring by the contractor during construction in accordance with FDM Chapter 117.

The CONSULTANT shall identify the necessary pay items to be included in the bid documents to monitor existing structures.

Optional Services (may be negotiated at a later date if needed): The CONSULTANT shall coordinate with and assist the geotechnical engineer and/or structural engineer to develop mitigation strategies (when applicable).

4.22 Technical Meetings

4.23 Quality Assurance/Quality Control

4.24 Independent Peer Review

4.25 Supervision

4.26 Coordination

5 ROADWAY PLANS (TBD)

The CONSULTANT shall prepare Roadway, TTCP, Utility Adjustment Sheets, plan sheets, notes, and details. The plans shall include the following sheets necessary to convey the intent and scope of the project for the purposes of construction.

5.1 Key Sheet

5.2 Typical Section Sheets

5.2.1 Typical Sections

5.2.2 Typical Section Details

5.3 General Notes/Pay Item Notes

5.4 Project Layout

5.5 Plan/Profile Sheet

5.6 Profile Sheet

5.7 Plan Sheet

5.8 Special Profile

5.9 Back-of-Sidewalk Profile Sheet

5.10 Interchange Layout Sheet

5.11 Ramp Terminal Details (Plan View)

5.12 Intersection Layout Details

5.13 Special Details

5.14 Cross-Section Pattern Sheets

5.15 Roadway Soil Survey Sheets

5.16 Cross Sections

5.17 Temporary Traffic Control Plan Sheets

5.18 Temporary Traffic Control Cross Section Sheets

5.19 Temporary Traffic Control Detail Sheets

5.20 Utility Adjustment Sheets

5.21 Selective Clearing and Grubbing Sheets

5.21.1 Selective Clearing and Grubbing

5.21.2 Selective Clearing and Grubbing Details

5.22 Tree Disposition Plan Sheets

5.22.1 Tree Disposition Plan Sheets

Tree Disposition Plan Sheets will be signed and sealed drawings showing the location and vertical/horizontal landscape design of the vegetation to be relocated. The Tree Disposition Plans will be produced at the scale of the roadway drawings or at a scale that best depicts the information. Interchange and details will be shown at no larger than a 1" =50" scale.

5.22.2 Tree Disposition Plan Tables and Schedules

5.23 Project Control Sheets

5.24 Environmental Detail Sheets

Preparation of detail sheets for potential environmental issues such as, underground fuel tanks and monitoring wells, septic tanks within the proposed right of way. All piping and pumps in association with the above referenced issues shall also be located and identified by the survey. The CONSULTANT shall relay to the DEPARTMENT any findings of contaminated soil, monitoring wells, or any features (particularly springs or sinks) relating to contamination or hazardous material.

Coordination with Permits/Environmental staff and preparing Dredge & Fill Detail sheets where applicable.

5.25 Utility Verification Sheets (SUE Data)

5.26 Quality Assurance/Quality Control

5.27 Supervision

6a DRAINAGE ANALYSIS

The CONSULTANT shall analyze and document Drainage Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

The CONSULTANT shall be responsible for designing a drainage and stormwater management system. All design work shall comply with the requirements of the appropriate regulatory agencies and the DEPARTMENT's Drainage Manual.

The CONSULTANT shall coordinate fully with the appropriate permitting agencies and the DEPARTMENT's staff. All activities and submittals should be coordinated through the DEPARTMENT's Project Manager. The work will include the engineering analyses for any or all of the following:

6a.1 Drainage Map Hydrology

Create a (pre- and/or post-condition) working drainage basin map to be used in defining the system hydrology. This map shall incorporate drainage basin boundaries, existing survey and/or LiDAR and field observations, as necessary, to define the system. Basin delineations shall also include any existing collection systems in a logical manner to aid in the development of the hydraulic model. Include coordination hours needed to convey drainage hydrologic features onto produced drainage maps.

6a.2 Base Clearance Calculations

Analyze, determine, and document high water elevations per basin which will be used to set roadway profile grade and roadway materials. Determine surface water elevations at cross drains, floodplains, outfalls and adjacent stormwater ponds. Determine groundwater elevations at intervals between the above-mentioned surface waters. Document findings in a Base Clearance Report.

6a.3 Pond Siting Analysis and Report

Evaluate pond sites using a preliminary hydrologic analysis. Document the results and coordination for all the project's pond site analyses. The Drainage Manual provides specific documentation requirements.

6a.4 Design of Cross Drains

Analyze the hydraulic design and performance of cross drains. Check existing cross drains to determine if they are structurally sound and can be extended. Document the design as required. Determine and provide flood data as required.

6a.5 Design of Ditches

Design roadway conveyance and outfall ditches. This task includes capacity calculations, longitudinal grade adjustments, flow changes, additional adjustments for ditch convergences, selection of suitable channel lining, design of side drain pipes, and documentation. (Design of linear stormwater management facilities in separate task.)

6a.6 Design of Stormwater Management Facility (Offsite or Infield Pond)

Design stormwater management facilities to meet requirements for stormwater quality treatment, attenuation and aesthetics. Develop proposed pond layout (contributing drainage basin, shape, contours, slopes, volumes, tie-ins, aesthetics, etc.), perform routing, pollutant/nutrient loading calculations, recovery calculations, design the outlet control structure and buoyancy calculations for pond liners when necessary.

6a.7 Design of Stormwater Management Facility (Roadside Treatment Swales and Linear Ponds)

Design stormwater management facilities to meet requirements for stormwater quality treatment, attenuation and aesthetics. Develop proposed pond layout (contributing drainage basin, shape, contours, slopes, volumes, tie-ins, aesthetics, etc.), perform routing, pollutant/nutrient loading calculations, recovery calculations and design the outlet control structure.

6a.8 Design of Floodplain Compensation

Determine floodplain encroachments, coordinate with regulatory agencies, and develop proposed compensation area layout (shape, contours, slopes, volumes, etc.). Document the design following the requirements of the regulatory agency.

6a.9 Design of Storm Drains

Delineate contributing drainage areas, determine runoff, inlet locations, and spread. Calculate hydraulic losses (friction, utility conflict and, if necessary, minor losses). Determine design tailwater and, if necessary, outlet scour protection.

6a.10 Optional Culvert Material

Determine acceptable options for pipe materials using the Culvert Service Life Estimator.

6a.11 French Drain Systems

Design French Drain Systems to provide stormwater treatment and attenuation. Identify location for percolation tests and review these, determine the size and length of French Drains, design the control structure/weir, and model the system of inlets, conveyances, French Drains, and other outfalls using a routing program.

6a.11.1 Existing French Drain Systems

Include this task if French Drains are proposed and the existing systems must be analyzed for a pre- versus post comparison of the peak stages and/or discharges.

6a.12 Drainage Wells

Design the discharge into deep wells to comply with regulatory requirements. Identify the location of the well, design the control structure/weir, and model the system using a routing program.

6a.13 Drainage Design Documentation Report

Compile drainage design documentation into report format. Include documentation for all the drainage design tasks and associated meetings and decisions, except for stand-alone reports, such as the Pond Siting Analysis Report and Bridge Hydraulics Report.

6a.14 Bridge Hydraulic Report

Calculate hydrology, hydraulics, deck drainage, scour, and appropriate counter measures. Prepare report and the information for the Bridge Hydraulics Recommendation Sheet.

6a.15 Temporary Drainage Analysis

Evaluate and address drainage to adequately drain the road and maintain existing offsite drainage during all construction phases. Provide documentation.

6a.16 Drainage Quantities for EQ Report

The CONSULTANT shall determine drainage pay items and quantities and the supporting documentation.

6a.17 Cost Estimate

Prepare cost estimates for the drainage components, except bridges and earthwork for stormwater management and flood compensation sites.

6a.18 Technical Special Provisions / Modified Special Provisions

6a.19 Hydroplaning Analysis

Perform a hydroplaning analysis to assist in the determination of the appropriate roadway geometry for all necessary locations (both typical sections and critical cross sections) as needed. See the FDOT Hydroplaning Guidance and FDOT Design Manual (FDM) Chapters 210 and 211 for more information.

6a.20 Existing Permit Analysis

Data gathering including desktop analysis of local, state and federal Drainage permits.

6a.21 Other Drainage Analysis

Includes all efforts for a drainage task not covered by an existing defined task.

6a.22 Noise Barrier Evaluation

Evaluate the capacity of drainage openings in noise barriers and locate them to ensure flows are accommodated.

6a.23 Erosion Control Plan

Includes analysis and design of the Erosion Control Plan. Includes creating the design file.

6a.24 Field Reviews

6a.25 Technical Meetings

Meetings with Department staff, regulatory agencies, local governments such as meetings with District Drainage Engineer, the Water Management District, FDEP, etc.

6a.26 Environmental Look-Around Meetings

Convene a meeting with Department staff, regulatory agencies, local governments and other stakeholders to explore watershed wide stormwater needs and alternative permitting approaches.

6a.27 Quality Assurance/Quality Control

6a.28 Independent Peer Review

6a.29 Supervision

6a.30 Coordination

6b DRAINAGE PLANS

The CONSULTANT shall prepare Drainage plan sheets, notes, and details. The plans shall include the following sheets necessary to convey the intent and scope of the project for the purposes of construction.

6b.1 Drainage Map (Including Interchanges)

6b.2 Bridge Hydraulics Recommendation Sheets

6b.3 Drainage Structures

6b.4 Lateral Ditch Plan/Profile & Cross Sections

6b.5 Retention/Detention/Floodplain Compensation Pond Details & Cross Sections

6b.6 Erosion Control Plan

6b.7 SWPPP

6b.8 Quality Assurance/Quality Control

6b.9 Supervision

7 UTILITIES

The CONSULTANT shall identify utility facilities and secure agreements, utility work schedules, and plans from the Utility Agency Owners (UAO) ensuring all conflicts that exist between utility facilities and the DEPARTMENT's construction project are addressed. The CONSULTANT shall certify all utility negotiations have been completed and that arrangements have been made for utility work to be undertaken.

7.1 Utility Kickoff Meeting

Before any contact with the UAO(s), the CONSULTANT shall meet with the District Utility Office (DUO) to receive guidance, as may be required, to assure that all necessary coordination will be accomplished in accordance with DEPARTMENT procedures. CONSULTANT shall bring a copy of the design project work schedule reflecting utility activities. The Consultant shall be prepared to discuss the projects applied utility schedule logic and current UAO contact information.

7.2 Identify Existing Utility Agency Owner(s)

The Consultant shall identify all Utility Agency Owners (UAOs) in the corridor and within and adjacent to the project limits that may be impacted by the project. Identification shall include the updates UAO contact information. The Consultant shall contact Sunshine 811, perform a field visit, and review prior FDOT utility permits, reports, existing plans, and surveys provided.

7.3 Make Utility Contacts

First Contact: The CONSULTANT shall send letters and plans to each Utility Agency Owner (UAO), one set for the utility office, and one set to the DEPARTMENT Offices as required by the District. Includes contact by phone for meeting coordination. Request type, size, location, easements, and cost for relocation if reimbursement is claimed. Request the voltage level for power lines in the project area. Send UAO requests for reimbursement to FDOT for a legal opinion. Include the meeting schedule (if applicable) and the design schedule. Include typical meeting agenda. If scheduling a meeting, give a 4-week notice.

Second Contact: At a minimum of 4 weeks prior to the meeting, the CONSULTANT shall transmit Phase II plans and the utility conflict information (when applicable and in the format requested by the DEPARTMENT) to each UAO having facilities located within the project limits, and one set to the DEPARTMENT Offices as required by the District.

Third Contact: Identify agreements and assemble packages. The CONSULTANT shall send agreements, letters, the utility conflict information (when applicable and in the format requested by the DEPARTMENT) and plans to the UAO(s) including all component sets, one set for the utility office, one set to construction and maintenance if required. Include the design schedule.

Not all projects will have all contacts as described above.

7.4 Exception Processing

The CONSULTANT shall be responsible for transmitting/coordinating the appropriate design reports including, but not limited to, the Resurfacing, Restoration and Rehabilitation (RRR) report, Preliminary Engineering Report, Project Scope and/or the Concept Report (if applicable) to each UAO to identify any condition that may require a Design Alternative. The CONSULTANT shall identify and communicate to the UAO any facilities in conflict with their location or project schedule. The CONSULTANT shall assist with the processing

of design alternative involving Utilities with the UAO and the DEPARTMENT. Assist with processing per the UAM.

7.5 Preliminary Utility Meeting

The CONSULTANT shall schedule (time and place), notify participants, and conduct a preliminary utility meeting with all UAO(s) having facilities located within the project limits for the purpose of presenting the project, review the current design schedule, evaluate the utility information collected, provide follow-up information on compensable property rights from the FDOT Legal Office, discuss the utility work by highway contractor option with each utility, and discuss any future design issues that may impact utilities. This is also an opportunity for the UAO(s) to present proposed facilities. The CONSULTANT shall keep accurate minutes and distribute a copy to all attendees.

7.6 Individual/Field Meetings

The CONSULTANT shall meet with each UAO as necessary, separately or together, throughout the project design duration to provide guidance in the interpretation of plans, review changes to the plans and schedules, standard or selective clearing and grubbing work, and assist in the development of the UAO(s) marked/RGB plans and work schedules. The CONSULTANT is responsible for motivating the UAO to complete and return the necessary documents after each Utility Contact or Meeting.

7.7 Collect and Review Plans and Data from UAO(s)

The CONSULTANT shall review UAO marked plans and data individually as they are received for content, accuracy, utility type, material, and size. Provide to the EOR (designer) for inclusion in the plans. Forward all requests for UAO reimbursement and supporting documentation to the DUO.

7.8 Subordination of Easements Coordination

The CONSULTANT, if requested by the DEPARTMENT, shall transmit to and secure from the UAO the executed subordination agreements prepared by the appropriate DEPARTMENT office. The CONSULTANT shall coordinate with the DUO the programming of the necessary work program funds to compensate the UAO.

7.9 Utility Design Meeting

The CONSULTANT shall schedule (time and place), notify participants, and conduct a Utility meeting with all affected UAO(s). The CONSULTANT shall be prepared to discuss impacts to existing trees/vegetation and proposed landscape, drainage, traffic signalization, temporary traffic control plans (TTCP) (construction phasing), review the current design schedule and letting date, evaluate the utility information collected, provide follow-up information on compensable property rights from FDOT Legal Office, discuss with each UAO the utility work by highway contractor option, discuss any future design issues that may impact utilities, etc., to the extent that they may have an effect on existing or proposed utility facilities with particular emphasis on drainage and TTCP with each UAO. The intent of this meeting shall be to assist the UAOs in identifying and resolving conflicts between

utilities and proposed construction before completion of the plans, including utility adjustment details. Also, to work with the UAOs to recommend potential resolution between known utility conflicts with proposed construction plans as may be deemed practical by the UAO. The CONSULTANT shall keep accurate minutes of all meetings and distribute a copy to all attendees within 3 days. See Task 4.5 (Horizontal/Vertical Master Design File) and Task 4.8 (Cross Section Design Files) for utility conflict location identification and adjustments.

7.10 Review Utility Markups & Work Schedules and Processing of Schedules & Agreements

The CONSULTANT shall review utility marked up plans and work schedules as they are received for content and coordinate review with the designer. Send color markups and schedules to the appropriate DEPARTMENT office(s) such as survey, geotechnical, drainage, structures, lighting, roadway, signals, utilities, landscape architecture, municipalities, maintaining agency, and District Traffic Operations for review and comment if required by the District. Coordinate with the District for execution. Distribute Executed Final Documents. Prepare Work Order for UAO(s). The CONSULTANT shall coordinate with the DUO the programming of necessary Work Program funds.

7.11 Utility Coordination/Follow-up

The CONSULTANT shall provide utility coordination and follow up. This includes follow-up, interpreting plans, and assisting the UAOs with completion of their work schedules and agreements. Includes phone calls, face-to-face meetings, etc., to motivate and ensure the UAO(s) complete and return the required documents in accordance with the project schedule. Ensure the resolution of all identified conflicts. The CONSULTANT shall keep accurate minutes of all meetings and distribute a copy to all attendees. This task can be applied to all phases of the project.

7.12 Utility Constructability Review

The CONSULTANT shall review utility schedules against construction contract time, and phasing for compatibility. Coordinate with and obtain written concurrence from the construction office. See Task 4.5 (Horizontal/Vertical Master Design File) and Task 4.8 (Cross Section Design Files) for utility conflict identification and adjustments.

7.13 Additional Utility Services

The CONSULTANT shall provide additional utility services. Additional services will be determined when the services are required and requested. This item is not usually included in the scope at the time of negotiation. It is normally added as a supplemental agreement when the need is identified.

7.14 Processing Utility Work by Highway Contractor (UWHC)

This includes coordination of utility design effort between the DEPARTMENT and the UAO(s). The CONSULTANT shall conduct additional coordination meetings, prepare and process the agreements, review tabulation of quantities, perform UWHC constructability

and bidability review, review pay items, cost estimates and Technical Special Provisions (TSP) or Modified Special Provision (MSP) prepared by the UAO. This does not include the utility design effort. This item is not usually included in the scope at the time of negotiation. It is normally added as a supplemental agreement when the need is identified. Effort for the EOR is not included in this task, see Roadway Analysis Task Group 4.

7.15 Contract Plans to UAO(s)

If requested by the District, the CONSULTANT shall transmit the contract plans as processed for letting to the UAO(s). Transmittals to UAO(s) via electronic delivery or another agreeable format.

7.16 Certification/Close-Out

This includes hours for transmitting utility files to the DUO and preparation of the Utility Certification Letter. The CONSULTANT shall certify to the appropriate DEPARTMENT representative the following:

All utility negotiations (Full execution of each agreement, approved Utility Work Schedules, Technical Special Provisions or Modified Special Provisions written, etc.) have been completed with arrangements made for utility work to be undertaken and completed as required for proper coordination with the physical construction schedule.

OR

An on-site inspection was made and no utility work will be involved.

OR

Plans were sent to the Utility Companies/Agencies and no utility work is required.

7.17 Other Utilities

The CONSULTANT shall provide other utility services. This includes all efforts for a utility task not covered by an existing defined task. Required work will be defined in the scope and negotiated on a case-by-case basis.

8 ENVIRONMENTAL PERMITS and ENVIRONMENTAL CLEARANCES

The CONSULTANT shall notify the DEPARTMENT Project Manager, Environmental Permit Coordinator, and other appropriate DEPARTMENT personnel in advance of all scheduled meetings with the regulatory agencies to allow a DEPARTMENT representative to attend. The CONSULTANT shall copy in the Project Manager and the Environmental Permit Coordinator on all permit related correspondence and meetings. The Consultant shall use current regulatory guidelines and policies for all permits required as identified in Section 2.4.

8.1 Preliminary Project Research

The CONSULTANT shall perform preliminary project research and shall be responsible for regulatory agency coordination to assure that design efforts are properly directed toward permit requirements. The research shall include but should not be limited to a

review of the project's PD&E documents including the Environmental Document, Natural Resources Evaluation Report, and Cultural Resources Assessment Survey Report.

The CONSULTANT shall research any existing easements or other restrictions that may exist both within or adjacent to the proposed project boundary. Project research may include but should not be limited to review of available: District Right of Way files and databases; federal, state, and local permit files and databases; and local government information including county and property appraiser data. The CONSULTANT shall determine if any Sovereign Submerged Lands easements need to be modified or acquired. Any applicable information will be shown on the plans as appropriate.

8.2 Field Work

8.2.1 Pond Site Alternatives:

The CONSULTANT shall review alternative pond sites as directed by the DEPARTMENT and information shall be included in the Pond Siting Report.

8.2.2 Establish Wetland Jurisdictional Lines and Assessments:

The CONSULTANT shall be responsible for, but not limited to, the following activities:

- Determine landward extent of wetlands and other surface waters as detailed in Rule Chapter 62-340, F.A.C., as ratified in Section 373.4211, F.S.; United States Army Corps of Engineers (USACE) Wetland Delineation Manual (Technical Report Y-87-1); Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Atlantic and Gulf Coastal Plain Region (ERD/EL TR-10-20).
- Collect all data and information necessary to determine the jurisdictional boundaries of wetlands and other surface waters as defined by the rules or regulations of each permitting agency processing a DEPARTMENT permit application for the project.
- Set seasonal high-water levels in adjacent wetlands with biological indicators
- Obtain a jurisdictional determination as defined by the rules or regulations of each permitting agency processing a DEPARTMENT permit application for the project.
- Prepare aerial maps showing the jurisdictional boundaries of wetlands and other surface waters. Aerial maps shall be reproducible, of a scale of 1"=400' or more detailed and be recent photography. The maps shall show the jurisdictional boundaries of each agency. Photo copies of aerials are not acceptable. When necessary, a wetland specific survey will be prepared by a registered surveyor and mapper. All surveyed jurisdictional boundaries are to be tied to the project's baseline of survey.
- Prepare a written assessment of the current condition and functional value of the wetlands and other surface waters. Prepare data in tabular form which includes the ID number for each wetland (and other surface water, if necessary) impacted, size of wetland to be impacted, type of impact, and identify any wetland (by ID number and size) within the project limits that will not be impacted by the project.
- Prepare appropriate agency forms to obtain required permits. Forms may include but are not limited to the USACE "Wetland Determination Data Form - Atlantic

and Gulf Coastal Plain Region"; the USACE "Request for Corps Jurisdictional Determination"; Uniform Mitigation Assessment Method forms and/or project specific data forms.

8.2.3 Species Surveys:

The CONSULTANT shall conduct wildlife surveys as defined by rules or regulations of any permitting agency, or commenting agency that is processing a DEPARTMENT permit.

8.3 Agency Verification of Wetland Data

The CONSULTANT shall be responsible for verification of wetland and other surface water data identified in Section 8.2 and coordinating regulatory agency field reviews, including finalization of assessments and jurisdictional determinations with applicable agencies.

8.4 Complete and Submit All Required Permit Applications

The CONSULTANT shall collect the data and information necessary to prepare the permit applications and obtain the environmental permits required to construct the project as identified in the Project Description and as described in 8.4.1, 8.4.2, and 8.15 (Other Environmental Permits). The CONSULTANT shall prepare each permit application in accordance with the rules and/or regulations of the regulatory agency responsible for issuing a specific permit and/or authorization to perform work. The permit application packages must be approved by the DEPARTMENT prior to submittal to regulatory agencies.

The CONSULTANT will submit all permit applications, as directed by the DEPARTMENT, and be responsible for payment of all permit and public noticing fees, unless directed otherwise by the DEPARTMENT.

8.4.1 Complete and Submit all Required Wetland Permit Applications:

The CONSULTANT shall prepare, complete, and submit required wetland permit (i.e. ERP, Section 404) application packages to the appropriate regulatory agencies. This includes, but is not limited to, applications submitted to WMDs and/or DEP, and USACE. The application package may include but is not limited to attachments (e.g. project location map, aerials, affidavit of ownership, pictures, additional technical analysis, etc.), a cover letter with project description as well as completion of applicable agency forms. The CONSULTANT shall prepare and respond to agency Requests for Additional Information (RAIs), including necessary revisions to the application package. All responses and completed application packages must be approved by the District Permit Coordinator prior to submittal to the regulatory agencies. Geotechnical permitting should also be prepared, submitted, and obtained.

8.4.2 Complete and Submit all Required Species Permit Applications:

The CONSULTANT shall prepare, complete and submit required species permit applications to the appropriate agencies. This includes federal and state protected species permit application packages as required. The work includes completion of application package (e.g. project location map, aerials, affidavit of ownership, pictures, additional technical analysis, etc.), and cover letter with project description as well as completion of applicable forms. The CONSULTANT shall respond to agency RAIs, including necessary revisions to the application package. All responses and completed applications must be approved by the District Permit Coordinator prior to submittal to the regulatory agency.

8.5 Coordinate and Review Dredge and Fill Sketches

The CONSULTANT shall review Dredge and Fill Detail sheets to ensure information on the sketch(es) meet the requirements of the regulatory agencies and are appropriate for environmental permit application submittal and acquisition. The CONSULTANT will also provide environmental data/information as needed to support the preparation of the Dredge and Fill sketches.

8.6 Complete and Submit Documentation for Coordination and/or USCG Bridge Permit Application

The CONSULTANT shall be responsible for the level of effort needed for the USCG authorization in accordance with the regulatory agency requirements.

8.6.1 Prepare and submit required documents for USCG Coordination

The CONSULTANT shall complete appropriate documentation required for the USCG to determine the navigability of the waterway and whether a USCG permit will be required.

8.6.2 Complete and submit USCG Bridge Permit Application

The CONSULTANT shall prepare and submit required USCG bridge permit application. The CONSULTANT shall be responsible for acquiring the USCG approval.

8.7 Prepare Water Management District or Local Water Control District Right of Way Occupancy Permit Application (N/A)

8.8 Prepare Coastal Construction Control Line (CCCL) Permit Application (N/A)

8.9 Prepare USACE Section 408 Application to Alter a Civil Works Project (N/A)

8.10 Compensatory Mitigation Plan (N/A)

8.11 Mitigation Coordination and Meetings (N/A)

8.12 Regulatory Agency Support (N/A)

8.13 Technical Support to the DEPARTMENT for Environmental Clearances and Re-evaluations (use when CONSULTANT provides technical support only) (N/A)

8.14 Preparation of Environmental Clearances and Re-evaluations (use when CONSULTANT prepares all documents associated with a re-evaluation) (N/A)

8.15 Other Environmental Permits (N/A)

8.16 Contamination Impact Analysis (N/A)

8.17 Asbestos Survey (N/A)

8.18 Technical Meetings (N/A)

8.19 Quality Assurance/Quality Control (N/A)

8.20 Supervision (N/A)

8.21 Coordination (N/A)

9 STRUCTURES - SUMMARY AND MISCELLANEOUS TASKS AND DRAWINGS

The CONSULTANT shall analyze, design, and develop contract documents for all structures in accordance with applicable provisions as defined in Section 2.19, Provisions for Work. Individual tasks identified in Sections 9 through 18 are defined in the Staff Hour Estimation Handbook and within the provision defined in Section 2. 20, Provisions for Work. Contract documents shall display economical solutions for the given conditions.

The CONSULTANT shall provide Design Documentation to the DEPARTMENT with each submittal consisting of structural design calculations and other supporting documentation developed during the development of the plans. The design calculations submitted shall adequately address the complete design of all structural elements. These calculations shall be neatly and logically presented on digital media or, at the DEPARTMENT's request, on 8 ½"x11" paper and all sheets shall be numbered. The final design calculations shall be signed and sealed by a Florida-licensed professional engineer. A cover sheet indexing the contents of the calculations shall be included and the engineer shall sign and seal that sheet. All computer programs and parameters used in the design calculations shall include sufficient backup information to facilitate the review task.

9.1 Key Sheet and Index of Drawings

9.2 Project Layout

9.3 General Notes and Bid Item Notes

9.4 Miscellaneous Common Details

9.5 Incorporate Report of Core Borings

9.6 Standard Plans- Bridges

9.7 Existing Bridge Plans

9.8 Structures Quantities for EQ Report

9.9 Cost Estimate

9.10 Technical Special Provisions and Modified Special Provisions

9.11 Field Reviews

9.12 Technical Meetings

9.13 Quality Assurance/Quality Control

9.14 Independent Peer Review

9.15 Supervision

9.16 Coordination

10 STRUCTURES - BRIDGE DEVELOPMENT REPORT

The Consultant shall prepare a Bridge Development Report (BDR). The BDR shall be submitted as part of the Phase I Roadway Submittal, General Requirements.

General Requirements

10.1 Bridge Geometry (N/A)

10.2 Ship Impact Data Collection (N/A)

10.3 Ship Impact Criteria (N/A)

Superstructure Alternatives

10.4 Short-Span Concrete (N/A)

10.5 Medium-Span Concrete (N/A)

10.6 Long Span Concrete (N/A)

10.7 Structural Steel (N/A)

Foundation and Substructure Alternatives

10.8 Pier/Bent (N/A)

10.9 Shallow Foundations / GRS Abutments (N/A)

10.10 Deep Foundations (N/A)

Movable Span

10.11 Data Collection and Design Criteria (N/A)

10.12 Movable Span Geometrics and Clearances (N/A)

10.13 Deck System Evaluation (N/A)

10.14 Framing Plan Development (N/A)

10.15 Main Girder Preliminary Design (N/A)

10.16 Conceptual Span Balance/Counterweight (N/A)

10.17 Support System Development (N/A)

10.18 Drive Power Calculations

10.19 Drive System Development (N/A)

10.20 Power and Control Development (N/A)

10.21 Conceptual Pier Design (N/A)

10.22 Foundation Analysis (FL PIER) (N/A)

10.23 Tender Visibility Study (N/A)

Other BDR Issues

10.24 Aesthetics (N/A)

10.25 TTCP/Staged Construction Requirements (N/A)

10.26 Constructability Requirements (N/A)

10.27 Load Rating for Damaged/Widened Structures (N/A)

10.28 Quantity and Cost Estimates (N/A)

10.29 Quantity and Cost Estimates - Movable Span (N/A)

10.30 Wall Type Justification (N/A)

Report Preparation

10.31 Exhibits (N/A)

10.32 Exhibits - Movable Span (N/A)

10.33 Report Preparation (N/A)

10.34 Report Preparation - Movable Span (N/A)

10.35 BDR Submittal Package (N/A)

Preliminary Plans

When ONLY Phase I plans are final deliverable, use Task Nos. as shown for applicable bridge types for project Activities 12 thru 16. Staffhours to be negotiated and scaled appropriately.

11 STRUCTURES - TEMPORARY BRIDGE (N/A)

N/A

12 STRUCTURES - SHORT SPAN CONCRETE BRIDGE

The CONSULTANT shall prepare plans for Short Span Concrete Bridge(s) at the location(s) specified in Section 2.5.

General Layout Design and Plans

12.1 Overall Bridge Final Geometry (N/A)

12.2 Expansion/Contraction Analysis (N/A)

12.3 General Plan and Elevation (N/A)

12.4 Construction Staging (N/A)

12.5 Approach Slab Plan and Details (N/A)

12.6 Miscellaneous Details (N/A)

End Bent Design and Plans

12.7 End Bent Geometry (N/A)

12.8 End Bent Structural Design (N/A)

12.9 End Bent Plan and Elevation (N/A)

12.10 End Bent Details (N/A)

Intermediate Bent Design and Plans

12.11 Bent Geometry (N/A)

12.12 Bent Stability Analysis (N/A)

12.13 Bent Structural Design (N/A)

12.14 Bent Plan and Elevation (N/A)

12.15 Bent Details (N/A)

Miscellaneous Substructure Design and Plans

12.16 Foundation Layout (N/A)

Superstructure Design and Plans

12.17 Finish Grade Elevation Calculation (N/A)

12.18 Finish Grade Elevations (N/A)

Cast-In-Place Slab Bridges

12.19 Bridge Deck Design (N/A)

12.20 Superstructure Plan (N/A)

12.21 Superstructure Sections and Details (N/A)

Prestressed Slab Unit Bridges

12.22 Prestressed Slab Unit Design (N/A)

12.23 Prestressed Slab Unit Layout (N/A)

12.24 Prestressed Slab Unit Details and Schedule (N/A)

12.25 Deck Topping Reinforcing Layout (N/A)

12.26 Superstructure Sections and Details (N/A)

Reinforcing Bar Lists

12.27 Preparation of Reinforcing Bar List (N/A)

Load Rating

12.28 Load Rating (N/A)

13 STRUCTURES - MEDIUM SPAN CONCRETE BRIDGE (N/A)

N/A

14 STRUCTURES - STRUCTURAL STEEL BRIDGE (N/A)

N/A

15 STRUCTURES - SEGMENTAL CONCRETE BRIDGE (N/A)

N/A

16 STRUCTURES - MOVABLE SPAN (N/A)

N/A

17 STRUCTURES - RETAINING WALLS

The CONSULTANT shall prepare plans for Retaining Wall(s) as specified in Section 2.5.

General Requirements

17.1 Key Sheet

17.2 Horizontal Wall Geometry

Permanent Proprietary Walls

17.3 Vertical Wall Geometry

17.4 Semi-Standard Drawings

17.5 Wall Plan and Elevations (Control Drawings)

17.6 Details

Temporary Proprietary Walls

17.7 Vertical Wall Geometry

17.8 Semi-Standard Drawings

17.9 Wall Plan and Elevations (Control Drawings)

17.10 Details

Cast-In-Place Retaining Walls

17.11 Design

17.12 Vertical Wall Geometry

17.13 General Notes

17.14 Wall Plan and Elevations (Control Drawings)

17.15 Sections and Details

17.16 Reinforcing Bar List

Other Retaining Walls and Bulkheads

17.17 Design (N/A)

17.18 Vertical Wall Geometry (N/A)

17.19 General Notes, Tables and Miscellaneous Details (N/A)

17.20 Wall Plan and Elevations (N/A)

17.21 Details (N/A)

18 STRUCTURES - MISCELLANEOUS

The CONSULTANT shall prepare plans for Miscellaneous Structure(s) as specified in Section 2.5.

Concrete Box Culverts

18.1 Concrete Box Culverts

18.2 Concrete Box Culverts Extensions

18.3 Concrete Box Culvert Data Table Plan Sheets

18.4 Concrete Box Culvert Special Details Plan Sheets

Strain Poles

18.5 Steel Strain Poles

18.6 Concrete Strain Poles

18.7 Strain Pole Data Table Plan Sheets

18.8 Strain Pole Special Details Plan Sheets

Mast Arms

18.9 Mast Arms

18.10 Mast Arms Data Table Plan Sheets

18.11 Mast Arms Special Details Plan Sheets

Overhead/Cantilever Sign Structure

18.12 Cantilever Sign Structures

18.13 Overhead Span Sign Structures

18.14 Special (Long Span) Overhead Sign Structures

18.15 Monotube Overhead Sign Structure

18.16 Bridge Mounted Signs (Attached to Superstructure)

18.17 Overhead/Cantilever Sign Structures Data Table Plan Sheets

18.18 Overhead/Cantilever Sign Structures Special Details Plan Sheets

High Mast Lighting

18.19 Non-Standard High Mast Lighting Structures

18.20 High Mast Lighting Special Details Plan Sheets

Noise Barrier Walls (Ground Mount)

18.21 Horizontal Wall Geometry

18.22 Vertical Wall Geometry

18.23 Summary of Quantities - Aesthetic Requirements

18.24 Control Drawings

18.25 Design of Noise Barrier Walls Covered by Standards

18.26 Design of Noise Barrier Walls not Covered by Standards

18.27 Aesthetic Details

Special Structures

18.28 Fender System (N/A)

18.29 Fender System Access (N/A)

18.30 Special Structures

18.31 Other Structures

18.32 Condition Evaluation of Signal and Sign Structures, and High Mast Light Poles

**18.33 Condition Evaluation of Signal and Sign Structures, and High Mast Light Poles
(No As built or Design Plans Available)**

18.34 Analytical Evaluation of Signal and Sign Structures, and High Mast Light Poles

18.35 Ancillary Structures Report

19 SIGNING AND PAVEMENT MARKING ANALYSIS

The CONSULTANT shall analyze and document Signing and Pavement Markings Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

19.1 Traffic Data Analysis

The CONSULTANT shall review the approved preliminary engineering report, typical section package, traffic technical memorandum and proposed geometric design alignment to identify proposed sign placements and roadway markings. Perform queue analysis.

19.2 No Passing Zone Study

The CONSULTANT shall perform all effort required for field data collection, and investigation in accordance with the DEPARTMENT's Manual on Uniform Traffic Studies.

The CONSULTANT shall submit the signed and sealed report to the DEPARTMENT for review and approval.

19.3 Signing and Pavement Marking Master Design File

The CONSULTANT shall prepare the Signing & Marking Design file to include all necessary design elements and all associated reference files.

19.4 Multi-Post Sign Support Calculations

The CONSULTANT shall determine the appropriate column size from the DEPARTMENT's Multi-Post Sign Program(s).

19.5 Sign Panel Design Analysis

Establish sign layout, letter size and series for non-standard signs.

19.6 Sign Lighting/Electrical Calculations

The CONSULTANT shall analyze and document Lighting/Electrical Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

The CONSULTANT shall prepare a photometric analysis to be submitted as part of the Lighting Design Analysis Report. An analysis shall be provided for each new and/or modified sign panel which requires lighting.

The Consultant shall submit voltage drop calculations and load analysis for each new and/or modified sign panel which requires lighting.

19.7 S&PM Quantities for EQ Report

The CONSULTANT shall determine signing and pavement marking pay items and quantities and the supporting documentation.

19.8 Cost Estimate

19.9 Technical Special Provisions and Modified Special Provisions

19.10 Other Signing and Pavement Marking Analysis

19.11 Field Reviews

19.12 Technical Meetings

19.13 Quality Assurance/Quality Control

19.14 Independent Peer Review

19.15 Supervision

19.16 Coordination

20 SIGNING AND PAVEMENT MARKING PLANS

The CONSULTANT shall prepare a set of Signing and Pavement Marking Plans in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums that includes the following.

20.1 Key Sheet & Signature Sheet

20.2 General Notes/Pay Item Notes

20.3 Project Layout

20.4 Plan Sheet

20.5 Special Details

20.6 Service Point Details

20.7 Guide Sign Data

20.8 Cross Sections (Sign Installations)

20.9 Quality Assurance/Quality Control

The CONSULTANT shall be responsible for the professional quality, technical accuracy and coordination of traffic design drawings, specifications and other services furnished by the CONSULTANT under this contract.

The CONSULTANT shall provide a Quality Control Plan that describes the procedures to be utilized to verify, independently check, and review all design drawings, specifications and other services prepared as a part of the contract. The CONSULTANT shall describe how the checking and review processes are to be documented to verify that the required procedures were followed. The Quality Control Plan may be one utilized by the CONSULTANT as part of their normal operation or it may be one specifically designed for this project.

20.10 Supervision

21 SIGNALIZATION ANALYSIS

The CONSULTANT shall analyze and document Signalization Analysis Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

21.1 Traffic Data Collection

The CONSULTANT shall perform all effort required for traffic data collection, including crash reports, 24 hr. machine counts, 8 hr. turning movement counts, 7 day machine counts, and speed & delay studies.

21.2 Traffic Data Analysis

The CONSULTANT shall determine signal operation plan, intersection geometry, local signal timings, pre-emption phasing & timings, forecasting traffic, and intersection analysis run.

21.3 Signal Warrant Study

21.4 Systems Timings

The CONSULTANT shall determine proper coordination timing plans including splits, force offs, offsets, and preparation of Time Space Diagram.

21.5 Reference and Master Signalization Design File

The CONSULTANT shall prepare the Signalization Design file to include all necessary design elements and all associated reference files.

21.6 Reference and Master Interconnect Communication Design File

The CONSULTANT shall prepare the Interconnect Communication Design file to include all necessary design elements and all associated reference files.

21.7 Overhead Street Name Sign Design

The CONSULTANT shall design Signal Mounted Overhead Street Name signs.

21.8 Pole Elevation Analysis

21.9 Traffic Signal Operation Report

[As defined by the District]

21.10 Signalization Quantities for EQ Report

The CONSULTANT shall determine signalization pay items and quantities and the supporting documentation.

21.11 Cost Estimate

21.12 Technical Special Provisions and Modified Special Provisions

21.13 Other Signalization Analysis

21.14 Field Reviews

The CONSULTANT shall collect information from the maintaining agencies and conduct a field review. The review should include, but is not limited to, the following:

- Existing Signal and Pedestrian Phasing
- Controller Make, Model, Capabilities and Condition/Age
- Condition of Signal Structure(s)
- Type of Detection as Compared with Current District Standards

- Interconnect Media
- Controller Timing Data

21.15 Technical Meetings

21.16 Quality Assurance/Quality Control

The CONSULTANT shall be responsible for the professional quality, technical accuracy and coordination of traffic design drawings, specifications and other services furnished by the CONSULTANT under this contract.

The CONSULTANT shall provide a Quality Control Plan that describes the procedures to be utilized to verify, independently check, and review all design drawings, specifications and other services prepared as a part of the contract. The CONSULTANT shall describe how the checking and review processes are to be documented to verify that the required procedures were followed. The Quality Control Plan may be one utilized by the CONSULTANT as part of their normal operation or it may be one specifically designed for this project.

21.17 Independent Peer Review

21.18 Supervision

21.19 Coordination

22 SIGNALIZATION PLANS

The CONSULTANT shall prepare a set of Signalization Plans in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums, which includes the following:

22.1 Key Sheet & Signature Sheet

22.2 General Notes/Pay Item Notes

22.3 Signalization Plan Sheets

22.4 Interconnect Plans

22.5 Traffic Monitoring Site

22.6 Guide Sign Data

22.7 Special Details

22.8 Service Point Details

22.9 Mast Arm/Monotube Tabulation Sheet

22.10 Strain Pole Schedule

22.11 TTCP Signal

22.12 Temporary Detection Sheet

22.13 Quality Assurance/Quality Control

The CONSULTANT shall be responsible for the professional quality, technical accuracy and coordination of traffic design drawings, specifications and other services furnished by the CONSULTANT under this contract.

The CONSULTANT shall provide a Quality Control Plan that describes the procedures to be utilized to verify, independently check, and review all design drawings, specifications and other services prepared as a part of the contract. The CONSULTANT shall describe how the checking and review processes are to be documented to verify that the required procedures were followed. The Quality Control Plan may be one utilized by the CONSULTANT as part of their normal operation or it may be one specifically designed for this project.

22.14 Supervision

23 LIGHTING ANALYSIS

The CONSULTANT shall analyze and document Lighting Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

23.1 Lighting Justification Report

The CONSULTANT shall prepare a Lighting Justification Report. The report shall be submitted under a separate cover with the Phase I plans submittal, titled Lighting Justification Report. The report shall provide analyses for mainlines, interchanges, and arterial roads and shall include all back-up data such that the report stands on its own. Back up data shall include current ADT's, general crash data average cost from the Florida Highway Safety Improvement Manual, crash details data from the last three years, and preliminary lighting calculations.

The report shall address warrants to determine if lighting warrants are met, and shall include a benefit-cost analysis to determine if lighting is justified. The report shall include calculations for the night-to-day crash ratio as well as a table summarizing the day-time and the night-time crashes. The report shall follow the procedures outlined in the FDOT Manual on Uniform Traffic Studies (MUTS) manual which utilize ADT, Three Year Crash Data, night/day crash ratio, percentage of night ADT, etc.

23.2 Lighting Design Analysis Report (LDAR)

The CONSULTANT shall prepare a Preliminary Lighting Design Analysis Report in accordance with the requirements of the FDOT Design Manual. The report shall be submitted under a separate cover with the Phase II plans submittal. After approval of the preliminary report, the CONSULTANT shall submit a revised report for each submittal.

23.3 Voltage Drop Calculations

The CONSULTANT shall submit voltage drop calculations showing the equation or equations used along with the number of luminaires per circuit, the length of each circuit, the size conductor or conductors used and their ohm resistance values. The voltage drop incurred on each circuit (total volts and percentage of drop) shall be calculated, and all work necessary to calculate the voltage drop values for each circuit should be presented in such a manner as to be duplicated by the District.

The Voltage Drop Calculations shall be submitted as part of the Lighting Design Analysis Report.

23.4 FDEP Coordination and Report

23.5 Reference and Master Design Files

The CONSULTANT shall prepare the Lighting Design file to include all necessary design elements and all associated reference files.

23.6 Temporary Highway Lighting

The CONSULTANT shall develop a Temporary Highway Lighting design and, when required, a Temporary Highway Lighting design file. The Temporary Highway Lighting design must account for all phases of the TTCP and includes the analysis, calculations, and placement of luminaires, supports, conductors, conduits, pull boxes, and electrical power service.

23.7 Design Documentation

The CONSULTANT shall submit a Design Documentation with each plans submittal under a separate cover and not part of the roadway documentation book. At a minimum, the design documentation shall include:

- Phase submittal checklist.
- Structural calculations for special conventional pole concrete foundations.
- Correspondence with the power company concerning new electrical service.

23.8 Lighting Quantities for EQ Report

The CONSULTANT shall determine lighting pay items and quantities and the supporting documentation.

23.9 Cost Estimate

23.10 Technical Special Provisions and Modified Special Provisions

23.11 Other Lighting Analysis

23.12 Field Reviews

The CONSULTANT shall collect information from the maintaining agencies and conduct a field review. The review should include but is not limited to the following:

- Existing Lighting Equipment
- Load Center, Capabilities and Condition/Age
- Condition of Lighting Structure(s)
- Verification of horizontal clearances
- Verification of breakaway requirements

23.13 Technical Meetings

23.14 Quality Assurance/Quality Control

23.15 Independent Peer Review

23.16 Supervision

23.17 Coordination

24 LIGHTING PLANS

The CONSULTANT shall prepare a set of Lighting Plans in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

24.1 Key Sheet & Signature Sheet

24.2 General Notes/Pay Item Notes

24.3 Pole Data, Legend & Criteria

24.4 Project Layout

24.5 Plan Sheets

24.6 Special Details

24.7 Service Point Details

24.8 Temporary Highway Lighting Plan Sheets

24.9 Quality Assurance/Quality Control

The CONSULTANT shall be responsible for the professional quality, technical accuracy and coordination of traffic design drawings, specifications and other services furnished by the CONSULTANT under this contract.

The CONSULTANT shall provide a Quality Control Plan that describes the procedures to be utilized to verify, independently check, and review all design drawings, specifications and other services prepared as a part of the contract. The CONSULTANT shall describe how the checking and review processes are to be documented to verify that the required procedures were followed. The Quality Control Plan may be one utilized by the CONSULTANT as part of their normal operation or it may be one specifically designed for this project.

24.10 Supervision

25 LANDSCAPE ANALYSIS

The CONSULTANT shall analyze and document Landscape Architecture Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

25.1 Data Collection

All research required to collect data necessary to complete the initial design analysis. Includes identifying local ordinances and collection of other project data.

25.2 Site Inventory and Analysis for Proposed Landscape

Includes identification of opportunities and constraints for the proposed landscape project based on existing site conditions. Identify available planting areas for nursery landscape material. Summary of analysis, if required, is included in conceptual design. Roll plots may be required.

25.2a Selective Clearing and Grubbing Site Inventory

25.2b Inventory and Analysis

25.2c1 Vegetation Disposition Plan-Mainline

25.2c2 Vegetation Disposition Plan-Interchange

25.3 Planting Design

25.3a Conceptual Planting Design

Includes delineation of all proposed planting types, scheme development and preliminary costs and reports. The design shall be submitted with the Phase I plans.

25.3a1 Report Preparation

25.3a2 Mainline

25.3a3 Interchanges, Intersections, and Rest Areas

25.3a4 Toll Plazas

25.3b Final Planting Design

Includes identifying the species/type, size, location, spacing, and quality of all plants.

25.3b1 Master Design File Creation

25.3b2 Mainline

25.3b3 Interchanges, Intersections, and Rest Areas

25.3b4 Toll Plazas

25.4 Irrigation Design

25.4a Conceptual Irrigation Design

Conceptual Design: Typically not done in master design file. Includes determination of water and power sources. Phase I design level.

25.4a1 Feasibility Report: Includes analysis of methods, materials and operation costs associated with proposed irrigation system design

25.4a2 Mainline

25.4a3 Interchanges, Intersections, and Rest Areas

25.4a4 Toll Plazas

25.4b Final Irrigation Design

Includes all work in master design files. Irrigation Design includes, but is not limited to, the locations and sizes of pumps, pump stations, mainlines, lateral lines, irrigation heads, valves, backflow and control devices.

25.4b1 Mainline

25.4b2 Interchanges, Intersections, and Rest Areas

25.4b3 Toll Plazas

25.5 Hardscape Design

25.5a Conceptual Hardscape Design (N/A)

25.5b Final Hardscape Design (N/A)

25.6 Roll Plots

Task includes any roll plots for the project to aid in developing final plans (landscape opportunity, disposition, site inventory and analysis, etc.)

25.7 Landscape Quantities for EQ Report

The CONSULTANT shall determine landscape pay items and quantities and the supporting documentation.

25.8 Cost Estimates

25.9 Technical Special Provisions and Modified Special Provisions

25.10 Inspection Services

Services may include: on-site inspection, construction, observation, monitoring, supervision, and any reporting requirements.

25.11 Other Landscape Services

25.12 Outdoor Advertising

Includes all work required to determine locations of all outdoor advertising permitted within the roadway project limits. Includes all work required to determine the proposed view zones and the supporting documentation.

25.13 Field Reviews

25.14 Technical Meetings / Public Meetings

25.15 Quality Assurance/Quality Control

25.16 Independent Peer Review

25.17 Supervision

25.18 Project Coordination

25.19 Interdisciplinary Coordination

26 LANDSCAPE PLANS

The CONSULTANT shall prepare a set of Landscape Plans which includes the following.

26.1 Key Sheet & Signature Sheet (N/A)

26.2 Plant Schedule (Sheet no longer produced) (N/A)

26.3 General Notes/Pay Item Notes (N/A)

26.4 Planting Plans for Linear Areas

26.5 Planting Plans for Non-Linear Areas (Stormwater Facilities, Rest Areas, Interchanges and Toll Plazas)

26.6 Planting Details

26.7 Irrigation Plans for Linear Areas

26.8 Irrigation Plans for Non-Linear Areas (Stormwater Facilities, Rest Areas, Interchange and Toll Plazas)

26.9 Irrigation Details

26.10 Hardscape Plans and Details

26.11 Maintenance Plan (N/A)

26.12 Quality Assurance/Quality Control (N/A)

26.13 Supervision (N/A)

27 SURVEY

The CONSULTANT shall perform survey tasks in accordance with all applicable statutes, manuals, guidelines, standards, handbooks, procedures, and current design memoranda.

The CONSULTANT shall submit all survey notes and computations to document the surveys. All field survey work shall be recorded in approved media and submitted to the DEPARTMENT. Field books submitted to the DEPARTMENT must be of an approved type. The field books shall be certified by the surveyor in responsible charge of work being performed before the final product is submitted.

The survey notes shall include documentation of decisions reached from meetings, telephone conversations or site visits. All like work (such as bench lines, reference points, etc.) shall be recorded contiguously. The DEPARTMENT may not accept field survey radial locations of section corners, platted subdivision lot and block corners, alignment control points, alignment control reference points and certified section corner references. The DEPARTMENT may instead require that these points be surveyed by true line, traverse or parallel offset.

27.1 Horizontal Project Control (HPC)

Establish or recover HPC, for the purpose of establishing horizontal control on the Florida State Plane Coordinate System or datum approved by the District Surveyor (DS) or District Location Surveyor (DLS); may include primary or secondary control points. Includes analysis and processing of all field collected data, and preparation of forms.

27.2 Vertical Project Control (VPC)

Establish or recover VPC, for the purpose of establishing vertical control on datum approved by the District Surveyor (DS) or the District Location Surveyor (DLS).; may include primary or secondary vertical control points. Includes analysis and processing of all field collected data, and preparation of forms.

27.3 Alignment and/or Existing Right of Way (R/W) Lines

Establish, recover or re-establish project alignment. Also includes analysis and processing of all field collected data, existing maps, and/or reports for identifying mainline, ramp, offset, or secondary alignments. Depict alignment and/or existing R/W lines (in required format) per DEPARTMENT R/W Maps, platted or dedicated rights of way.

27.4 Aerial Targets

Place, locate, and maintain required aerial targets and/or photo identifiable points. Includes analysis and processing of all field collected data, existing maps, and/or reports. Placement of the targets will be at the discretion of the aerial firm.

27.5 Reference Points

Reference Horizontal Project Control (HPC) points, project alignment, vertical control points, section, $\frac{1}{4}$ section, center of section corners and General Land Office (G.L.O.) corners as required.

27.6 Topography/Digital Terrain Model (DTM) (3D)

Locate all above ground features and improvements for the limits of the project by collecting the required data for the purpose of creating a DTM with sufficient density. Shoot all break lines, high and low points. Effort includes field edits, analysis and processing of all field collected data, existing maps, and/or reports.

27.7 Planimetric (2D)

Locate all above ground features and improvements. Deliver in appropriate electronic format. Effort includes field edits, analysis and processing of all field collected data, existing maps, and/or reports.

27.8 Roadway Cross Sections/Profiles

Perform cross sections or profiles. May include analysis and processing of all field-collected data for comparison with DTM.

27.9 Side Street Surveys

Refer to tasks of this document as applicable.

27.10 Underground Utilities

Designation includes 2-dimensional collection of existing utilities and selected 3-dimensional verification as needed for designation. Location includes non-destructive excavation to determine size, type and location of existing utility, as necessary for final 3-dimensional verification. Survey includes collection of data on points as needed for designates and locates. Includes analysis and processing of all field collected data, and delivery of all appropriate electronic files.

27.11 Outfall Survey

Locate all above ground features and improvements for the limits of the project by collecting the required data for the purpose of a DTM. Survey with sufficient density of shots. Shoot all break lines, high and low points. Includes field edits, analysis and processing of all field collected data, existing maps, and/or reports.

27.12 Drainage Survey

Locate underground data (XYZ, pipe size, type, condition and flow line) that relates to above ground data. Includes field edits, analysis and processing of all field collected data, existing maps, and/or reports.

27.13 Bridge Survey (Minor/Major)

Locate required above ground features and improvements for the limits of the bridge. Includes field edits, analysis and processing of all field collected data, existing maps, and/or reports.

27.14 Channel Survey

Locate all topographic features and improvements for the limits of the project by collecting the required data. Includes field edits, analysis and processing of all field collected data, maps, and/or reports.

27.15 Pond Site Survey

Refer to tasks of this document as applicable.

27.16 Mitigation Survey

Refer to tasks of this document as applicable.

27.17 Jurisdiction Line Survey

Perform field location (2-dimensional) of jurisdiction limits as defined by respective authorities, also includes field edits, analysis and processing of all field collected data, preparation of reports.

27.18 Geotechnical Support

Perform 3-dimensional (X,Y,Z) field location, or stakeout, of boring sites established by geotechnical engineer. Includes field edits, analysis and processing of all field collected data and/or reports.

27.19 Sectional/Grant Survey

Perform field location/placement of section corners, 1/4 section corners, and fractional corners where pertinent. Includes analysis and processing of all field-collected data and/or reports.

27.20 Subdivision Location

Survey all existing recorded subdivision/condominium boundaries, tracts, units, phases, blocks, street R/W lines, common areas. Includes analysis and processing of all field collected data and/or reports. If unrecorded subdivision is on file in the public records of the subject county, tie existing monumentation of the beginning and end of unrecorded subdivision.

27.21 Maintained R/W

Perform field location (2-dimensional) of maintained R/W limits as defined by respective authorities, if needed. Also includes field edits, analysis and processing of all field collected data, preparation of reports.

27.22 Boundary Survey

Perform boundary survey as defined by DEPARTMENT standards. Includes analysis and processing of all field-collected data, preparation of reports.

27.23 Water Boundary Survey

Perform Mean High Water, Ordinary High Water and Safe Upland Line surveys as required by DEPARTMENT standards.

27.24 Right of Way Staking, Parcel / Right of Way Line

Perform field staking and calculations of existing/proposed R/W lines for on-site review purposes.

27.25 Right of Way Monumentation

Set R/W monumentation as depicted on final R/W maps for corridor and water retention areas.

27.26 Line Cutting

Perform all efforts required to clear vegetation from the line of sight.

27.27 Work Zone Safety

Provide work zone as required by DEPARTMENT standards.

27.28 Vegetation Survey

Locate vegetation within the project limits.

27.29 Tree Survey

Locate individual trees or palms within the project limits.

27.30 Miscellaneous Surveys

Refer to tasks of this document, as applicable, to perform surveys not described herein. The percent for Supplemental will be determined at negotiations. This item can only be used if authorized in writing by the District Surveyor (DS), District Location Surveyor (DLS) or their representative.

27.31 Supplemental Surveys

Supplemental survey days and hours are to be approved in advance by DS or DLS. Refer to tasks of this document, as applicable, to perform surveys not described herein.

27.32 Document Research

Perform research of documentation to support field and office efforts involving surveying and mapping.

27.33 Field Review

Perform verification of the field conditions as related to the collected survey data.

27.34 Technical Meetings

Attend meetings as required and negotiated by the Surveying and Mapping Department.

27.35 Quality Assurance/Quality Control (QA/QC)

Establish and implement a QA/QC plan. Also includes subconsultant review, response to comments and any resolution meetings if required, preparation of submittals for review, etc.

27.36 Supervision

Perform all activities required to supervise and coordinate project. These activities must be performed by the project supervisor, a Florida P.S.M. or their delegate as approved by the District Surveying Office.

27.37 Coordination

Coordinate survey activities with other disciplines. These activities must be performed by the project supervisor, a Florida P.S.M. or their delegate as approved by the District Surveying Office.

28 PHOTOGRAMMETRY

The CONSULTANT shall perform photogrammetric tasks in accordance with all applicable statutes, manuals, guidelines, standards, handbooks, procedures, and current design memoranda.

In addition to the maps and photographic products, the CONSULTANT shall submit all computations to document the mapping. This will include documentation of all decisions reached from meetings, telephone conversations, and site visits.

28.1 Flight Preparation

Review record data, create target diagrams, and plan the mission.

28.2 Control Point Coordination

Determine photo identifiable control points, and mark contact prints.

28.3 Mobilization

Perform pre- and post-flight aircraft inspection; prepare the aircraft and camera for the mission.

28.4 Flight Operations

Operate the aircraft, aerial camera, and other instruments to obtain aerial photography.

28.5 Photo Products

Prepare contact prints, contact diapositives, and photo enlargements.

28.6 LiDAR

Includes data acquisition, post processing of LiDAR data to XYZ coordinates for "bare earth" classification.

28.7 Aerial Triangulation

Measure and adjust control within aerial images.

28.8 Surfaces

Includes collection of break lines and spot elevations.

28.9 Ortho Generation

Includes creation of final images.

28.10 Rectified Digital Imagery (Georeferenced)

Create the rectified digital image.

28.11 Mosaicking

Create the mosaic.

28.12 Sheet Clipping

Create plot files for sheets from the database.

28.13 Topographics (3D)

Prepare topographic maps including surface and planimetrics. (Photogrammetrist will not propose hours for Surfaces and Topographics.)

28.14 Planimetrics (2D)

Prepare 2D planimetric map.

28.15 Drainage Basin

Includes preparing drainage basin maps in clipped "sheet" format.

28.16 CADD Edit

Perform final edit of graphics for delivery of required Microstation design files (.dgn), CADD, and Geopak files.

28.17 Data Merging

Merge photogrammetric files, field survey files, and data from other sources.

28.18 Miscellaneous

Other tasks not specifically addressed in this document.

28.19 Field Review

Perform on site review of maps.

28.20 Technical Meetings

Attend meetings as required.

28.21 Quality Assurance/Quality Control

Establish and implement a QA/QC plan.

28.22 Supervision

Supervise all photogrammetric activities. This task must be performed by the project supervisor, a Florida P.S.M.

28.23 Coordination

Coordinate with all elements of the project to produce a final photogrammetric product.

29 MAPPING

The CONSULTANT will be responsible for the preparation of control survey maps, right of way maps, maintenance maps, sketches, other miscellaneous survey maps, and legal descriptions as required for this project in accordance with all applicable DEPARTMENT Manuals, Procedures, Handbooks, District specific requirements, and Florida Statutes. All maps, surveys and legal descriptions will be prepared under the direction of a Florida Professional Surveyor and Mapper (PSM) to DEPARTMENT size and format requirements utilizing DEPARTMENT approved software, and will be designed to provide a high degree of uniformity and maximum readability. The CONSULTANT will submit maps, legal descriptions, quality assurance check prints, checklists, electronic media files and any other documents as required for this project to the DEPARTMENT for review at stages of completion as negotiated.

Master CADD File

29.1 Alignment

29.2 Section and 1/4 Section Lines

29.3 Subdivisions / Property Lines

29.4 Existing Right of Way

29.5 Topography

29.6 Parent Tract Properties and Existing Easements

29.7 Proposed Right of Way Requirements

The ENGINEER OF RECORD (EOR) will provide the proposed requirements. The PSM is responsible for calculating the final geometry. Notification of Final Right of Way Requirements along with the purpose and duration of all easements will be specified in writing.

29.8 Limits of Construction

The limits of construction DGN file as provided by the EOR will be imported or referenced to the master CADD file. Additional labeling will be added as required. The PSM is required to advise the EOR of any noted discrepancies between the limits of construction line and the existing/proposed right of way lines, and for making adjustments as needed when a resolution is determined.

29.9 Jurisdictional/Agency Lines

These lines may include, but are not limited to, jurisdictional, wetland, water boundaries, and city/county limit lines.

Sheet Files

29.10 Control Survey Cover Sheet

29.11 Control Survey Key Sheet

29.12 Control Survey Detail Sheet

29.13 Right of Way Map Cover Sheet

29.14 Right of Way Map Key Sheet

29.15 Right of Way Map Detail Sheet

29.16 Maintenance Map Cover Sheet

29.17 Maintenance Map Key Sheet

29.18 Maintenance Map Detail Sheet

29.19 Reference Point Sheet

This sheet(s) will be included with the Control Survey Map, Right of Way Map and Maintenance Map.

29.20 Project Control Sheet

This sheet depicts the baseline, the benchmarks, the primary and secondary control points and their reference points including the type of material used for each point, their XYZ

coordinates, scale factors and convergence angles. This sheet(s) may be included with the Control Survey Map, Right of Way Map and Maintenance Map.

29.21 Table of Ownerships Sheet

Miscellaneous Surveys and Sketches

29.22 Parcel Sketches

29.23 TITF Sketches

29.24 Other Specific Purpose Survey(s)

29.25 Boundary Survey(s) Map

29.26 Right of Way Monumentation Map

29.27 Title Search Map

29.28 Title Search Report

29.29 Legal Descriptions (N/A)

29.30 Final Map/Plans Comparison

The PSM will perform a comparison of the final right of way maps with the available construction plans to review the correctness of the type of parcel to be acquired and the stations/offsets to the required right of way. The PSM will coordinate with the EOR to resolve any conflicts or discrepancies and provide documentation of the review.

29.31 Field Reviews

29.32 Technical Meetings

29.33 Quality Assurance/Quality Control

29.34 Supervision

29.35 Coordination

29.36 Supplemental Mapping

This task is to cover efforts resulting from major design and/or development changes after 60% map development that affect the right of way requirements/parent tract property lines and may include any number of tasks. Request and approval to utilize the Supplemental Mapping hours will be in writing and approved by the District Right of Way Surveyor prior to any work being done under this task.

30 TERRESTRIAL MOBILE LiDAR

The CONSULTANT shall perform Terrestrial Mobile LiDAR tasks in accordance with all applicable statutes, manuals, guidelines, standards, handbooks, procedures, and current design memoranda.

In addition to the maps and LiDAR products, the CONSULTANT shall submit all computations and reports to support the mapping. This will include documentation of all decisions reached from meetings, telephone conversations, and site visits.

30.1 Terrestrial Mobile LiDAR Mission Planning

Research and prepare materials necessary for the successful execution of the Mobile LiDAR Mission. This includes but is not limited to route and safety planning, GPS /data acquisition scheduling, weather reports, and site terrain research.

30.2 Project Control Point Coordination

All efforts necessary to coordinate the proper placement of project ground control; i.e.g., base stations, transformation control points, and validation points, supporting the Mobile LiDAR survey .

30.3 Terrestrial Mobile LiDAR Mobilization

Prepare the LiDAR sensor and vehicle for project data collection, and get specialized personnel and equipment on site.

30.4 Terrestrial Mobile LiDAR Mission

Perform site calibrations of LiDAR sensor and collect laser survey data, including any simultaneous base station GPS occupations and operation of any necessary safety equipment.

30.5 Terrestrial Mobile LiDAR Processing

Download and post process collected measurement data from Mobile LiDAR vehicle sensors, and any base stations occupied during mission. Analyze Mobile LiDAR measurement points and scan route overlaps. Separate any large point cloud data sets into manageable file sizes with corresponding indexes.

30.6 Terrestrial Mobile Photography Processing

Process, reference, and name digital photographic imagery files collected during Mobile LiDAR mission.

30.7 Transformation / Adjustment

Adjust LiDAR point cloud data to Project Control points. Create point cloud data file(s) in approved digital format. Prepare required reports of precision and accuracy achieved. If this task is performed by separate firm, or is the final product to be delivered, include effort for Survey Report.

30.8 Classification / Editing

Identify and attribute (classify) point cloud data into requested groups. Classify or remove erroneous points.

30.9 Specific Surface Reporting

Prepare reports, data and/or graphics of specific surface details such as, but not limited to pavement rutting, bridge structure clearance to roadway surface.

30.10 Topographic (3D) Mapping

Produce three dimensional (3D) topographic survey map(s) from collected Mobile LiDAR data. This includes final preparation of Construction Information Management (CIM) deliverable, if applicable.

30.11 Topographic (2D) Planimetric Mapping

Produce two dimensional (2D) planimetric map(s) from collected Mobile LiDAR data.

30.12 CADD Edits

Perform final edit of graphics for delivery of required CADD files. This includes final presentation of CIM deliverable, if applicable.

30.13 Data Merging

Merge Mobile LiDAR survey and mapping files, with other field survey files, and data from other sources.

30.14 Miscellaneous

Other tasks not specifically addressed in this document.

30.15 Field Reviews

Perform on site review of maps.

30.16 Technical Meetings

Attend meetings as required.

30.17 Quality Assurance/ Quality Control

Establish and implement a QA/QC plan.

30.18 Supervision

Supervise all Terrestrial Mobile LiDAR activities. This task must be performed by the project supervisor, a Florida P.S.M.

30.19 Coordination

Coordinate with all elements of the project to produce a final product.

31 ARCHITECTURE DEVELOPMENT (N/A)

N/A

32 NOISE BARRIERS IMPACT DESIGN ASSESSMENT IN THE DESIGN PHASE (N/A)

N/A

33 INTELLIGENT TRANSPORTATION SYSTEMS ANALYSIS

The CONSULTANT shall analyze and document Intelligent Transportation System (ITS) Analysis Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, existing ITS standard operating procedures, ITS master and strategic plans, Florida's SEMP guidelines, National, statewide and/or regional ITS architectures, and current design bulletins.

33.1 ITS Analysis

The CONSULTANT shall review the previously prepared and approved preliminary engineering report(s), typical section package, traffic technical memorandum, adjacent projects programmed by the DEPARTMENT and other local highway agencies, and proposed geometric design alignment to identify impacts to existing ITS components (if applicable) and proposed ITS field device placements. The CONSULTANT shall review the project intelligence files provided by the District's asset maintenance agent(s) related to all previously constructed ITS projects and maintenance documentation for the project corridor to ensure all cited ITS elements are included in this project for replacement and/or restoration.

Systems Engineering Analysis

The CONSULTANT shall perform a systems engineering analysis including a Concept of Operations (ConOps), Project Systems Engineering Management Plan (PSEMP), Requirements Traceability Verification Matrix (RTVM), and other documents as necessary based on project complexity and risk as required by Florida Department of Transportation Systems Engineering and Intelligent Transportation Systems (ITS) Architecture Procedure (Procedure Number 750-040-003).

Design Guidelines

The CONSULTANT shall use applicable DEPARTMENT requirements and guidelines, including, but not limited to, the FDM, Standard Plans, and Standard Specifications for Road and Bridge Construction in the design of ITS. The CONSULTANT design is expected to include the following attributes, facilities, infrastructure, ITS devices, systems, and associated work: [Associated Work]

The CONSULTANT shall review the existing TMC Operations and develop additional incident management service requirements as necessary to support during the Construction Phase of the Project. The CONSULTANT shall coordinate with District's TSM&O Office for additional information regarding existing Incident Management and TMC Operational Procedures (If desired by the District).

All ITS devices shall be compatible with the latest version of the National Transportation Communications for ITS Protocol (NTCIP) and compatible with SunGuide software platform.

The CONSULTANT shall design the project such that all ITS field devices and ancillary components comply with FDOT's Approved Product List (APL) or, when applicable and approved by the DEPARTMENT, FDOT's Innovative Product List (IPL) and are supported within the SunGuide software or other software approved by the DEPARTMENT.

Closed Circuit Television (CCTV) Subsystem

CCTV devices shall be spaced and located as required to meet the Project requirements, Standard Specifications, FDM Section 233.10, District-specific requirements, guidance from the ConOps, and as approved by the DEPARTMENT. The CONSULTANT shall be responsible for the design and exact field locations for the camera assemblies. The camera subsystem shall provide overlapping coverage to overcome visual blockage and to monitor DMS messages, and toll-amount DMS, as directed by the DEPARTMENT.

The CONSULTANT shall select CCTV technologies to meet the Project needs, ConOps requirements, and as approved by the DEPARTMENT. CCTV assemblies may include a camera lowering device (CLD), as directed by the DEPARTMENT.

Per FDM 233.6 and FDM 233.10, the position, height, and design of each camera pole shall be finalized during the design phase of the project. The maximum distance of this type of camera from the DMS sign is specified in FDM. The minimum distance from the DMS sign shall be determined by the CONSULTANT to provide full viewing of the DMS legends based on the analysis performed and approved by the District ITS office. Such analysis includes viewing angle, horizontal and vertical control determination based on the CCTV camera manufacturers that are on APL.

If required by the DEPARTMENT, the CONSULTANT shall determine the camera location by performing a videography study at each proposed camera site. The study shall include video at the proposed camera location and elevation with respect to the roadway elevation. The CONSULTANT shall identify the final number and locations of the camera assemblies based on the videography study.

The camera system design shall ensure that the video quality is not degraded due to wind or vibration. The CONSULTANT shall be responsible for the design of the poles and foundations to minimize the potential for vibration. The CONSULTANT shall prepare cross section plan sheets showing details of horizontal and vertical clearances of the proposed equipment with identified utilities.

Vehicle Detection Subsystem

Vehicle detection devices shall be spaced as required to meet the Project requirements (speed, volume, and occupancy detection), Standard Specifications, FDM Section 233.9, District-specific requirements, guidance from the ConOps, and as approved by the DEPARTMENT.

The CONSULTANT shall select vehicle detection technology to meet the Project needs, ConOps requirements, and as approved by the DEPARTMENT. Detection technologies include induction loops, video imaging, microwave, thermal imaging, wireless magnetometer, and vehicle probe detection systems. In the case of the arterial management systems with a systemwide signal controlled intersections, the CONSULTANT shall select vehicle detection technology type that is currently being used by the local maintaining agencies, if applicable.

The CONSULTANT shall be responsible for the design of a non-intrusive vehicle detection subsystem for the limited access roadway facilities, arterials and sub-arterials with signalized intersections as required by the DEPARTMENT and by local maintaining agencies and specified in the scope of services. The detectors shall be positioned near other ITS field device infrastructure including the fiber-optic splice vaults when feasible to reduce cost. Final detection station locations shall be based on the number of location variables identified during the design phase.

Automatic Vehicle Identification (AVI) Subsystem

AVI detection devices shall be spaced as required to meet the Project requirements, Standard Specifications, FDM 233.9.5, District-specific requirements, guidance from the ConOps, and as approved by the DEPARTMENT.

The CONSULTANT shall select AVI technology to meet the Project needs, Standard Specifications, FDM, District-specific requirements, ConOps requirements, and as approved by the DEPARTMENT.

The CONSULTANT shall coordinate all design efforts for use of SunPass AVI transponders with the Florida's Turnpike Enterprise (FTE) Tolls technical personnel.

Dynamic Message Sign (DMS) Subsystem

The CONSULTANT shall be responsible for the design of the DMS subsystem for the roadway facilities. Both expressway and arterial dynamic message signs (DMS) shall be located to meet the Project requirements, Standard Specifications, FDM 233.11, District-specific requirements, guidance from the ConOps, and as approved by the DEPARTMENT. All FDOT FDM requirements shall be met for DMS locations. DMS locations shall be designed in conjunction with the Project's master signing design. The position of each DMS shall be finalized during the design phase of the project.

The CONSULTANT shall select DMS technology, type, and display to meet the Project requirements and ConOps requirements.

The CONSULTANT shall locate the DMS to satisfy the required sign functionality and to provide the required visibility of the signs. The project communications system shall enable full control of the DMS from the TMC facilities. All DMS hardware, software and related infrastructure components shall be fully compatible with SunGuide software. All DMS shall include a dedicated confirmation CCTV camera that allows for visual verification of the messages posted on the DMS by a TMC Operator (if desired by the District).

The CONSULTANT shall design support structures to accommodate the specified DMS to meet the design functional, operational, and maintenance requirements.

Arterial Dynamic Message Sign (ADMS) Subsystems (Front Access)

ADMS shall be spaced as required to meet the Project requirements, Standard Specifications, FDM Section 233.11, District-specific requirements, guidance from the ConOps, and as approved by the DEPARTMENT.

The CONSULTANT shall select ADMS technologies to meet the Project needs, ConOps requirements, and as approved by the DEPARTMENT.

The ADMS shall be placed for the purpose of Traffic Incident Management (TIM), Integrated Corridor Management (ICM), Active Arterial Management (AAM), and other applications as directed by the DEPARTMENT. ADMS on arterial roadways are to be placed at a distance from the on-ramps of the limited access facilities determined by traffic analysis of the arterial back of queue and to allow time for the motorists to read the sign messages. Communication with ADMS shall be designed so that they can be managed and maintained by the District TMC. All FDOT FDM requirements shall be met for ADMS locations. ADMS locations shall be designed in conjunction with the Project's master signing design on major widening projects. All ADMS shall include a dedicated confirmation CCTV camera that allows for visual verification of the messages posted on the DMS by a TMC Operator (if desired by the District).

Embedded Dynamic Message Signs

Embedded DMS shall be spaced as required to meet the Project requirements, Standard Specifications, FDM Section 233.11, District-specific requirements, express lanes requirements, guidance from the ConOps, and as approved by the DEPARTMENT.

The CONSULTANT shall select Embedded DMS technologies to meet the Project needs, ConOps requirements, and as approved by the DEPARTMENT.

The CONSULTANT design shall include Embedded DMS signs when the project is part of a toll facility, part of an express lanes facility, part of a truck parking availability system, or other usage described in the ConOps, as required by the DEPARTMENT. The Embedded DMS signs are comprised of DMS panels embedded in a static sign panel. The Embedded DMS may have one or more line of text depending upon the application. Embedded DMS are to be located on the main line, express lanes, ramps, and on the crossroads as required to meet the project needs.

All Embedded DMS shall include a dedicated confirmation CCTV camera that allows for visual verification of the messages posted on the Embedded DMS by a TMC Operator (if desired by the District).

Dynamic Trailblazing Sign Subsystems (DTBS)

DTBS shall be spaced as required to meet the Project requirements, Standard Specifications, FDM, District-specific requirements, guidance from the ConOps, and as

approved by the DEPARTMENT to support evacuation, incident management, detour management, special event traffic management, active arterial management and/or integrated corridor. If directed by the DEPARTMENT, the CONSULTANT shall develop the well-defined active traffic management detour plan.

The CONSULTANT shall select DTBS technologies to meet the Project needs, ConOps requirements, and as approved by the DEPARTMENT.

The CONSULTANT shall design the DTBS to recommend directions of travel to motorists. The active DTBS Embedded DMS and/or blank-out signs shall be sized based on the proposed legends or cardinal directions used for the active traffic management detour plans. The DTBS shall be connected to the fiber optic network to be operated and managed at the TMC. The DTBS will be mounted on new support structure or if mounted on existing structure, the required structural analysis shall be performed for the existing structure. The size and types of dynamic and active portion of the signs shall be coordinated with the District ITS office prior to design.

Roadway Weather Information Systems (RWIS)

RWIS shall be spaced as required to meet the Project requirements, Standard Specifications, FDM 233.12.1, District-specific requirements, guidance from the ConOps, and as approved by the DEPARTMENT.

The CONSULTANT shall select RWIS technologies to meet the Project needs, ConOps requirements, and as approved by the DEPARTMENT.

The CONSULTANT shall develop or modify Technical Special Provisions or Modified Special Provisions for RWIS based upon the unique needs of the project. The CONSULTANT shall ensure that, each RWIS site consists of a remote processing unit (RPU), communication hardware, and determine the site-specific components from below, as required by the DEPARTMENT::

- Fog/Smoke Detection sensor;
- Classifying Precipitation;
- Precipitation Occurrence Sensor;
- Water Film Height Sensor;
- Air Temperature/Relative Humidity Sensor;
- Wind Speed and Direction Sensor;
- RWIS Tower/Pole Structure, foundation, base, and cabinet with electrical service, and lightning protection & grounding assembly; and,
- Communication hardware.

When required by the DEPARTMENT, the Water Film Height Sensor shall be included in the RWIS design for hydroplaning detection and to activate advance warning signs with flashing beacons. The RWIS Water Film Height Sensor shall be a fully autonomous Non-Invasive Road Weather Intelligent Sensor (NIRS) with optical principles mounted above the roadway that can measure the water film depths and temperature for the purpose of determining hydroplaning conditions and warning the motoring public. In addition, it shall communicate via 120 volts active current (VAC) Web Relay Controller with one (1) or

more Flashing Beacon Warning Signs, and Fiber Optic-Based Communications to the TMC. It shall include all ancillary components required for a complete and acceptable operational system. This ITS subsystem shall be connected to the existing Department ITS and fiber optic network via a proposed new Managed Field Ethernet Switch (MFES) inside a proposed local hub. This ITS subsystem shall provide real time data and analog outputs for roadway water film height and ice detection layer thickness and values.

Traffic Signal Data Subsystem

The Traffic Signal Data Subsystem shall be provided at locations as required to meet the Project requirements, Standard Specifications, FDM, District-specific requirements, guidance from the ConOps, and as approved by the DEPARTMENT.

The CONSULTANT shall select Traffic Signal Data Subsystem technologies to meet the Project needs, ConOps requirements, and as approved by the DEPARTMENT.

The CONSULTANT shall design the Traffic Signal Data Subsystem to include, as a minimum, Advance Transportation/Traffic Controllers (ATC) provided at the signalized intersections. The ATC shall include an open architecture hardware and software platform to interface with the latest network-wide supervisory Advanced Traffic Management System (ATMS) software currently being used by the local highway agencies supporting a wide variety of Intelligent Transportation Systems (ITS) applications. This includes traffic management, safety, and security.

The CONSULTANT shall design other data-related applications for the Traffic Signal Data Subsystem, as directed by the DEPARTMENT, such as for basic Connected and Automated Vehicles (CAV) elements, ramp signaling, reliable data collection and analytics using Automated Traffic Signal Performance Measures (ATSPM), and edge computing capabilities.

Connected and Automated Vehicles (CAV) Subsystems

The CAV Subsystem shall be provided at locations as required to meet the Project requirements, Standard Specifications, District-specific requirements, guidance from the ConOps, and as approved by the DEPARTMENT.

The CONSULTANT shall select CAV Subsystem technologies to meet the Project needs, ConOps requirements, and as approved by the DEPARTMENT.

The CONSULTANT shall develop or update CAV Subsystem Technical Special Provisions or Modified Special Provisions (MSP/TSP) for Roadside Units (RSU) and other CAV Subsystem features based upon the unique needs of the project. The CONSULTANT shall ensure that each RSU site consists of a remote processing unit (RPU), communication hardware, mounting hardware, cabling, power supply, and other site-specific components as required. The CONSULTANT shall develop RSU requirements for communication between connected vehicles and roadside equipment such as ATC, detection systems, and warning beacons that are compatible with both Cellular Vehicle to Everything (C-V2X) communication and Dedicated Short Range Communication (DSRC) national standards and protocols. The CONSULTANT shall also coordinate FCC licensing requirements for

two-way real-time C-V2X communication and DSRC, depending on national standards and policies, with the DEPARTMENT's Statewide TSM&O program office. The MSP/TSP shall address integration with the DEPARTMENT's Security Management Credential System (SCMS) requirements.

The MSP/TSP shall require RSU field equipment to be on the FDOT APL, the FDOT IPL or, as a minimum, tested at the Traffic Engineering Research Laboratory (TERL) prior to approval for use on the project. The MPS/TSP shall require RSU field equipment to be supported by the central system in the TMC and to be capable of transmitting required messages and data to and from the roadway and users via vehicle on-board units (OBU) and other mobile devices over the applicable communication schema in compliance with industry standards.

When used inside a traffic signal cabinet, the CONSULTANT shall ensure the cabinet is equipped with ATC and the RSU is connected to the signal controller, Ethernet switch, and the above ground radio, and GPS antennas.

When used on the interstate, the CONSULTANT shall develop the TSP/MSP to ensure the RSU is housed inside a corrosion-resistant enclosure that is NEMA 4X with IP66 rating, and meets the system requirements broken into the following categories:

- Power
- Environmental
- Physical
- Functional
- Performance
- Interface

Wrong-way Vehicle Detection Systems (WWVDS)

The WWVDS shall be provided at locations as required to meet the Project requirements, Standard Specifications, FDM, Traffic Engineering and Operations Bulletin 19-03, District-specific requirements, guidance from the ConOps, and as approved by the DEPARTMENT.

The CONSULTANT shall select WWVDS technologies to meet the Project needs, ConOps requirements, Traffic Engineering and Operations Bulletin 19-03, and as approved by the DEPARTMENT.

The CONSULTANT shall select the WWVDS technology for compatibility with the District SunGuide software version and to meet the project needs. The WWVDS shall collect and process data locally prior to sending a notification to the TMC. The CONSULTANT shall design the WWVDS for remote configuration, calibration, monitoring, and diagnostic of real-time traffic activities from the TMC using the SunGuide software and software provided by the detection system vendor. The WWVDS shall perform to meet the project requirements under all environmental and traffic conditions expected for the corridor. The WWVDS shall detect wrong way drivers within the specified accuracy. Vibration and shocks shall not affect the performance of the system. The WWVDS and highlighted signs shall be hardwired for power and communications to the

main controller. Design shall be in accordance with Traffic Engineering and Operations Bulletin 19-03.

Structural Health Monitoring System (SHMS) Connectivity Subsystem

The SHMS connectivity shall be provided at locations as required to meet the Project requirements, Standard Specifications, FDM, District-specific requirements, guidance from the ConOps, and as approved by the DEPARTMENT.

The CONSULTANT shall select SHMS connectivity technologies to meet the Project needs, ConOps requirements, and as approved by the DEPARTMENT.

The CONSULTANT shall design the SHMS connectivity subsystem which includes a fully operational ITS cabinet containing the data acquisition logger, MFES, UPS, RPMU, and all necessary surge protection devices to receive the data from various optical sensors or non-optical sensors connected to the local data acquisition enclosures installed inside the bridge arches, attached inside the girders, and the stayed cables supporting the main spans. The CONSULTANT shall coordinate with the structural and SHMS disciplines to provide for a collapsed ring topology of the communication scheme and provide for connectivity to the fiber optic network. The SHMS data shall be transmitted via the existing and proposed 10 Gigabits per second fiber optic cable plant to the designated remote operation center for monitoring by the District Bridge Operations and Maintenance.

The CONSULTANT is not responsible for the design and location of the SHMS sensors, sensor types, electrical, and data acquisition enclosures and hardware.

Ramp Signaling Subsystem (RSS)

The RSS shall be provided at locations as required to meet the Project requirements, Standard Specifications, FDM 233.12.2, District-specific requirements, guidance from the ConOps, and as approved by the DEPARTMENT.

The CONSULTANT shall select RSS technologies to meet the Project needs, ConOps requirements, and as approved by the DEPARTMENT.

The CONSULTANT shall design the Ramp Signaling Subsystem at the locations determined by the Department as part of previous traffic studies that justified the installation. The RSS shall provide the TMC the ability to remotely control the RSS via current controlling software supported by the SunGuide. The RSS shall include the following components:

- Cabinet equipment including: controller, modem, display panel, detector amplifiers, output/power distribution assembly, load switches, current monitor, flasher for warning sign beacon, ability to support continuous operation for a minimum 2 hours in the event of power loss, and report power management unit.
- Supporting infrastructure including: conduits; RSS monitoring CCTV; two-head (red and green) LED signal display; and, LED flashing beacons.
- Detection including: mainline (upstream and downstream), RSS demand and passage, and ramp queue detectors.

- Signing including: Ramp Signaled When Flashing (W3-4); One Vehicle per Green (R10-13); Two Vehicle per Green (Modified R10-13), if needed; All Vehicles Stop on Red; One car per Green Each Lane (R89-1); Right Lane Ends (W4-2R); Merging Traffic (W4-1)
- Pavement markings including: 12-inch-wide stop bar running from edge line to edge line and 6-inch-wide solid white centerline for a minimum distance of 250 feet upstream of the stop bar and terminated at the stop bar on two-lane metered ramps.

Truck Parking Availability System (TPAS)

The TPAS shall be designed at locations as required to meet the Project requirements, Standard Specifications, FDM, District-specific requirements, guidance from the ConOps, and as approved by the DEPARTMENT.

The CONSULTANT shall select TSPA Subsystem technologies to meet the Project needs, ConOps requirements, and as approved by the DEPARTMENT.

ITS Software Subsystem

The ITS Software Subsystem shall be provided as required to meet the Project requirements, Standard Specifications, FDM, District-specific requirements, guidance from the ConOps, and as approved by the DEPARTMENT.

The CONSULTANT shall develop ITS Software Subsystem requirements to meet Project needs, the ConOps, and as approved by the DEPARTMENT.

33.2 Communications Subsystem Analysis

See FDM 233.4, 233.5, and 233.8 for communication systems design requirements. The CONSULTANT shall review the existing communication files in GIS or PDF format provided by the DEPARTMENT and or the local highway agencies and create an overall communication map to summarize mapping data associated with the fiber optic conduits and cables connectivity. This provides a communication location-based intelligence for the project and will be used in the communication design. In addition, the CONSULTANT shall include high level overview of how the project corridor(s) are connected to the TMC communication network including the existing and proposed master communication hubs.

The CONSULTANT shall develop a communications plan to determine the optimal communications medium for the project corridor. The plan shall be developed prior to submittal of Phase I plans. The plan shall identify communications media alternatives and provide a cost estimate that includes initial, operations and maintenance cost for the life cycle of the communications network. The plan shall ensure that video, voice, and data will be communicated in real-time between center to-field and center-to-center (C2C) nodes as applicable. The communications system design must utilize non-proprietary, open-architecture, standards-based, robust, scalable, and proven technology. The communication plan analysis shall address communication and connections between field devices, communications and connections between field devices and the TMC, center-to-center communications between TMCs, and any other communication links or connections required to meet project goals and ConOps guidance. The plan must include bandwidth

analysis and recommendations, needs assessment, and provide recommendations regarding minimum requirements, media, network devices, protocols, network topology, communication redundancy, future needs, spare capacity, and any communications or data sharing with other agencies.

The plan must include loss budget analysis and calculations for the optical cable lengths and bandwidth. The CONSULTANT shall provide the calculations confirming the loss budgets are in conformance with allowable values established in the standard specifications. The CONSULTANT shall calculate the loss budgets based on distance, anticipated fusion splices, and connectors to ensure the cabling will work with the links intended to be used. After installation, the loss budget for the cabling is compared to the actual test results during final acceptance to ensure the cable plant is installed properly.

For major widening projects where the existing underground fiber optic communication cables and ITS sites are impacted, the CONSULTANT shall review the roadway, drainage, and TTCP plans to analyze and identify the magnitude of impact to the existing ITS infrastructure. The CONSULTANT shall prepare the Maintenance of Communication (MOC) concept that supports the final design in efforts to maintain and sustain center-to-field device connectivity and operability to the existing ITS field devices previously deployed along the project corridor. The MOC analysis shall consider and mitigate the impacts of the project's various construction phases so as to sustain center-to-field devices connectivity and operability in order to maintain operational quality as a minimum at the level provided prior to construction start and minimizing down time of the critical devices.

After approval of the plan, the CONSULTANT shall submit a revised plan including a detailed design analysis for each submittal. The CONSULTANT's communications design shall include multiple redundant paths for each location, which allows for automatic switching of communications path onto a secondary path, if the primary path is impacted (if desired by the District).

33.3 Grounding, Surge Suppression, and Lightning Protection Analysis

The CONSULTANT shall be responsible for a complete and reliable grounding, surge suppression, and lightning protection design to provide personnel and equipment protection against faults, surge currents and lightning transients. When Standards Plans depicting air terminal device heights above poles or equipment are not available, the height of the air terminal above poles or equipment shall be determined using applicable standards. See FDM 233.3.8 for additional design requirements.

33.4 Power Subsystem

See FDM Section 233.3 for ITS Power Design Requirements. The CONSULTANT shall be responsible for an electrical design in accordance with all NEC requirements. No solar power should be utilized as a power solution for the Project unless otherwise approved by the DEPARTMENT. To enhance power reliability, the CONSULTANT shall design a power distribution and backup system consisting of, at a minimum, underground power conduits and conductors, transformers, diesel fuel generators, automatic transfer switches (ATS), uninterruptable power supply (UPS), electrical distribution panel, equipment

framing, reinforced concrete pad for the generator, site drainage, site security fencing and security camera (as directed by the DEPARTMENT), power command and control, Ethernet-based Modbus, and ITS Cabinet with Remote Power Management Unit (RPMU), and all associated equipment. The power backup system shall supply electrical power in event of commercial power supply failure for all system components. Power equipment shall be installed in areas to avoid wet locations. All connections and equipment shall be protected from moisture and water intrusion. The CONSULTANT shall ensure that vandal resistant mechanisms for all electrical infrastructure shall be included as part of the Design.

The CONSULTANT shall submit the power system design and voltage drop calculations for the power distribution system as part of phase II, III, and IV design submittals. The CONSULTANT shall conduct a short circuit and protection coordination study for the designed power system and document the study as part of the power system design report.

33.5 Voltage Drop Calculations

See FDM Section 233.3.6 for voltage drop design requirements. The electrical design shall address allowable voltage drops per the NEC. The CONSULTANT shall submit voltage drop calculations for any electrical circuit providing power to the ITS field devices beyond the electric utility service point. The calculations shall document the length of each circuit, its load, the size of the conductor or conductors and their ohm resistance values and the required voltages from the service point to the respective ITS devices to maintain voltage drops within allowable limits. The voltage drop incurred on each circuit (total volts and percentage of drop) shall be calculated, and all work necessary to calculate the voltage drop values for each circuit should be presented in such a manner as to be duplicated by the District. Load analysis calculations shall be submitted covering electrical path from all power sources to each ITS site connected to each power source. All voltage drop calculations shall allow for future expansion of ITS infrastructure, if identified in the Project ConOps.

33.6 Design Documentation

The CONSULTANT shall submit a Design Documentation Book with each plan submittal under separate cover and not part of the roadway documentation book. At a minimum, the design documentation book shall include:

- Quantities and engineers estimate for all applicable items on plans.
- Phase submittal checklist.
- Three-way quantity check list
- Structural calculations for all structures
- Power Design Analysis, voltage drop calculations, and load analysis calculations.
- Correspondences including utility design meeting and conflict resolutions.
- Electrical Power Service Letter of Confirmation.
- Subsurface Utility Exploration tables for each ITS support structure.

33.7 Existing ITS

The CONSULTANT shall research any required legacy system or system components that may be impacted by new work, such as: existing communications; existing types, numbers,

locations, models, manufacturers, and age of ITS devices; as-built plans; existing operating software; existing center-to-field devices; and C2C communications and capabilities.

The project intelligence files provided by the DEPARTMENT and researched by the CONSULTANT may include the following documents:

- Existing ITS field devices compared to the latest FDOT Standards and District requirements: device type, model, manufacturer, capabilities, condition, date installed, and historical maintenance logs. The DEPARTMENT will provide the ITS FM data, when available, to the CONSULTANT upon request.
- Condition of support structure(s), and associated mechanical brackets, and vertical hangers.
- Electrical power related to the existing demand loads, sizes of the main and branch circuit breakers for the service disconnect, underground or overhead service feeder sizes from the power company transformer to the meter base.
- Existing fiber optic allocation as a graphical display of the existing buffer tube for the ITS devices at the Managed Field Ethernet Switch points, the buffer allocated for the existing local communication hubs, given number of connections within a corridor while maintaining the maximum number of physical connection on a specific Local Area Network (LAN), and local hubs to existing master communication hubs.
- A KMZ file of the existing fiber optic pull and splice boxes, ITS devices, local hubs, power service poles with latitudes and longitudes data.
- Underground infrastructure.
- Proximity to utilities.
- Other field reconnaissance as necessary to develop a complete ITS design package.

33.8 Queue Analysis

The CONSULTANT shall perform a queue analysis at high volume interchanges and high frequency conflict / crash locations to determine optimal placement of DMS using project forecasted traffic volumes. This analysis shall be performed prior to submittal of the Phase I plans. The Consultant shall perform other traffic engineering analysis as necessary to ensure that the DMS locations are selected based on optimum message delivery to the motorists.

The CONSULTANT shall perform field observation of the existing traffic patterns during the normal peak hours to determine the optimal placement of DMS, ADMS, CCTV cameras, and detection sites.

The CONSULTANT shall perform lane closure analysis and determine the time periods where construction activities can be performed. The lane closure analysis shall be performed using the available traffic data.

In cases when traffic technical memorandums have been performed by others and are available through the DEPARTMENT, or available from TMC CCTV camera surveillance sites, the CONSULTANT shall use these reports and information in lieu of performing traffic engineering and safety analysis.

The CONSULTANT shall coordinate with District's TSM&O Office for additional information regarding existing Incident Management and TMC Operational Procedures to address maintenance of ITS and post construction requirements.

33.9 Reference and Master ITS Design File

The CONSULTANT shall prepare the ITS design file to include all necessary design elements and the reference files for topo, R/W roadway, utilities files, etc. This effort includes the design and layout of all proposed ITS devices and electrical service points, conduits, pull boxes, conductor sizing, generators, and transformers. All existing ITS infrastructure shall be referenced to the new ITS plan sheets (if applicable).

33.10 Reference and Master Communications Design File

The CONSULTANT shall prepare the communication design file to include all necessary design elements and all associated reference files as well as reference files of topo, R/W, roadway, utilities files, existing ITS communications infrastructure, etc. This effort includes design and layout of proposed communications conduit, cabinet, pull boxes, splice boxes, standard route markers, communications plan overview, fiber optic sizing, fiber optic splicing, connections, communications hubs, etc.

33.11 ITS Poles and Overhead Structures Elevation Analysis

See FDM Section 233.6 for ITS Poles and Structures design requirements. The CONSULTANT shall evaluate pole elevation requirements and design pole heights to meet the Project requirements including field of view; elimination of occlusion; site access for maintenance vehicles and personnel; access to pole mounted equipment, such as CCTV cameras, traffic detectors, and cabinets; and probability of lightning strike.

The CONSULTANT shall coordinate with roadway, structures, and drainage disciplines to confirm that the elevations are updated during various design phases, and the ITS poles and overhead structure details are revised and designed with the correct heights, lengths, foundation depths and sizes.

33.12 DMS Sign Panel Design Analysis

The CONSULTANT shall design all ITS signing in conjunction with the Roadway Master Signing. This includes any static sign panel that includes changeable message elements. Expressway and arterial full size DMS shall not be co-located with other static signs. [If desired by the District].

The DMS sign panel analysis applies to walk-in DMS, front access ADMS, and embedded Toll Amount and Status DMS and Dynamic Trail Blazing Signs. The CONSULTANT shall provide the following design information for the DMS sign design basis and fabrication:

- Pixel Pitch
- Number of display messages
- Character height
- Number of characters per line
- Character spacing

- Mechanical properties of the sign such as weight, height, width, depth, and not including the vertical hanger size and weight.

33.13 ITS Quantities for EQ Report

The CONSULTANT shall determine ITS pay items and quantities and the supporting documentation.

33.14 Cost Estimate

The CONSULTANT shall prepare an engineer's cost estimate for the project using historical data from the FDOT or from other Industry sources. The CONSULTANT shall also load the category information, pay items and quantities into AASHTOWare Project Preconstruction.

33.15 Technical Special Provisions and Modified Special Provisions

The CONSULTANT shall develop Technical Special Provisions (TSP) and Modified Special Provisions (MSP) for the specific items or conditions of the project that are not addressed in the FDOT's Standard Specifications, Supplemental Specifications and Special Provisions.

33.16 Other ITS Analyses

[Add detailed project needs for any other ITS-related analyses]

33.17 Field Reviews

The CONSULTANT shall conduct a field review for the required phase submittals. The review shall identify necessary data for all elements of the project including, but not limited to, the following:

- Existing ITS Field Devices as compared with the latest FDOT standards and District requirements
- Device Make, Model, Capabilities, Condition / Age, Existence of SunGuide Software Driver
- Condition of Structure(s), cabinets, and other above-ground infrastructure and devices
- Type of Detection as Compared with Current District Standards and preferences.
- Underground Infrastructure
- Proximity of other utilities
- Any other field reconnaissance as necessary to develop a complete ITS design package

33.18 Technical Meetings

The CONSULTANT shall attend meetings as necessary to support the project.

33.19 Quality Assurance / Quality Control

The CONSULTANT shall be responsible for the professional quality, technical accuracy and coordination of designs, drawings, specifications, and other services and work furnished by the CONSULTANT under this contract.

The CONSULTANT shall provide a Quality Control Plan that describes the procedures to be utilized to verify, independently check, and review all design drawings, specifications, and other documentation prepared as a part of the contract. The CONSULTANT shall describe how the checking and review processes are to be documented to verify that the required procedures were followed. The Quality Control Plan may be one utilized by the CONSULTANT as part of their normal operation or may be one specifically designed for this project. The CONSULTANT shall utilize the District's quality control checklist. The responsible Professional Engineer that performed the Quality Control review shall sign a statement certifying that the review was conducted.

The CONSULTANT shall, without additional compensation, correct all errors or deficiencies in their works.

33.20 Supervision

The CONSULTANT shall provide all efforts required to supervise all technical design activities.

33.21 Coordination

The CONSULTANT shall coordinate with Survey, Geotech, Drainage, Structures, Lighting, Roadway Design, Utilities, municipalities, maintaining agencies and Traffic Operations to produce a final set of construction contract documents and to ensure that a high degree of accuracy for the design plans is achieved. The CONSULTANT shall coordinate with the roadway Utility Adjustment Plan to incorporate all ITS support structural foundations symbols drawn to scale in the Utility Adjustment Plans and attend the utility design meetings conveying the information to all utility owners to preserve the location of the proposed foundations and avoid any conflicts.

34 INTELLIGENT TRANSPORTATION SYSTEMS PLANS

The CONSULTANT shall prepare a set of ITS Plans in accordance with the FDOT Design Manual that includes the following:

34.1 Key Sheet

The CONSULTANT shall prepare the key sheet in accordance with the latest format depicted in the FDM.

MUTCD

Standard Specifications, Developmental Specifications

Standard Plans

34.2 General Notes / Pay Item Notes

The CONSULTANT shall include all pertinent general notes and pay item notes as deemed fit and as established by the District.

34.3 Project Layout

The CONSULTANT shall prepare plan sheet(s) with an overview of the entire project that include stations and offsets, project limits, intersection locations, ramps, railroads crossings, devices, device identification using SunGuide nomenclature, and plan sheet numbering and coverage.

34.4 Typical and Special Details

The CONSULTANT shall prepare typical and / or special details for conditions in the project not addressed by the DEPARTMENT's Standard Plans for Design, Construction, Maintenance, and Utility Operations on the State Highway System. The CONSULTANT shall prepare special details not addressed by FDOT Standard Plans, including block diagrams, hub cabinets, wiring diagrams, solar power service, and special mounting details, horizontal directional drilling at critical crossings, wireless ethernet equipment for local and broadband communication, Ethernet based Blue Toad, Ramp Signaling System, RSU block diagrams, Power station site plan, Field Equipment Shelters for master hubs, electrical and communication conduit, equipment inside box girders..

34.5 Plan Sheet

The CONSULTANT shall prepare the ITS plan sheets utilizing the Design file to include all necessary information related to the project design elements and all associated reference files. The plan sheets shall include general and pay item notes and pay items. The plans shall depict the location of ITS devices and cabinets, pull boxes, splice boxes, conduit runs, electrical service points, conduit, pull boxes, and conductors, and underground and overhead utilities, if applicable. Devices shall be located by station and offset as well as setback from the travel way. The CONSULTANT shall ensure the ITS sites and ground mounted cabinets locations are not in wetlands or wet drainage channels, do not interfere with protected species, meet the OSHA circle of safety from the overhead energized lines, and do not conflict with underground utilities.

34.6 ITS Communications Plans

The CONSULTANT shall prepare plans for the communications network. These plans shall consist of block diagrams, splicing diagrams, port assignments, wiring diagrams, and all other information necessary to convey the design concept to the contractor. These plans shall be included in the ITS plan set and be prepared in a manner consistent with immediately adjacent ITS project installations (planned or installed). Communication plans shall include conduit, fiber, pull and splice boxes, ITS devices, communication lateral drops, fiber connection hardware, pay items etc.

The communication system shall be an open-architecture, non-proprietary, real-time, multimedia communications network. The communication system design must be compatible and completely interoperable with the existing systems.

[Discuss any needs or allowance for temporary communication connectivity options]

The CONSULTANT's design shall include protecting and maintaining the existing ITS infrastructure. For locations where existing ITS infrastructure is impacted, the CONSULTANT's design shall include mitigation to minimize the downtime of existing

system as per the District's requirements and prepare the Maintenance of Communication (MOC) plans. The CONSULTANT shall develop the MOC sheets for the project, providing temporary communications as necessary, notes, details, and direction applicable to the ITS elements and associated communications for inclusion in the MOC plans. The MOC plans shall include the notes, plan sheets, cross sections showing existing and proposed grades with the tables defining the stations limits for the conduit depths below existing and proposed grades for various construction phases.

If applicable, the CONSULTANT shall review the roadway TTCP, drainage, structures, and landscaping plans and prepare the MOC plans for each construction phase. The MOC plans shall include construction phasing notes, half cross sections depicting existing and proposed grades, roadway templates, drainage ponds, flood mitigation zones, provide tables depicting the station range, location and depth of the proposed fiber optic trunk line below existing and proposed grades. The MOC plans shall optimize the reliable field-to-center (F2C) connectivity and operability of the ITS field devices previously deployed along the project corridor. The MOC design effort shall mitigate the impacts of the project's various construction phases so as to sustain center-to-field devices connectivity and operability, maintaining operational quality as a minimum at the level provided prior to construction start and minimizing down time as much as possible.

In cases, where major alteration to the existing roadway begins in the areas where the existing ITS devices and underground communication will be impacted at the initial construction phase, the CONSULTANT shall include the permanent ITS and communication and electrical power work to be constructed in the early phase and stage of the construction to activate the devices. The notes referencing the MOC plan details shall be included in the TTCP plans alerting the CONTRACTOR and emphasizing the importance of keeping the ITS devices operational. Subsequently, the CONSULTANT shall attend the utility design and pre-construction meeting conveying the importance of the MOC and operability of the overall system. The CONSULTANT shall include the MOC plan sheets in the beginning of the ITS plans.

The CONSULTANT is responsible for the design of the communication infrastructure and its integration with the DEPARTMENT's communication system. Additionally, the CONSULTANT shall determine the most cost effective, best performing, communication connectivity option. The communication system must allow command and control as well as data and video transmission between the field devices and the TMC(s) at [Location] and when applicable master communication hub(s) at [Location].

Conduit paths shall be selected to provide a continuous duct system on one side of the road unless otherwise requested by the DEPARTMENT. The various components of ITS sites will be located on both sides of the freeway and therefore under pavement bore and lateral conduits will be necessary to access equipment locations. The CONSULTANT is responsible to locate the ITS sites so they are accessible by maintenance vans.

34.7 Fiber Optic Splice Diagrams

The CONSULTANT shall produce fiber optic cable splicing diagrams to show the connectivity of the fiber optic cable from its termini at field devices to the TMC. The

diagrams shall denote new and existing fiber routes, splices, and terminations involved in the work. The diagrams shall identify cables by size, tube color / number and stand colors / numbers. All cables shall be identified either by numbering system identified either by numbering system identified on the plans or by bounding devices. The diagrams shall denote the types of connectors in the patch panels.

The CONSULTANT shall determine physical connection points and methods between the existing project limits to make the desired physical connection. The CONSULTANT shall determine and identify the Buffer Tube/Fiber and Ring allocation to maintain acceptable maximum number of the local intersection per ring before redundant ring to a master communication hub and manage the transmission bandwidth. The CONSULTANT shall analyze existing and proposed fiber optic communication infrastructure for physical and logical connectivity into existing infrastructure.

34.8 Grounding and Lightning Protection Plans

The CONSULTANT shall include efforts to design a complete and reliable lightning protection design for each pole and associated devices, ITS device installation, as well as device cabinets and communications hubs, etc. if not already addressed in the FDOT's Standard Plans for Design, Construction, Maintenance and Utility Operations on the State Highway System. Where the ITS site is located on viaducts and bridges, the CONSULTANT shall provide the grounding and lightning protection details in the plans and show the work that is integral to the elevated superstructure and substructure.

34.9 Cross Sections

The CONSULTANT shall prepare cross sections for all ITS devices and support structures including the ground mounted cabinets or local hubs. The cross section shall include the underground and overhead utilities with utility relocation provisions.

34.10 Guide Sign Work Sheets

The CONSULTANT shall prepare the guide sign work sheets to include all necessary information related to the design of the static and DMS, Embedded DMS, and DTBS in the project corridor.

34.11 Special Service Point Details

The CONSULTANT shall design any special service point and electrical distribution system beyond the electric utility company's service point. The plan shall depict with pay items, general and plan notes the locations of transformers, switches, disconnects, conduits, pull boxes and power conductors. The plans shall identify the location of underground and overhead service points with identifying pole and transformer numbers. The CONSULTANT shall prepare the plan sheets depicting the electrical riser diagram and the line diagram for each location.

34.12 Strain Pole Schedule

The CONSULTANT shall incorporate the schedule detail chart for concrete or steel strain poles in the plan set. The strain pole schedule details shall include stations, offsets, the

ground elevations, proposed elevations, top of foundation elevation, all attachment tie-in heights, pole length, and embedment length.

34.13 Overhead / Cantilever Sign Structure

The CONSULTANT shall be responsible for preparing the civil and structural plans of the overhead/cantilever structures, for proper installation of the DMS on the horizontal truss, viewing angle and decision site distance as per Chapter 2e - Guide Signs-Freeways and Expressways in the Manual on Uniform Traffic Control Devices (MUTCD) and Florida Department of Transportation FDOT Design Manual (FDM) and all other applicable manuals and guidelines as per governing regulations.

The details shall include stations, offsets, the existing ground elevations, proposed elevations, top of drilled shaft foundation elevation, all attachment tie-in heights, upright length, and drilled shaft embedment length. The CONSULTANT shall coordinate the design with the roadway, structural, and MSE wall disciplines and cross reference the critical information on the respective plans for installation, routing of conduits for electrical power and communication inside the substructure and superstructure, and parapets and pilasters. In segments where concrete median barrier walls are proposed, The CONSULTANT shall coordinate the design with the roadway, drainage, and structural disciplines to design the drilled shafts integral to the barrier walls and minimizing the shoulder width reduction.

34.14 Other Overhead Sign Structures (Long Span, Monotube, etc.)

The CONSULTANT shall be responsible for preparing the civil and structural plans when determining the requirements for other type of structures (long span, monotube, etc) used as part of the project for proper installation of the DMS, viewing angle and decision sight distance requirement as per AASHTO Green Book, Chapter 2e - Guide Signs-Freeways and Expressways in the Manual on Uniform Traffic Control Devices (MUTCD) and Florida Department of Transportation FDOT Design Manual (FDM) and all other applicable manuals and guidelines as per governing regulations.

The details shall include stations, offsets, the existing ground elevations, proposed elevations, top of drilled shaft foundation elevation, all attachment tie-in heights, upright length, and drilled shaft diameter and embedment length. The CONSULTANT shall coordinate the design with the roadway, drainage, structural, and MSE wall disciplines and cross reference the critical information in the respective plans for installation, routing of conduits for electrical power and communication inside the substructure and superstructure, bridge deck, and parapets with pilasters.

34.15 Temporary Traffic Control Plans

The CONSULTANT shall prepare Temporary Traffic Control Plans (TTCP) to minimize impact to traffic during the construction of ITS field devices and associated communications infrastructure that will be deployed along the project corridor.

The TTCP shall strive to maintain and sustain center-to-field device connectivity and operability to the ITS field devices previously deployed along the project corridor. The

TTCP effort shall consider and mitigate the impacts of the project's various construction phases so as to sustain center-to-field devices connectivity and operability, maintaining operational quality as a minimum at the level provided prior to construction start and minimizing down time as much as possible. The CONSULTANT shall develop the TTCP sheets for the project, providing temporary communications as necessary, notes, details, and direction applicable to the ITS elements and associated communications for inclusion in the TTCP.

The CONSULTANT shall review the existing TMC Operations and develop additional incident management service requirements as necessary to support during the Construction Phase of the Project. The CONSULTANT shall coordinate with District's Traffic Operations ITS Office for additional information regarding existing Incident Management and TMC Operational Procedures.

34.16 Interim Standards

The CONSULTANT shall adhere to all Department's Interim Standards for ITS applications.

34.17 GIS Data and Asset Management Requirements

The CONSULTANT is responsible for providing Geographic Information System (GIS), spatial data, for the ITS components design. This information is required to integrate ITS components to the SunGuide software. A coordinate point compatible with the Florida State Plane System or FDOT's current coordinate plane system shall be collected for all ITS components part of the Project design. All GIS information provided shall be compatible with the FDOT's ITS FM asset management software.

The information shall be transferred to the as-built plans and submitted to the District in electronic format along with the as-built plans.

The Global Positioning System (GPS) unit shall be provided by the CONSULTANT and used to collect data with a minimum accuracy of three (3) meters when differentially corrected. The CONSULTANT shall collect spatial data points and physical address location for:

- DMS, Embedded DMS, ADMS, DTBS location (mainline and arterial)
- Vehicle detection pole location
- CCTV camera pole location
- WWVDS sites
- Ramp Signal system sites
- RWIS locations
- RSU sites
- Ground mounted cabinets
- Fiber optic cable path (fiber backbone)
- Communications hubs
- Standard route markers
- Lateral fiber optic cable connections
- Lateral power cable connections

- Pull boxes (power and fiber)
- Splice boxes
- Power drops (service point and cable path)
- Power station site equipment (Generator, Power Distribution, ITS Cabinet, Pad Mounted Transformers, power service pole)

34.18 Quality Assurance / Quality Control

The CONSULTANT shall utilize the District's quality control checklist for traffic design drawings in addition to the QC effort described in section three.

34.19 Supervision

The CONSULTANT shall supervise all technical design activities.

35 GEOTECHNICAL (N/A)

N/A

36 3D MODELING

The CONSULTANT shall analyze and document Roadway Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

The CONSULTANT shall deliver all master design files, 3D surface design models, and all supporting digital files for the development of plans as required in the FDOT CADD Manual.

The CONSULTANT shall prepare a 3D model using the latest FDOT software in accordance with the FDOT CADD Manual. Includes all efforts required for developing files for 3D deliverables supporting automated machine guidance for design models. This includes importing survey data and creation of existing 3D surface features and models, and developing proposed corridor models with necessary detail of features to depict the proposed project in 3D to comply with the FDOT CADD Manual.

The CONSULTANT shall add detail to the corridor and design model for 3D design. Includes many elements that contribute to this including but not limited to slope transitions, typical section transitions, changes in pavement depth, berms, swales/ditches, and other feature transitions. Extra corridor structure leads to extra assemblies, extra targeting, etc.

The CONSULTANT shall create an accurate roadway design model which includes modeling the intersections.

The CONSULTANT shall submit .dgn files associated with the 3D Model and their respective components.

36.1 Phase I 3D Design Model

The CONSULTANT shall prepare, submit and present for review by the DEPARTMENT, Phase I 3D interactive model, comprised of, but not limited to: Existing features (pavement,

shoulders, sidewalk, curb/gutter, utilities-if required per scope, drainage - if required per scope) and proposed corridor(s).

36.2 Phase II 3D Design Model

The CONSULTANT shall prepare, submit and present for review by the DEPARTMENT, Phase II 3D model, comprised of, but not limited to: Modification of the Phase I model to update the model to comply with changes based on the Phase I review comments and to include the addition of ponds, floodplain compensation sites, retaining walls, barrier walls, guardrail terminals, cross overs, gore areas, side street connections, roundabouts, and driveways.

[List optional services to be included, e.g. 3D deliverables files for review, Curb Ramps, Closed Drainage Network, Bridge Modeling, Bridge Abutment, Overhead sign post/structures with foundation, Toll gantry and overhead DMS structures with foundation, proposed utilities (pressure pipe/gravity), etc.]

36.3 Phase III 3D Design Model

The CONSULTANT shall prepare, submit and present for review by the DEPARTMENT, Phase III 3D model and 3D deliverables files for review, comprised of, but not limited to: Modification of the Phase II model to update the model to comply with changes based on the Phase II review comments and to further refine areas of transition between templates, detailed grading areas, bridge approaches and end bents, median noses, shoulder transition areas, retaining walls, barrier walls and guardrail.

36.4 Final 3D Model Design

The CONSULTANT shall prepare for review by DEPARTMENT, the Phase IV 3D model and deliverables, comprised of, but not limited to: Modification of the Phase III model to update the model to comply with changes based on the phase III review comments and to accurately generate, export and otherwise prepare the final 3D deliverable files as described in the FDOT CADD Manual.

36.5 Cross Section Design Files

The CONSULTANT shall establish and develop cross section design files in accordance with the FDOT CADD manual and FDOT Design Manual. Includes all work required to establish and utilize intelligent/automated methods for creating cross sections including determining the locations for which all cross sections will be shown, existing and proposed features, cross section refinement, placement of utilities and drainage, soil boxes, R/W lines, earthwork calculations, and other required labeling.

36.6 Template and Assembly Development (Optional)

The CONSULTANT shall prepare for approval by DEPARTMENT, project specific templates/assemblies needed to develop the features required to deliver the 3D model.

36.7 Quality Assurance/Quality Control

36.8 Supervision

36.9 Coordination

37 PROJECT REQUIREMENTS

37.1 Liaison Office

The DEPARTMENT and the CONSULTANT will designate a Liaison Office and a Project Manager who shall be the representative of their respective organizations for the Project. While it is expected the CONSULTANT shall seek and receive advice from various state, regional, and local agencies, the final direction on all matters of this project remain with the DEPARTMENT Project Manager.

37.2 Key Personnel

The CONSULTANT's work shall be performed and directed by the key personnel identified in the proposal presentations by the CONSULTANT. Any changes in the indicated personnel shall be subject to review and approval by DEPARTMENT.

37.3 Progress Reporting

The CONSULTANT shall meet with the DEPARTMENT as required and shall provide a written monthly progress report with approved schedule, schedule status, and payout curve or by using the earned value method that describe the work performed on each task. The report will include assessing project risk through monthly documentation of identifying and updating the risk category and approach for monitoring those tasks. Invoices shall be submitted after the DEPARTMENT approves the monthly progress report and the payout curve or with earned value analysis. The Project Manager will make judgment on whether work of sufficient quality and quantity has been accomplished by comparing the reported percent complete against actual work accomplished.

37.4 Correspondence

Copies of all written correspondence between the CONSULTANT and any party pertaining specifically to this contract shall be provided to the DEPARTMENT for their records within one (1) week of the receipt or mailing of said correspondence.

37.5 Professional Endorsement

The CONSULTANT shall have a Licensed Professional Engineer in the State of Florida sign and seal all reports, documents, Technical Special Provisions and Modified Special Provisions, and plans as required by DEPARTMENT standards.

37.6 Computer Automation

The project will be developed utilizing Computer Aided Drafting and Design (CADD) systems. The DEPARTMENT makes available software to help assure quality and

conformance with policy and procedures regarding CADD. It is the responsibility of the CONSULTANT to meet the requirements in the FDOT CADD Manual. The CONSULTANT shall submit final documents and files as described therein.

37.7 Coordination with Other Consultants

The CONSULTANT is to coordinate his work with any and all adjacent and integral consultants so as to effect complete and homogenous plans and specifications for the project(s) described herein.

37.8 Optional Services

At the DEPARTMENT's option, the CONSULTANT may be requested to provide optional services. The fee for these services shall be negotiated in accordance with the terms detailed in Exhibit B, Method of Compensation, for a fair, competitive and reasonable cost, considering the scope and complexity of the project(s). Additional services may be authorized by Letter of Authorization or supplemental amendment in accordance with paragraph 2.00 of the Standard Consultant Agreement. The additional services may include Construction Assistance, Review of Shop Drawings, Final Bridge Load Rating, update (Category II) bridge plans electronically (CADD) for the Final "As-Built" conditions, based on documents provided by the DEPARTMENT (CADD Services Only) or other Services as required.

38 INVOICING LIMITS

Payment for the work accomplished shall be in accordance with Method of Compensation of this contract. Invoices shall be submitted to the DEPARTMENT, in a format prescribed by the DEPARTMENT. The DEPARTMENT Project Manager and the CONSULTANT shall monitor the cumulative invoiced billings to ensure the reasonableness of the billings compared to the project schedule and the work accomplished and accepted by the DEPARTMENT.

The CONSULTANT shall provide a list of key events and the associated total percentage of work considered to be complete at each event. This list shall be used to control invoicing. Payments will not be made that exceed the percentage of work for any event until those events have actually occurred and the results are acceptable to the DEPARTMENT.